
 <p>MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.</p>	<p>OFFICE OF THE EXECUTIVE ENGINEER EHV PROJECTS DIVISION-III, SOLAPUR CIN. NO. U40109MH2005SGC153646 M.S.E.T.Co. Ltd, 132 kV, Navives S/Stn. Premises Old mill Compound, Solapur-413001 E-Mail: ee6630@mahatransco.in Phone No. (0217) 2320181</p>	
---	--	--

No. EE/EHV/PD-III/Solapur/471

Date: 22/04/2025

E-ENQUIRY

Sub:- E-enquiry for HT & LT line shifting at Gat no. 355, Near Tuljapur road at Village Barshi, Tal. Barshi, Dist. Solapur for 132kV Barshi TSS.

Sealed and superscripted quotations are invited for the work as detailed below with subject to following terms & conditions.

TERMS & CONDITIONS:

- 1) The rate should be quoted on firm quotations basis.
- 2) The rate should be provided as per schedule A format as enclosed with clear bifurcations of taxes.
- 3) The Total work amount should be limited to Rs.**2.40** Lakhs Rupees only.
- 4) Your sealed quotations should reach this office on or before up to **Dt.- 28/04/2025.**
- 5) Quotation shall be sent under sealed cover duly subscribed as our Enquiry No & Quotation for **"E-enquiry for HT & LT line shifting at Gat no. 355, Near Tuljapur road at Village Barshi, Tal. Barshi, Dist. Solapur for 132kV Barshi TSS"** in block letters.
- 6) Service provider has to submit Certificate of Experience for the execution of similar work in Govt. Organization as well as private sector duly signed by the officer not below the rank of Executive Engineer or equivalent in case of Govt. works or from authorized authority of Private sector along with copies of work orders mentioned in the certificate for private sector work.
- 7) The offer shall be valid for acceptance for the period of **3** months from the date of submission.
- 8) The entire work as per the scope in schedule "A & B" is to be completed within a period of 30 days from the date of handing over of the clear site for work.
- 9) All the documents i.e. PAN card, GST registration, ITR- Balance sheet & GST return for last financial years etc. and other accompanying documents like Shop Act, Electrical Contractor License & labor license shall bear the authorized signature of agency, failing which the offer will be liable for rejection.
- 10) The material shall be guaranteed for a period of **One year (01 Year)** from the date of commissioning. If any defect is observed during guarantee period the same will have to be replaced / attended free of cost or as specified by manufacturer whichever is higher.

- 11) If contractor fails to execute the order, it will be treated as breach of contract & contract will be terminated & order will be cancelled by forfeiting the EMD/Security Deposit.
- 12) The material supplied for this work must be in line with MSEDCL/MSETCL specifications & its inspection should be arranged by you before fixing it on site.
- 13) Permission from Electrical Inspector should be arranged from your end.
- 14) If any ROW arises contractor should resolve the same. MSETCL will be provide necessary technical co-operation as per MSETCL term & conditions.
- 15) Engineer in charge: The Additional Executive Engineer, EHV S/Stn Projects Subdivision Pandharpur shall be the Engineer-in-charge for execution of this work.
- 16) Material Inspection: The undersigned or our authorized representative will be free to visit the contractor site stores and also verify the materials in custody of the contractor as and when required at any time.
- 17) Manpower and T & P: All the instruments, T&P, vehicles, labors etc. required for this work shall be arranged by agency. No T&P or labour will be provided by the MSETCL.
- 18) Accident & loss: If any accident is occurred to your staff during the execution of work, the whole responsibility lies on you. Also if any loss is occurred during the work to the MSEDCL/MSETCL's property, the whole cost of equipments will be recovered from your bills or anywhere pending with MSETCL.
- 19) Contractor's Employees: Contractor should employ & provide only such employees who are skilled & experienced for execution & supervision of such type of works.
- 20) Jurisdiction of court: In case of dispute if any, legal jurisdiction of the Court shall be in Solapur only.
- 21) The undersigned has reserved the right to modify or cancel the order at any stage without assigning any reason thereof and without any liability on MSETCL.

Thanking You,

Sd/-
(Mr. S.F. Deshmukh)
Executive Engineer
EHV Proj. Div-III, Solapur

Encl:- Schedule A & B

Copy s.w.rs.to:-

1) The Superintending Engineer, EHV Projects Circle, Pune

Copy to

1) The Manager (F&A), Proj. Div-III, Solapur

2) The Addl. Executive Engineer EHV S/Stn Proj. S/Dn, Solapur.

**E-enquiry for HT & LT line shifting at Gat no. 355, Near Tuljapur road at Village
Barshi, Tal. Barshi, Dist. Solapur for 132kV Barshi TSS**

Schedule A (LT line shifting)

Sr. No.	Description of Material (DTC)	Unit	Qty	Ex- Work Rate / Unit (Rs)	18% GST Amount (Rs)/ Unit	Total Amount Rs.
	LT line					
1	PSC Pole 8 mtr (200 kg)	No.	6			
2	55 mm ² AAAC Conductor	Rmt	1080			
3	ACSR Weasel Conductor	Rmt	360			
4	M.S. Flats 50 X 6 mm	Kg.	24			
5	LT Shackle insulator	No.	21			
6	Aluminium bobbins for neutral	No.	7			
7	LT Shackle hardware	Pair	21			
8	Jointing sleeves for AAAC	No.	2			
9	PG Clamp	No.	0			
10	Earthing Sets L.T	Set	2			
11	L.T.Stay Set	Set	4			
12	G.I.Stay Wire 7/3.15mm(10 SWG)	Kg.	40			
13	Stay Insulators	No.	4			
14	Binding wire	Kg.	0			
15	Binding tape	No.	0			
16	G.I.Wire 8 SWG/ 6 SWG	Kg.	40			
17	L.T.Spacers 4 wire LT line	No.	24			
18	Sundries such as N/B, washers, welding, etc.	LS	2			
1	Concreting ration 1:3:6	Cmt.	2			
	Total amount of Supply + Erection (Incl. all taxes)					
a	Total amount (Supply) Rs.					
b	Erection charges (Labour) 15% on total of ex work					
c	18% GST on Sr. no b					
d	Total amount of Supply + Erection (sr. no a+b+c)					
e	Total Amount (Incl. all taxes)					

Sd/-
Executive Engineer
EHV Projects Div-III, Solapur

E-enquiry for HT & LT line shifting at Gat no. 355, Near Tuljapur road at Village Barshi, Tal. Barshi, Dist. Solapur for 132kV Barshi TSS

Schedule B (HT line shifting)

Sr. No.	Description of Material (DTC)	Unit	Qty	Ex- Work Rate / Unit (Rs)	18% GST Amount (Rs)/ Unit	Total Amount Rs.
	11 kV Mill Feeder					
1	RSJ 116x100, 11 m long	No.	1			
2	RSJ 116x100, 9 m long	No.	1			
3	11 kv guarding channel MS 75x40	Kg.	21			
4	M.S.Channel 75x40x6 mm	Kg.	49			
5	MS angle 50x50x6 mm	Kg.	29			
6	M.S. Flats(50 X 10mm)	Kg.	8			
7	Sleeve joints	No.	1			
8	11 KV V cross arm with clamp	No.	1			
9	11 KV Top fitting with clamp	No.	1			
10	11 kV Pin Insulators with G.I. Pins	No.	9			
11	Disc Insulator 11 KV 70 KN	No.	12			
12	Strain Hardware for 55 Sq.mm AAAC	Set	12			
13	55 mm ² AAAC Conductor	Rmt	360			
14	H.T.Stay Set	Set	2			
15	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	20			
16	Earthing Sets H.T	Set	2			
17	G.I.Barbed Wire 'A' type.	Kg.	6			
18	G.I.Wire 8 SWG/ 6 SWG	Kg.	20			
19	Danger Board in yard.	No.	2			
20	G.I.Nut Bolts	Kg.	2			
21	Black Bituminus Paint	Ltr.	2			
22	Red Oxide Paint for 2 coats	Ltr.	4			
23	Aluminium Paint for 1 coat	Ltr.	2			
24	Sundries	LS	1			
	Erection					
1	Concreting ration 1:3:6	Cmt.	2			
	Total amount of Supply + Erection (Incl. all taxes)					
a	Total amount (Supply) Rs.					
b	Erection charges (Labour) 15% on total of ex work					
c	18% GST on Sr. no b					
d	Total amount of Supply + Erection (sr. no a+b+c)					
e	Total Amount (Incl. all taxes)					

Sd/-
Executive Engineer
EHV Projects Div-III, Solapur