


CIN NO. U40109MH2005SGC153646

 MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.	<p>MAHARASHTRA STATE ELCECTICITY TRSNSMISSION CO LTD 400 KV R.S.O&M Division, Lonikand-I SambhajiNagar At Post LonikandTal ,Haveli Dist Pune-412 216 Phone No-7447440591(CR)</p> <hr/> <p>email id ee6130@mahatransco.in/elonikand400kv@gmail.com</p>	
--	---	---

Ref-EE/400 KV /R.S.O&M /Dn/Lonikand-I/Tech/ 518

Date:- 11.08.2025

TO WHOM SO EVER IT MAY CONCERN

This office intends to prepare the estimate for the Work of Air Conditioning Plant replacement work at 400kV R S Lonikand-1., accordingly Calling budgetary offer& the details are as follows:

Sr No.	Particular	Unit	Ex-works (Rate in Rs.)	GST @ 18%	Unit rate incl. GST (Rs.)
A.	Supply Part				
1	AHU Air Conditioning Plant (Plant Air Handelling Units 22000 CFM at 100MM strict pressure recirculated type double skin air handelling units for calssified areas double skin AHU in thermal breakprofile complete with mixing chamber section fan section filter section return airplenum with Al. Aerofoil type volume control damper for return air damper withdouble HDPE insect mesh 20 Micron filter DIDW backward curved air blower Nicotra6 ROW deep cooling coil 2 Nos alternative return Air Filter 10Micron filter size610x610x300 mm velocity across microm filter 10 & 5 up to 500 FPM service window supply air volume control damper weather proof light with limit switch non FLP motor for blower pressure dip guage for measuring filter)	No			
2	Air cooled condensing unit compressor condenser interconnecting , Piping, Refrigerant Gas ,Expansion Valves hand shut off volve Insulation & Installation of 11TR. ODU Make- BluStar/ Hitachi/ Voltas, etc...	No			
3	Refrigerant piping of Hard copper with insulation alongwith heart proof & sound proof wall paneling work andalluminium partition work	Mtr			
4	Controls for refrigeration system include expansion valvesfilter drier & refrigerant control valves, isolation valve etc.	No			
5	Refrigerant Gas R-22	Kg			
6	MS stand for condensing unit & AHU Units	No			
7	Electrical Control panel with RYB indication suitable capacity of SFU /MCCB with Digital KWH Meter volts & AMP meter fully auto contol panel all types of indication like LP/HP/AHU OFF/ON and Tripping system of over load	No			

B	Service Part				
1	Dismantling of old AC Plant	Job			
2	Modification of old ducting & replacement canvas cushion 22 Guage	Sq ft			
3	10 sqmm 4 core flexible copper cable ODU to control panel & panel to air handling units	Mtr			
4	Labour Charges, Testing & Commissioning of Centralized AC Plant	Job			

* The quoted rates must be valid for 180 days (minimum).

* Ex Works Rates must be including all taxes & charges except GST.

All interested bidders are requested to submit their best offer along with valid documents of PAN, GST, Shop Act /NOC of Gram Panchayat, Experience certificate for **similar work** under MSETCL or any other Govt. or Private sector. The offer send on E-mail id:- **ee6130@mahatransco.in** on or before **16.08.2025**.

This budgetary offer is invited only for estimation purpose and same will not be considered for any bidding or other activity& no work order will be issued based on this offer. Before submitting budgetary offer,agency may contact the concern or agency representative can visit the site location for detailed information.

Contact Person :-

1) R. V. Amberwadikar, Executive Engineer -7447440507

2) N. S. Paraskar, Add. Executive EngineerMaintenance -7447440714

Sd/-
R.V.Amberwadikar
Executive Engineer
400 KV R.S. O&M Dn.Lonikand-I

