

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.**  
**INTRA OFFICE COMMUNICATION**

<b>Name of Office</b>	: Executive Engineer, EHV Projects Division, Kolhapur
<b>Office address</b>	: Vidyut Bhavan, Admm. Building, 2nd Floor, Tarabai Park, Kolhapur.
<b>Contact No.</b>	: 0231- 2665320 (P), 0231- 2655937 (O)
<b>E-Mail</b>	: ee3610@mahatransco.in

**Ref. :** EE/EHV Projects/Dn./Kop/E-Enquiry/No.

**000718**

**Date : 18 AUG 2025**

**Sub :** E-Enquiry for the budgetary offer for balance erection work of 132kV Niwali  
- Ratnagiri line under EHV Projects Division, Kolhapur.

Dear Sir,

The sealed & subscribed quotations are invited for the budgetary offer for balance erection work of 132kV Niwali - Ratnagiri line under EHV Projects Division, Kolhapur as per the Schedule 'A' attached herewith subject to following terms & conditions.

**TERMS AND CONDITIONS :**

- 1) The quotations should reach to this office on or before **25.08.2025 upto 18.00 Hrs.** This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- 2) The contractor has to furnish GST, PAN No. in the offer.
- 3) **The rates quoted by the bidder, shall be considered as inclusive of GST & all other duties, taxes other levies LW Cess, IT etc. which are payable by the contractor as per statutory regulations.**
- 4) Income tax shall be deducted from the bills at prevailing rates, as per Income Tax Act 1961.
- 5) Bids shall remain valid for 120 days after the date of bid opening prescribed by the employer.
- 6) **Security Deposit :** Within Fifteen (15) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 10% of the contract value by RTGS.
- 7) **Period :** The time period for completion of the item under Schedule 'A' under this contract will be **120 days**. The period shall be entitled from date of intimation from MSETCL.
- 8) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.
- 9) **Warantee/ Guarantee :** 2 Years from date of final from the date of final acceptance of the work by the owner. Final acceptance means the MSETCL's written acceptance of the works performed after successful testing & commissioning of the project.

- 10) **Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer after scrutiny of bills at concerned Sub-Division Office.**
- 11) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 12) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost.
- 13) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 14) The contractor shall not sub-let the works awarded on him under this contract.
- 15) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 16) Quotation incomplete in any respect shall be rejected.
- 17) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 18) Quotation received late or with incomplete details against above clauses will not be considered.
- 19) Labour welfare cess/ GST/other statutory payment etc. considered in contract value will be deducted at appropriate rate prevailing during tenure of contract.
- 20) Certificate for successful completion of same type of work is required,

Thanking You.

Yours faithfully,

*Uphosale*  
**Executive Engineer,  
EHV Projects Dn. Kolhapur.**

**Encl. :** Schedule A.

**Copy s.w.rs. to :**

The Suptd. Engineer, EHV Projects Circle, Kolhapur.

**Copy to :**

- 1) The Addl. Executive Engineer, EHV Lines Proj. S/Dn. Kolhapur..
- 3) The Manager (F&A), EHV Projects Dn. Kolhapur.
- 4) Notice Board.
- 5) MSETCL, Website.

M/F.



# EHV PROJECTS DIVISION, KOLHAPUR

## “SCHEDULE - A”

**Name of Line: - Balance work of 132kV Niwali Phata to Ratnagiri line.**

### Erection Portion

Sr. No.	Particulars (Erection Portion)	Unit	Quantity	Location No.
1	Cut point work at existing locations with 0.2 ACSR conductor including shifting of conductor on newly erected DC towers in suspension. <b>(Total Locations 12)</b>	Nos.	35	Loc. No. 221, 224, 225, 228, 231, 234, 235, 241A, 242, 244, 244A, 245
2	Stringing of conductors on S/C, D/C, M/C, H/Z towers including transportation of conductor and required material from site store to site locations, laying, paving, jointing, rough sagging, final sagging, clipping, fixing of accessories, hoisting of insulators, jumpering etc. on tower complete in all respect including tree cutting if required as per the direction of Engineer incharge. (which includes the works involved in the crossing of LT, HT and EHV power lines, railway and river crossing). (viz dismantling and restringing of conductors)			
A	132kV S/C (with 0.2 ACSR) on DC line (With tensioner & puller arrangement)	Km	3.476	Loc. No. 221 to 224 & 225 to 235
B	132kV S/C (with 0.2 ACSR) on DC line. (NH CROSSING) (With tensioner & puller arrangement)	Km	0.159	Loc. No. 224 to 225
C	132kV D/C (with 0.2 ACSR) on DC line (With tensioner & puller arrangement)	Km	0.230	Loc. No. 241 to 241A
D	132kV S/C (with 0.2 ACSR) on MC line (With tensioner & puller arrangement)	Km	#REF!	Loc. No. 242 to 244 & 244A to 247
E	132kV S/C (with 0.2 ACSR) on MC line. (NH CROSSING) (With tensioner & puller arrangement)	Km	0.214	Loc. No. 244 to 244A
3	Stringing of Earthwire including transportation of earthwire and required material from site store to site locations, laying, fixing hardware, fixing accessories, paving out earth wire, jointing, tensioning, stringing and clamping of 7/3.15 sq. mm high tensile galvanized steel wire etc. (With tensioner & puller arrangement)	Km	9.783	Loc. No. 201 to 212, 214 to 215, 217 to 235, 241 to 247

4	<b>Misc. Works</b>			
A	Dismantling charges for Tower (including loading/unloading & transportation as per the directives & instruction of Engr.In-charge.)	MT	10	As & when necessary removal of cross arm
B	Dismantling of conductor lines including E/W and Stays whenever required.(including Hardwares, insulators, conductor & earthwire & its loading/unloading & transportation as per the directives & instruction of Engr.In-charge.)			
	Providing Back Stay			
	For 132 kV tower	Per Stay	21.00	Loc. No. 221, 224, 225, 228, 231, 234, 241, 241A
	Mobilization of gang (min 15 labours)	per occasion	10.00	As per requirement

Note: 1) Material supply is not included in above work.  
2) Outage constraints may arise during execution.