

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD**  
**(CIN NO- U40109MH2005SGC153646)**

From,  
Executive Engineer  
PAC Division, Kolhapur-416005  
Off-0231-2662668 E-mail: - ee3530@mahatransco.in

MSETCL/EE/PAC/Dn./Kop/T/ No- 265

Date : - 20.08.2025

**Re- Enquiry (Budgetary offer)**

**Sub :-** Re-Enquiry for submission of budgetary offer for Supply, installation, testing & commissioning of Remote terminal units(RTU) at 04No's of substations under EHV PAC Division Kolhapur..

\*\*\*\*\*

Dear Sir,

Budgetary offers are invited by the undersigned for Supply, installation, testing & commissioning of Remote terminal units (RTU) at 04No's of substations under EHV PAC Division Kolhapur **on or before: 28.08.2025 up to 17:00 Hrs.** The other terms and conditions are as mentioned below.

- 1) Quotation should be duly filled in and submitted to this office **via post or e-mail** – **ee3530@mahatransco.in**
- 2) **This enquiry is solely for collection of offer for estimate purpose & not for work allocation.**
- 3) The offer should be submitted as per details mentioned below.
- 4) Quote rate in prescribed format.

Sr. No.	Particulars	Qty. in Nos.	Rate per unit in Rs. (Excl Gst)	Amount in Rs. (Incl Gst)
1	Supply of direct pulling RTU having following specification. Compliance to IEC 61850 & IEC104, Serial Port:- RS232 and RS485 ports , 2 ports each ( RS 232 for IEC 101 Data out & RS 485 for MFM Data IN ) No. of Ethernet port:- RJ45 - 2 Nos. Universal Power supply 24 – 230 V AC / DC. Memory card;- eMMC 4 GB Flash RRAM 512 MB DDR3 SD RAM No. of console ports;- 1, Multi-client reporting.	03		
2	Supply of direct pulling RTU with DI & AI (No of DI 60/No of AI 16) having following specifications. Compliance to IEC 61850 & IEC104, Serial Port:- RS232 and RS485 ports , 2 ports each ( RS 232 for IEC 101 Data out & RS 485 for MFM Data IN ) No. of Ethernet port:- RJ45 - 4 Nos. Universal Power supply 24 – 230 V AC / DC. Memory card;- eMMC 4 GB Flash RRAM 512 MB DDR3 SD RAM No. of console ports;- 1, Multi-client reporting.	01		
3	Installation, configuration testing & commissioning of above Remote terminal units (RTU) at 1) 400 KV Talandage 2) 220 KV Mudshingi 3) 220 KV Tilawani 4) 132 KV Bambwade	04		
	Total including GST			

-sd-

**Executive Engineer**  
**PAC Division Kolhapur.**