



(CIN No. U40109MH2005SGC153646)

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.**  
**INTRA OFFICE COMMUNICATION**

<b>Name of Office</b>	: Executive Engineer, EHV Projects Division, Kolhapur
<b>Office address</b>	: Vidyut Bhavan, Admm. Building, 2nd Floor, Tarabai Park, Kolhapur.
<b>Contact No.</b>	: 0231- 2665320 (P), 0231- 2655937 (O)
<b>E-Mail</b>	: ee3610@mahatransco.in

Ref. : EE/EHV Projects/Dn./Kop/E-Enquiry/No.

No 00841

Date : - 1 OCT 2025

**Sub :** E-Enquiry for balance work of 132kV Jaysingpur - Kurundwad link line under EHV Projects Division, Kolhapur.

Dear Sir,

The sealed & subscribed quotations are invited for the offer for balance work of 132kV Jaysingpur - Kurundwad link line under EHV Projects Division, Kolhapur as per the Schedule 'A' attached herewith subject to following terms & conditions.


**TERMS AND CONDITIONS :**

- 1) The quotations should reach to this office on or before **09.10.2025 upto 18.00 Hrs.** This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- 2) The contractor has to furnish GST, PAN No. in the offer.
- 3) The bidder should have an experience in execution of similar work.
- 4) the bidder should possess the valid Electrical Contractor License.
- 5) **The rates quoted by the bidder, shall be inclusive of GST & all other duties, taxes, levies, LW Cess etc. which are payable by the contractor as per statutory regulations.**
- 6) Income tax & Labour welfare cess shall be deducted from the bills at prevailing rates, as per Income Tax Act 1961.
- 7) The estimated amount of subject work is Rs. 6,73,259.93 (Including GST)
- 8) Bids shall remain valid for 60 days after the date of bid opening prescribed by the employer.
- 9) **Security Deposit :** Within Seven (7) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 10% of the contract value by RTGS.
- 10) **Period :** The time period for completion of the item under Schedule 'A' under this contract will be **45 days.** The period shall be entitled from date of handing over of site by MSETCL.
- 11) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.
- 12) **Warantee/ Guarantee :** 1 Years from date of final acceptance of the work by the owner.
- 13) Quantity mentioned in the Schedule 'A' may vary as per actual site requirement, during execution.

- 14) Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer in charge after scrutiny of bills at concerned Sub-Division Office.
- 15) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 16) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost. Material viz. cross arm, earthwire, conductor, hardware, insulators etc required for subject work shall be provided by MSETCL.
- 17) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 18) The contractor shall not sub-let the works awarded on him under this contract.
- 19) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 20) Quotation incomplete in any respect shall be rejected.
- 21) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 22) Quotation received late or with incomplete details against above clauses will not be considered.

Thanking You.

Yours faithfully,

  
**Executive Engineer,  
EHV Projects Dn. Kolhapur.**

**Encl. :** Schedule A.

**Copy s.w.rs. to :**

The Suptd. Engineer, EHV Projects Circle, Kolhapur.

**Copy to :**

- 1) The Addl. Executive Engineer, EHV Lines Proj. S/Dn. I&II Kolhapur. - All the material required for balance work shall be kept ready in MSETCL's custody.
- 3) The Manager (F&A), EHV Projects Dn. Kolhapur.
- 4) Notice Board.
- 5) MSETCL, Website.

M/F.



## EHV PROJECTS DIVISION, KOLHAPUR

### “SCHEDULE - A”


**Name of Line: - Balance work of 132kV Jaysingpur to Kurundwad link line.**

Sr. No.	Particulars	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Stringing of conductors on S/C, D/C, M/C,H/Z towers including transportation of conductor and required material from site store to site locations, laying, paving, jointing, rough sagging, final sagging, clipping, fixing of accessories, hoisting of insulators, jumpering etc. on tower complete in all respect including tree cutting if required as per the direction of Engineer incharge. ( which includes the works involved in the crossing of LT,HT and EHV power lines, railway and river crossing). ( viz dismantling and restringing of conductors)				
	132kV D/C (with 0.2 ACSR) on DC line (For Loc. No. 4 to 8 of Miraj-Jaysingpur line)	Km	1.7		
2	Stringing of Earthwire including transportation of earthwire and required material from site store to site locations, laying, fixing hardware, fixing accessories, paving out earth wire, jointing, tensioning, stringing and clamping of 7/3.15 sq. mm high tensile galvanized steel wire etc. (1. For Jaysingpur-Ichalkaranji line -Loc. No. 4 to 5 & Loc. No. 13 to Jaysingpur Gantry. 2. For Miraj - Jaysingpur line - Loc. No. 1 to 8)	Km	3.5		
3	Earthing of towers with Counter Poise Type earthing including excavation of pits / trenches, laying of earthwire & fitting plates of tower legs as per the drawing & back filling, complete in all respect as per directions of Engr. in-charge.	No.	9		
4	Tree cutting (For 2nd Ckt Stringing Miraj-Kurundwad line Span - 22 to 23, 41 to 42, 66 to 67, 70 to 71 & 72 to 73)	Span	5		
5	Hydra services required for stringing work as per requirement	Hrs	72		

Sr. No.	Particulars	Unit	Quantity	Rate in Rs.	Amount in Rs.
5	Complete erection of DC/MC/Horizontal tower (Including special tower) with its extension for EHV Lines(as per requirement) with fixing of bolts & nuts, tightening, punching & fitting including attachment (like step bolts, ladders, platforms, "U" bolts, shackles, hangers, strain plates etc) & including transportation of material from site stores to work sites, tightening & punching of Bolts & Nuts complete in all respect, punching of bolts, fixing of danger plates, fixing of danger plates, fixing of number plates, fixing of phase plate, fixing of anticlimbing device, fixing of circuit plate etc. (Box type cross arm at Loc. No. 7)	MT	3.60		
6	Dismantling charges for Tower (including loading/unloading & transportation as per the directives & instruction of Engr. In-charge) (For Loc. No. 7 upto bottom of cross arm)	MT	3		
7	Dismantling of conductor lines including E/W & stays wherever required. (including Hardwares, insulators, conductor & earthwire & its loading/unloading & transportation as per the directives & instruction of Engr. In-charge) (For Loc. No. 4 to 8 of Miraj -Jaysingpur line)	Km	1.35		
8	132kV Tower back stay (For Loc. No. 4 - 6 Nos. & For Loc. No. 8- 6 Nos.)	Nos.	12		

Note:

- 1) All T&P, Labour, crane etc shall be arranged by the contractor at his own cost..
- 2) Material viz. cross arm, earthwire, conductor, hardware, insulators etc required for subject work shall be provided by MSETCL.
- 3) Quantity mentioned in the Schedule 'A' may vary as per actual site requirement, during execution.



(A. C. Dhamale)

Executive Engineer,  
EHV Projects Division, Kolhapur

Signature of Contractor

Date: