



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD

(CIN No.U40109MH2005SGCI53646)

 MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd	Office of the Executive Engineer PAC-II, Pimpri-Chinchwad Address: Block No.109, Admin Building, Ground Floor, Rasta Peth, Pune 411011 Phone No : 7447440515 E- mail- ee6520@mahatransco.in	
--	---	---

Ref: EE/PAC/Div-II/PC/DYEE(O)/Enquiry-6/2025-26/273

Date : 03.10.2025

ENQUIRY

To,
MSETCL Portal,

Sub: - E-Enquiry for Supply of Ferrule Printing Machine, Digital Multimeters & Digital Clamp Meters required for testing work at various batches under PAC Division-II, Pimpri-Chinchwad.

Sir,

Sealed & super scribed quotations are invited from the reputed experienced/Registered contractor for the work as described in Schedule 'A' & 'B' enclosed herewith. The prescribed forms and documents mentioned in Schedule 'A' and 'B' duly filled in, with the rates written in words & figures & signed, should be sent by registered post or in person to the Executive Engineer, MSETCL, PAC Division-2, Block No. 109, Admin. Bldg. Rasta peth, Pune -11 **on or before up to 16.00 Hrs. dtd. 14.10.2025.**

TERMS AND CONDITIONS:

- 1. Scope Of Work:-** Supply of Ferrule Printing Machine, Digital Multimeters & Digital Clamp Meters required for testing work at various batches under PAC Division-II, Pimpri-Chinchwad. as per Schedule – A & Annexure A enclosed herewith
- 2. Period Of Contract:** The Period of contract will be Two months (60 days) from date of issue of work order.
- 3. Security Deposit:** The successful Bidder shall pay 10 % of the contract value towards security deposit within within 7 days from the date of receipt of LOI in the form of FDR/B.G. of any Nationalized/ scheduled Bank in the favour of “Superintending Engineer, EHV O&M Circle, MSETCL, Pune” valid for one year or online payment NEFT/RTGS. The amount will be refunded in the normal course, after expiry of the contract period subject to deduction, if any, forfeited as per the terms & conditions. As per MSETCL circular no. 2578 dtd 28.07.14, if security deposit is not paid within 7 days, 18% interest will be charged of the work order value. No interest will be allowed on this deposit. If on the breach of contract during contract period S.D. will be forfeited without assigning any reason.
- 4. Rate Validity:** The offer shall be valid for acceptance for a period of 120 days from the last date of submission of quotation.
- 5. Acceptance Of Enquiry:** The Company does not bind itself to accept the lowest or any bid neither will any reason be assigned for the rejection of any bid. It is also not binding on the Company to disclose any analysis report on Enquiry.

6. Discarded To Enquiry Conditions: The Company reserves to itself the right to reject the Enquiry.

7. Work Completion Period:- Supply should be completed within 1 months from the date of issue of work order

8. Sample Approval: *Before finalization of purchase order for supply, Sample should be got approved by Executive Engineer, PAC Division-II, Pimpri-Chinchwad. In case of any deviation from Schedule A specification, material will be rejected and order will be issued to next lowest agency conforming to specifications.*

09. Signing Of Contract: The contractor shall enter into an agreement of Rs. 500/- with the MSETCL within 7 days from the date of receipt of the work order. Until the agreement is executed, the MSETCL will not be liable to pay, nor shall the contractor be entitled to claim amount due or payable under the contract. The necessary stamp duty for the agreement shall be borne by the contractor.

10. Guarantee: - Guarantee of material supplied to MSETCL should be provided for **minimum 12 months**. Any defects developed during guarantee period should be rectified at the cost of contractor.

11. Penalty: If the work is not completed within stipulated period the penalty @ ½% per week as applicable subject to maximum 10% of the order value of work, will be levied. Loss to MSETCL property or equivalent etc. due to your negligence will be penalized & will be recovered from the bill.

12. Failure Of Execution Of Work: Work will have to be executed as per the instruction of Executive Engineer or his representative. For failure to execute the work as per given Schedule "A" against the order in full, within the stipulated period, the Company shall be at liberty, without further notice or reminder to the contractor to get the same work done on account of and at the risk of the contractor and the prefer a claim for the difference in price and for all expense whatsoever incurred in getting the said work done and the same shall be recovered from any payment due to the Contractor from bills or deposit.

13. Submission Of Tax Invoice : The tax invoice should be submitted to the Office of Executive Engineer, PAC Division-II, Pimpri-Chinchwad as per Schedule 'A'. After receipt of tax invoice, payment will be effected accordingly subject to availability of funds.

14. Right of acceptance/rejection: The undersigned reserves the right to accept or reject the order without assigning any reason thereof. The undersigned reserves the right to alter, modify or cancel the above order at any stage if found necessary.

15. Conditions of Contract: All General / Technical / Commercial terms & conditions of the contract of the Company are applicable to this contract & will be binding on you

16. In case of any dispute whatsoever, regarding interpretation of the terms and conditions, or quality, the decision of the Executive Engineer, PAC Division-II, Pimpri-Chinchwad will be final and binding on the contractor.

17. Income Tax : Income Tax will be deducted from the contractor's bill.


18. All other Standard Terms and conditions prescribed by M.S.E.T.C.L., regarding supply and work, which are not stated here, are also applicable to this contract.

19. **Jurisdiction:** All disputes, differences related to the tender contract shall be subject to the exclusive jurisdiction of Pune District Court.

20. **Quality Of Work:** Quality of material supplied should be strictly confirmed to our specification, otherwise it will be rejected and contractor has to redone the same at his cost and risk only.

21. The provision made in various Acts in force applicable to this contract is obligatory on the Contractor while executing the work.



Yours faithfully,



**Executive engineer
PAC Division-2,
Pimpri-Chinchwad**

Copy to:-The Manager, F & A, (EHV O & M) Circle, Pune.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
(CIN No.U40109MH2005SGCI53646)

 MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.	Office of the Executive Engineer PAC-II, Pimpri-Chinchwad Address: Block No.109, Admin Building, Ground Floor, Rasta Peth, Pune 411011 Phone No : 7447440515 E- mail- ee6520@mahatransco.in	
---	---	---

Ref: EE/PAC/Div-II/PC/DYEE(O)/Enquiry-6/2025-26/


Date : 03.10.2025

Subject: - Enquiry for Supply of Ferrule Printing Machine, Digital Multimeters & Digital Clamp meters for PAC Division-2, Pimpri-Chinchwad.

Schedule 'A'

Sr. No.	Particular	Quantity in Nos.	Ex. Rate Per Unit	GST %	Total Amount Including GST
1	Ferrule Printing Machine (<i>Technical Specifications As per Annexure A</i>)	1			
2	Digital Multimeter, True RMS AC Current & Voltage, 10A, 6000 Count, Safety CAT III 1000V, CAT IV 600V, IP67, AC-DC upto 1kV (Standard Make like Fluke, Rishab, Megger or equivalent) (<i>Technical Specifications As per Annexure A</i>)	3			
3	Digital AC Earthleakage Clampmeter (0-100A with 0.001mA resolution, Ranges: 0-6mA, 60mA, 6A, 60A, 100A, TRMS) (Standard Make like Fluke, Rishab, Megger or equivalent) (<i>Technical Specifications As per Annexure A</i>)	3			

Note: 1) Please confirm the specification of quoted instrument as per Schedule A along with make and model of Equipment. Also attach Technical data sheets of the quoted instrument.


Executive Engineer,
PAC Div-2, MSETCL
Pimpri-Chinchwad

Form to be filled by bidder:-

Form for quoting % rate for item included in Schedule 'A'

Estimated Cost :- The estimated cost amounting to Rs. 2,80,815.22 /- including GST & Labour cess.

I, am ready to execute the work to _____% above (In words _____)



Or _____ % below (In words _____) the estimated cost.

Or on **AT PAR** of the estimated cost.

Date :-

Signature of Bidder :-

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
(CIN No.U40109MH2005SGCI53646)

 MAHATRANSCO Maharashtra State Electricity Transmission Co. Ltd.	Office of the Executive Engineer PAC-II, Pimpri-Chinchwad Address: Block No.109, Admin Building, Ground Floor, Rasta Peth, Pune 411011 Phone No : 7447440515 E- mail- ee6520@mahatransco.in	
---	---	---

Ref: EE/PAC/Div-II/PC/DYEE(O)/Enquiry-6/2025-26/

Date : 03.10.2025


SCHEDULE "B"

a) **Work :** Enquiry for Supply of Ferrule Printing Machine, Digital Multimeters & Digital Clamp meters for PAC Division-2, Pimpri-Chinchwad.

b) **Estimated cost :- Rs. 2,80,815.22/-** Including all taxes.



Following documents certificate/ as a proof of qualifying pre-requisites, brochures, attested certificates etc. need to submitted along with the quotation, otherwise the quotation will not be accepted

Sr. No.	Name of document
1	Full name and address of the company/ firm.
2	Permanent address of the contractor/ proprietor of the firm and proof for the same.
3	Proof for valid registration under Shop & Establishment Act 1948 with attested True copy. OR NOC of Gram Panchayat for shop establishment (The NOC should valid for current year).OR Udyog Adhar
4	PAN card copy & (Aadhar) UID Card attested true copy.
5	GST Registration Certificate
6	Authorization letter of OEM


Executive engineer
PAC Div-2, Pimpri-Chinchwad


MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD

(CIN No.U40109MH2005SGCI53646)

 MAHA TRANSCO Maharashtra State Electricity Transmission Co. Ltd.	Office of the Executive Engineer PAC-II, Pimpri-Chinchwad Address: Block No.109, Admin Building, Ground Floor, Rasta Peth, Pune 411011 Phone No : 7447440515 E- mail- ee6520@mahatransco.in	
---	---	---

EE/PAC/Div-II/PC/DYEE(O)/Enquiry-6/2025-26**Date : 03.10.2025****'Annexure A'**

Sr. No.	Items	Technical Specifications
1.	Ferrule Printing Machine	1) Print up to 36mm TZe laminated tapes width and ϕ 2.5 mm - ϕ 6.5 mm PVC Tubes. 2) QWERTY Keyboard, USB and WiFi connection 3) Auto and Half cut function 4) Twin-engine for tube and label 5) Self-replaceable Tube cleaner, cutter and rollers 6) Optional Rechargeable Li-ion battery
2.	Digital Multimeter, (Standard Make like Fluke, Rishab, Megger or equivalent)	True RMS AC Current & Voltage with VFD Measurements 0-10A, 6000 Count, AC & DC Voltages Range: 60.00mV, 600.0mV, 6.000V, 60.00V, 600.0V, 1000V AC & DC Currents Range: 600.0 μ A, 6000 μ A, 60.00 μ A, 600.0 μ A, 6.000 A, 10.00 A AC current & voltage bandwidth: 45 Hz to 1 kHz (Sine); 50/60 Hz (All wave). Safety Rating: IEC 61010-1: Pollution Degree 2, IEC 61010-2-033: CAT IV 600 V, CAT III 1000 V IP67, AC-DC upto 1kV
3.	Digital AC Earthleakage Clampmeter (Standard Make like Fluke, Rishab, Megger or equivalent)	0.001 mA resolution Up to 100 A AC, Ranges 6.000 mA / 60.00 mA / 600.00 mA / 6.000 A / 60.00 A / 100.0 A TRMS 6000 count Low pass filter to aid stability of readings


**Executive Engineer,
PAC Division-2, MSETCL
Pimpri-Chinchwad**