



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office : 400KV RS O&M Dn. Karad.
Office Address : Administrative Building, Ground Floor, Vijaynagar,
Post – Supane, Tal – Karad Dist – Satara, Pin No. 415114
Email ID : ee3130@mahatransco.in
Website : www.mahatransco.in
CIN No. : U40109MH2005SGC153646

EE/400KV/RS/O&M/DN/KRD/T/No. **No 0 0 6 2 3** Date: 03.11.2025.

EXTENSION OF E-ENQUIRY FOR BUDGETARY OFFER

(Through MSETCL web page)

TO WHOM SO EVER IT MAY CONCERN

BUDGETARY OFFER

Please find attached herewith a detail schedule for work of Design, Supply, Installation & Commissioning of Mono Crystalline bi-facial (Non DCR) PV Module 40 KW Rooftop Solar Project at Administrative Building Zone office MSETCL Karad. All interested & experienced bidders are requested to submit their best lowest **budgetary offer** on the Mail ID: ee3130@mahatransco.in or submit physically to this office for the same up to **Dated. 10.11.2025 up to 18:00Hrs.** Taxes should be quoted distinctly if any.

Please note that this budgetary offer is for estimation purpose only.


(C.L. Bharamgunde)
Executive Engineer
400KV RS(O&M)Dn.Karad

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD**400KV RS (O&M) Division, Karad**

(CIN No.- U40109MH2005SGC153646)

SCHEDULE 'A'

Sub - Work of Design, Supply, Installation & Commissioning of Mono Crystalline bi-facial (Non DCR) PV Module 40 kW Rooftop Solar Project at Administrative Building Zone office MSETCL Karad.

Sr. No	Description	Qty.	Unit	Price	GST 12/18 %	GST Amt.	Unit Rate with GST	Total Amt.
1	540 wp Solar Pv Model	75	EA	.	12%			
2	40 Kw 3Ø On-Grid Solar Inverter	1	EA		12%			
3	1.6 mm GI Str wt Pathway-Solar Inverter	2300	KG		18%			
4	3m Cu Bonded Solid Rod Solar Earthing	1	EA		18%			
5	1.1kV PVC 3.5CX70 Al Ar Pwr Cable	35	M		18%			
6	1.1kV PVC 1Cx4mm² M/strand DC Cable	500	M		18%			
7	Module Cleaning System -40 kW Solar	1	Set		18%			
8	Distribution Panel -40 kW Solar Plant	1	Set		18%			
9	Multifunction Digital Energy Meter 40/200 (Gen Meter)	1	EA		18%			
10	Bidirectional Digital Energy Meter 40/200 (ABT-Net Meter)	1	EA		18%			
11	Sundries i.e. Nutbolts ,Washer - HT/LT Line	32	KG		18%			
12	S&I of R/T Solar system	1	AU		18%			
	IC&Liasioning 40 kW R/t Solar System		EA					
Total Amount								

NOTE :-**This budgetary offer is only for estimation purpose.****(C.L.Bharamgunde)****Executive Engineer****400KV RS(O&M)Dn.Karad**