



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**  
(CIN No. U40109MH2005SGC153646)

<b>From : Executive Engineer</b>
<b>Name of Office : EHV Project Division, Sangli</b>
<b>Office address : Office of the Executive Engineer, 2<sup>nd</sup> Admin. Bldg., Vishrambag, Sangli – 416415.</b>
<b>Contact No. 0233 – 2301187, FAX No. 0233 – 2301137, 0233 – 2302997 (P)</b>
<b>Email Id: ee3620@mahatransco.in, Website : www.mahatransco.in</b>

**Ref.: EE/EHV PD/SGL/No.1000**

**Date: 15.07.2017**

**E-enquiry – 11**

To

Sub :- Preliminary & detailed survey of 132 KV lines under  
EHV Projects Division, Sangli.

Sir,

The sealed & subscribed quotations are invited for Preliminary & detailed survey of 132 KV lines under EHV Projects Division, Sangli as per the Schedule 'A' attached herewith subject to following terms & conditions, so as to reach this office on or before **24.07.2017** upto 17:30 hours.

**Terms and Conditions:**

- 1) The quotation shall be sent in sealed cover, clearly superscribed with the words "quotation for Preliminary & detailed survey of 132 KV lines EHV Projects Division, Sangli.
- 2) The quotation should be on designation of the Executive Engineer EHV Projects Dn., Sangli.
- 3) The rates quoted should be including the labour charges and material charges. The bidder shall quote his overall percentage in terms of (+) or (-) percentage or above / below / At par percentage on the overall total estimated cost mentioned in Schedule 'A' by the owner.
- 4) **Mode of Destination** - Preliminary & detailed survey of 132 KV lines under EHV Projects Division, Sangli.
- 5) **Work Period:** The time period for the completion of item under Schedule 'A' under this contract will be 4 months or upto completion of work order value, whichever is later. The work is to be started & completed within work period i.e. 4 months from the date of receipt of firm order / handing over of site, otherwise penalty as per MSETCL's rules will be levied.
- 6) **Rates** : Rates should be firm and inclusive of all taxes.

- 7) **Quantity** : The Quantity mentioned in the Schedule 'A' is tentative and subject to variation on either-wise. However, payment will be made for the work actually done.
- 8) **Payment**: Payment will be released as early as possible against M.B. recording / SAP formalities. No advance payment will be released against work.
- 9) **Xerox Copies** : Please attach the following documents alongwith quotation –
- a) PAN Xerox copy.
  - b) Registration under Bombay Shop & Establishment Act 1948.
  - c) GST Registration / Certificate.
  - d) Experience Certificate for similar work done within 5 years. The experience certificate should be issued by the Ex. Engineer or equivalent or above.
- 10) **Security Deposit** : 5% of the contract value will have to be paid within 15 days from receipt or acceptance of the order.
- 11) **Validity**: Quotation should be kept valid for at least 60 days from due date.
- 12) **Validity**: a) Quotation received late / with incomplete details against above clauses will not be considered. b) Right to reject any or all quotations without assigning any reason (s) there of reserved by the undersigned.
- 13) Contractor itself should aware to all terms and conditions of MSETCL.

Thanking You,

Yours Faithfully,

Encl.: Schedule A.

**-Sd/-**  
**Executive Engineer**  
**EHV Project Dn., Sangli.**

Copy S.w.rs. to –  
The Superintending Engineer EHV PC Kolhapur  
Copy to –  
The Addl. Ex. Engineer S & I S/Dn., Sangli.  
The Manager (F&A) EHV Project Dn., Sangli  
Notice Board

M/f.

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.  
EHV PROJECTS DIVISION, SANGLI**

**SCHEDULE - A**

**Name of Work :-** Preliminary and detailed survey work of 132 KV lines under EHV Projects Division, Sangli.

Sr. No.	Description of work	Unit	QTY. (Approx.)	Ex-works	GST @18% on Ex-works	Labour Cess @ 1% on Ex-works	Rate Rs/Unit	Amount
1	Preliminary survey of above mentioned line by using total station/ theodolite by selecting the route which should be economical, & best suitable for construction point of view by avoiding forest, social forest, irrigation tanks and private/N.A. properties marking the same on toposheet to the scale prescribed by MSETCL and submitting for approval to MSETCL etc. complete	Kms	23	2504.35	450.78	25.04	2980.18	68544.06
2	Detailed survey of the approved route by using a total station/thedolite instruments & as per specifications including taking levels at fixed intervals of 20 mtrs. Cross section levels if required & detailed of Telephone/L.H/H.T. Line/EHV line crossing. Preparing soft copy/field book of the work & submitting the same.	Kms	23	5008.7	901.57	50.09	5960.35	137087.98
3	Preparation of ground profile (L section) on standard scale graph tracing paper showing details & marking the tower spotting on ground profiles by using the approved sag template, tower spotting data & preparation of tower schedule submitting one sag template original profiles route map & two prints of tower schedules, soft copy of the same of each line etc. complete.	Kms	25	834.785	150.26	8.35	993.39	24834.85
4	Providing & fixing concrete pillars of 100 x 100 x 600 mm size including necessary excavation fixing etc. complete as directed by Engineer-in-charge.	Nos.	80	236.52	42.57	2.37	281.46	22516.70
5	Providing & Preparing the list of Survey/Gat No. map of final route passing through each village, town, showing gat No. by separate marking involving forest etc. complete as directed by Engineer-In-Charge.	Kms	23	1113.04	200.35	11.13	1324.52	30463.90
							<b>Total :-</b>	<b>283447.50</b>
							<b>Say Rs.</b>	<b>283448.00</b>

**(Rupees in words: Two Lakh Eighty Three Thousand Four Hundred Forty Eight only)**

**I am ready to execute the above work with :**

----- Equal to estimated cost

----- % Above (in words ----- % above)

----- % Below (in words ----- % below)

**the estimated cost.**

**Note: Offer other than this proforma will not be accepted.**

**Signature of Contractor  
Dated: -**

**-Sd/-  
Executive Engineer  
EHV Projects Division, Sangli**



