

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**(CIN No. U40109MH2005SGC153646)**

From:- Executive Engineer (Civil)
EHV Civil Construction cum Maintenance Division Nashik
"Administrative Building", Block No. 6, 1st floor, Racea Plot, Old Saykheda Road,
Jail Road, Nashik Road-422 101.
Ph No.:-0253-2403102 (O), Fax No.:-0253-2403103
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

Date:-

18 SEP 2017

NO 959 3
e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Providing & laying the vitrified tiles other miscellaneous work of control room at 220 KV OCR Eklahare Sub station, Dist:- Nashik." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Providing & laying the vitrified tiles other miscellaneous work of control room at 220 KV OCR Eklahare Sub station, Dist:- Nashik.

The quotations should reach to this office on or before **27/09/2017** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.
- (a) **Compulsory Primary Documents in 1st Envelop:(Technical Bid)**
 - (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government.
 - (ii) GST/ GSTIN Registration Certificate.
 - (iii) E.P.F. Registration Certificate – issued by competent authority of Govt.
 - (iv) Experience of having successfully completed similar civil works.
 - (v) Payment of **EMD Rs. 2990.00** to be made by bidder off-line only upto 14.00hrs of **27/09/2017** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope
- (b) **Documents in 2nd Envelop:(Price Bid)**
 - i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- 5) Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- 6) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 7) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 8) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 9) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 10) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.

- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



**Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.**

Copy s.w.r.t.-

- 1) The Chief Engineer EHV Projects cum O&M Zone, Nashik.
- 2) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer [Civil] EHV Civil S/Dn.-I, Nasik.
- 2) The Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED
EHV Civil Construction Cum Maint. Division. Nashik.

Name of Work - Providing & laying the vitrified tiles other miscellaneous work of control room at 220 KV OCR
 Eklahare Sub station, Dist:- Nasik

Schedule "B"

Sr No	Description of item	Qty	Unit	Rate	Add GST 18%	Total	Amount
1	Removing cement tiles, or marble or Shahabad or Tandur stones, polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts, complete. Additional Item Spec. No. : As directed by Engineer in charge.	20.00	Sqm	22.00	3.96	25.96	519.20
2	Removing lime or lean cement concrete including stacking the spoils as directed with all leads, lifts, complete. Additional Item Spec. No. : As directed by Engineer in charge.	11.87	Cum	297.00	53.46	350.46	4160.84
3	Removing battens/Angle from roof and stacking them as directed with all leads and lifts etc. complete. Additional Item Spec. No. : As directed by Engineer in charge.	100.00	RMT	4.00	0.72	4.72	472.00
4	Providing and laying in situ, cement concrete M-15 / 1:2:4 of trap / granite / quartzite / gneiss metal for foundation and bedding including bailing-out water manually, formwork, compacting, covering newly laid concrete by gunny bag, plastic or tarpaulin, curing etc. complete. (Wooden planks / shuttering will not be allowed. The shuttering should be of waterproof plywood or tailer made angle and steel plate) Spec. No. : Bd.E.1 Page No. 287 & IS 456:2000	5.00	Cum	4248.00	764.64	5012.64	25063.20
5	Providing and fabricating structural steel work in rolled sections, fixed with connecting plates or angle cleats in main and cross beams, hip and jack rafters, purlins, connecting to truss members and the like, as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted / bolted / welded connections and one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade complete. Spec. No. : Bd.C.3 Page No. 275	0.10	MT	44679.00	8042.22	52721.22	5272.12
6	Providing and laying vitrified matt fininsh tiles of RAK/ Kajaria/ Nitco/ Asian or equivalent make having size 590 mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming S.156222006 (Group Bla) of approved make, shade and patternfor flooring in required position laid on a bed of 1:4 cement morar including neat cement float, filling joints, curing and cleaning etc. complete. a) Flooring	190.00	Sqm	1099.00	197.82	1296.82	246395.80

Sr No	Description of item	Qty	Unit	Rate	Add GST 18%	Total	Amount
7	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing complete. Spec. No. : Bd.L.2 Page No. 368	50.00	Sqm	102.00	18.36	120.36	6018.00
8	Removing matting from roof /flooring and stacking as directed with all leads and lifts etc. complete. Additional Item Spec. No. : As directed by Engineer in charge.	256.00	Sqm	3.00	0.54	3.54	906.24
9	Providing and laying aluminum chequered plates for cable trench cover of thickness 3.15 mm plain plus 0.85 mm Chequered fixed to M.S. angle frame of Size 25x25x3 mm both side diagonal and at border including fabrication, painting to angles in three coats of silver painting revetting and making grooves to the chequered plate for handling etc. complete.	1.00	Sqm	2443.00	439.74	2882.74	2882.74
10	Conveying materials obtained from road cutting including all lifts, laying in layers, breaking clods, dressing to the required lines, curves, grades and section for a lead of over 50m. to 300m. from the site of excavation to the site of deposition as directed. Spec. No.: MORTH 305	17.30	Cum	77.00	13.86	90.86	1571.65
11	Providing Brick masonry in cement mortar 1:6 using Fly Ash bricks in foundations and plinth of inner walls / in plinth of external walls including bailing-out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering complete.	1.00	cum	4216.00	758.88	4974.88	4974.88
						Total Rs.	298236.67
						Say Rs.	298238.00


Executive Engineer (Civil)
EHV CCCM Dn. Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.