

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenance Division Nashik

"Administrative Building", Block No. 6, 1st floor, Racca Plot, Old Saykheda Road,
Jail Road, Nashik Road-422 101.

Ph No:-0253-2403102 (O), Fax No:-0253-2403103

E-Mail ID : ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

941

Date:-

13-9-17

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Painting to control room at 132 KV OCR Eklahare Sub station, Dist:- Nashik." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Painting to control room at 132 KV OCR Eklahare Sub station, Dist:- Nashik.

The quotations should reach to this office on or before **21/09/2017** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop:(Technical Bid)

- Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government.
- GST/ GSTIN Registration Certificate.
- E.P.F. Registration Certificate – issued by competent authority of Govt.
- Experience of having successfully completed similar civil works.
- Payment of **EMD Rs. 2990.00** to be made by bidder off-line only upto 14.00hrs of **21/09/2017** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

(b) Documents in 2nd Envelop:(Price Bid)

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.

- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



**Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.**

Copy s.w.r.t.-

- 1) The Chief Engineer EHV Projects cum O&M Zone, Nashik.
- 2) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer [Civil] EHV Civil S/Dn.-I, Nasik.
- 2) The Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.


MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED
EHV Civil Construction Cum Maint. Division. Nashik.

Name of Work: Painting to control room at 132 KV OCR Eklahare Sub station, Dist:- Nashik.

Schedule "B"

Sr No	Description of item	Quantity	Unit	Rate Excludin g taxes	Add GST 18%	Total	Amount, Rs.
1	Scraping out old white wash or colour wash or distemper by steel wire brushing/ scraping by sand paper and preparing the wall surface smooth including necessary repairs to scratches etc. complete	1620.00	Sqm	6.00	1.08	7.08	11469.60
2	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) tc.complete.Bd.P.6 Page No. 414 & Preapproval of superintending Engineer	1200.00	Sqm	60.00	10.80	70.80	84960.00
3	Providing and applying two coats of textured synthetic paint of approved shade and quality and one coat of primer before applying textured paint including scaffolding if necessary preparing surface by thoroughly cleaning oil, grease, dirt and other materials as required, etc. complete.As directed by Engineer in charge.	765.00	Sqm	104.00	18.72	122.72	93880.80
4	P/A two coats of polymer based external paint of standard manufacturer like Apex from Asian paints, Excel from Nerulac paints of approved colour to the plastered surfaces including scaffolding if necessary, cleaning and preparing the surfaces for specified building complete. (sample and brand is to be got approved from EE before use)(prior specific permission of S.E. shall be obtained before inclusion of this item in the estimate) Specification no. as directed by Engr in charge.	255.00	Sqm	174.00	31.32	205.32	52356.60
5	Providing and applying two coats of lead/zinc base oil paint/ bituminous paint of approved colour and shade to new wood work and fiber boards including preparing the surface, knotting, scaffolding if necessary, excluding primer coat etc.completeBd.O. 1 Page No. 403	70.00	Sqm	43.00	7.74	50.74	3551.80
6	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to the plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.Bd.0.8 Page No.406	100.00	Sqm	35.00	6.30	41.30	4130.00

Sr No	Description of item	Quantity	Unit	Rate Excludin g taxes	Add GST 18%	Total	Amount, Rs.
7	Providing & applying washable oilbound distemper of approved colour and shade to old & new surfaces in two coats including scaffolding, he surfaces. (excluding the primer coat.) etc. complete. Bd.P.5 Page No. 413	50.00	Sqm	30.00	5.40	35.40	1770.00
8	Providing and applying putty to new plastered surfaces in two coats to receive approved paint in all positions including all materials,labour scaffolding and curing etc. complete. As directed by Engineer in charge.	510.00	Sqm	77.00	13.86	90.86	46338.60
Total Rs.							298457.40
Say Rs.							298458.00


Executive Engineer (Civil)
EHV CCCM Dn.Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.