



(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra (E), Mumbai-400 051.

Office of the Executive Engineer,	То,
EHV Project Division, MSETCL,	
M.S.E.B Colony, Gorakshan Road, Akola	
Email: ee1610@mahatransco.in	
Web: www.mahatransco.in	
Phone No: 0724-2450691 & Fax: 0724-2450692	

No. MSETCL/EE/EHV/Proj./Div/Tech/AKL/No. 4620 Date: 21 NOV 2017

E-Enquiry

Sub:- Work of Carrying out Reconnaissance, Alignment and Detailed survey work of 132 KV LILO on Paras – Akot Line for proposed 132 KV S/Stn at (Karanja Ramzanpur) Mauje Khatka, Tq. Telhara, Dist Akola. -4.5 KM

Dear Sirs,

Sealed & super scribed percentage rate quotations are invited Carrying out Reconnaissance, Alignment and Detailed survey work of 132 KV LILO on Paras – Akot Line for proposed 132 KV S/Stn at (Karanja Ramzanpur) Mauje Khatka, Tq. Telhara, Dist Akola. -4.5 KM in the Schedule'B' annexed herewith and terms and conditions given below. The Bidders should submit their quotations on or before **28.11.2017 upto 17.00** Hrs. In case of hand delivery, Quotation should be handed over to receipt Clark of this office. MSETCL will not be responsible in any manner for the postal delay of any type.

Terms & Conditions:-

- 1. The scope of work is Carrying out Reconnaissance, Alignment and Detailed survey work of 132 KV LILO on Paras Akot Line for proposed 132 KV S/Stn at (Karanja Ramzanpur Mauje Khatka, Tq. Telhara, Dist Akola. -4.5 KM as per the items of Schedule'B' annexed and as directed by Engineer-in-charge.
- 2. The work shall have to be completed in all respect within a period of 8 days from the date of handing over of site, failing which the contractor shall be liable for penalty @1/2 % per week on unfinished work or maximum to 10 % of the value of the work order.
- 3. The rates quoted by the contractor should include all tools & plants, labors and
- 4. The work shall be executed as per the directives of engineer in-charge and as per the standard specifications of MSETCL
- 5. The rates quoted shall be exclusive of all GST taxes etc, However taxes should be mentioned in the bid.
- 6. In case the work is held up due to any reason, no compensation will be made for that.





(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra (E), Mumbai-400 051.

- 7. The contractor shall be responsible for all the accidents/damages caused during execution of work and he shall make good of the same at his own cost'
- 8. The contractor should abide all prevailing labor laws and following documents should be submitted along with bid
 - a) Shop and Establishment certificate
 - b) GST registration Certificate
 - c) PAN card
 - d) The bidders should have executed similar type of work particularly in MSETCL/Govt. Institution for minimum 5 Km. Experience for the similar nature of work should not be less than 5 Kms & certificate issued from the officer not below the rank of Executive Engineer regarding details of suruey work'
 - e) Income Tax return for previous 3 years.
 - f) The bidder should furnish the list of T&P equipment applicable along with detailed specifications/ ratings which available to them.
- 9. 100% payments shall be released by EHV Project Division, Akola as per availability of fund, after submission of bill in triplicate to EHV S&I S/Dn., Akola & necessary certification with recording in Measurement Book by Addl. Executive Engineer, EHV S&I S/Dn., Akola.
- 10. The quantities mentioned in the Schedule"B" are approximate and liable for variation MSETCL will not provide any materials, labour & T&P.
- 11. The right to reject any or all the bids without assigning any reason is reserved by the undersigned.
- 12. Bidder should not submit 'Conditional Quotation'. Such conditional offer shall be liable for rejection,
- 13. The estimated cost of the work is Rs. 79731.00 (Rs. Seventy Nine Thousand seven Hundred & Thirty One Only) including GST @ 18%.
- 14. 5% Security Deposit of Rs. 3400/- shall be paid at office of Executive Engineer, EHV Proj. Dn., Akola within 07 days after receipt of order.





(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra (E), Mumbai-400 051.

15. Agreement: You have to execute the agreements as per the provision of "Mumbai Mudrank Adhiniyam 1958, clause no.34" with requisite stamp of Rs.500.00 within 7 days from the receipt of order. You will have to enter into an agreement with MSETCL for the above work & until such agreement is not executed with MSETCL, the MSETCL shall not be liable to pay nor you shall be entitled for any amount due under this contract. The cost of stamp Paper requires shall be borne by you. The proforma of agreement should be should be collected from the office of Executive Engineer, EHV Proj. Division, Akola.

Encl:- Schedule 'B'

Executive Engineer. EHV Project Division, MSETCL, Akola.

Copy s.w.r. to:-

The Superintending Engineer, EHV PC, Amravati.

Copy to :-

- 1) The Addl. Executive Engineer, S&I S/Dn, Akola.
- The Manager(F&A), EHV Proj. Division, Akola.
- 3) Notice Board
- 4) MSETCL Website





(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra (E), Mumbai-400 051.

E-Enquiry No. MSETCL/EE/EHV/Proj/Div/Tech/AKL/No.

Date:-

Work Schedule

Name of the work :- Work of Carrying out Reconnaissance, Alignment and Detailed survey work of 132 KV LILO on Paras - Akot Line for proposed 132 KV S/Stn at (Karanja Ramzanpur) Mauje Khatka, Tq. Telhara, Dist Akola. -4.5 KM

Schedule 'B'

S.N.	Particulars of Item	Quantity	Unit	Rate Rs.	Amount Rs.
1	Reconnaissance survey of proposed route of line on field to ensure that forest area, village areas percolation tank catchments area and non agriculture land / plot are avoided. Also to ensure that proposed route of the line should be Shortest in length and approachable for erection of line and submitting 3 alternative routes on the route map having scale 1cm=0.50 km. on top sheets as per directives of engineer in charge.	4.5	KM	3232.00	14544.00
s c c a ir fri fri it s r r	Carrying out alignment as per approved route map by using precision Total station fixing of alignment by using wooden pegs duly concreted. To carry out detailed survey by chaining & leveling along the route and collecting details like HT,TP,EHV lines, railway, highways, roads canals etc. and fixing of stone/concrete pillars to angle points and important crossing and duly paited. Preparing ground profile (L-Section) with tower spotting on standard scale graph paper in a scale of 1cm=20M (Verticle) showing each details such as nalla, road, railway, telephone and tower lines in plans and elevation, collecting village maps from revenue authorities and joining them with proper scale (1:10000) and marking the surveyed nes belt, forest area ,N.A., plots as per scale on		KM	11110.00	49995.00





(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra

(E), Mumbai-400 051.

3	Excavation in all types of soil for trial pit of size 1MX1Mx3M deep along the route alignment at an integral of 3Km as well as at heavy angle points including refilling the trial pit after inspection and as directed by the Engineer in	2	No.	1515.00	3030.00	
	charge		Su	b-Total Rs.	67569.00	
	GST 18%					
Total Estimated Amount in Rs.						
Total Estimated Amt. Rs.						

(In Word:- Rs. Seventy Nine Thousand Seven Hundred & Thirty One Only.)

Note:- Overloading / Taxes should be mentioned separately.

Executive Engineer, EHV Project Division, MSETCL, Akola.





(CIN No.- U40109MH2005SGC153646)

Registered office: Prakashganga, Plot No.C-19, "E" Block, 1st Floor, Bandra Kurla Complex, Bandra (E), Mumbai-400 051.

PERCENTAGE RATE FORM

Form for	Quoting %	Rate for	items	included	in	Schedule	'B'	for-
----------	-----------	----------	-------	----------	----	----------	------------	------

E-Enquiry No:-MSETCL/EE/EHV/Proj./Div/Tech/AKL/No.

Date :-

Name of Work: E-enquiry for Work of Carrying out Reconnaissance, Alignment and Detailed survey work of 132 KV LILO on Paras – Akot Line for proposed 132 KV S/Stn at (Karanja Ramzanpur) Mauje Khatka, Tq. Telhara, Dist Akola. -4.5 KM

Estimated cost :- Rs. **79731.00** (Rs. Seventy Nine Thousand Seven Hundred & Thirty One Only.) including GST @ 18%.

I am ready to execute the work in Schedule B at:

E-Mail ID for Correspondence :-

	*			
1)		% Above (In word		% Above) the
	estimated cost.			
2)		% Below (In words		% Below) the
	estimated cost.			
3)	Rate Quoted = Estimated	Cost i.e. Rs	(In Word	医克里斯氏氏征 电阻 医乳腺 医乳腺 医乳腺 医乳腺 医二甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基甲基
)		
			C!	
			Signature with s	tamp of bidder:
	Name of Contractor :-			
		•		
	Address:-			
	PAN Card No:-			
	An Card No:-			
	Mobile No.:-			