

**MAHARASHTRA STATE ELECT. TRANSMISSION CO. LTD.**

From :-  
Name of Office :- EHV Civil Const. Cum Maint. Division, MSETCL, Amravati  
Office address :- Vidhyut Bhavan Shivaji nagar Amravati – 444603  
Contact No. :- 0721- 2663659  
Email Id :- [ee1710@mahatransco.in](mailto:ee1710@mahatransco.in)

EEC/EHV/CCCM/Dn./Amt/ Tech/

**406**

**Date 25.04.2018**

**E-QUOTATION**

**TO**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Sub : - Deepening of open well at 220KV S/Stn. Yavatmal.

**Due on : - 03.05.2018**

Dear Sir,

Sealed and super scribed Percentage rate quotations are invited so as to reach this office on or before **03.05.2018** up to **15.00** Hours for the execution of various items of works as per the Schedule - 'B' enclosed and as per the terms and conditions given below : -

**' TERMS & CONDITIONS '**

1. The terms and conditions mentioned in the ' Works and Contract ' Book-let are applicable and copies of same can be purchased by the Contractor (s) on payment of Rs. 50.00 from the office.
2. The work shall have to be completed in all respect within a period of **10 days** from the date issue of work order , failing which the Contractor will be liable to pay compensation / penalty at Half percent per week maximum up to 10% of the value of the work order.
3. The rates quoted by the Contractors shall include : -
  - i. All tools and plants required for carrying out the job.
  - ii. All labor charges required to execute the job.
  - iii. All temporary works required to complete the work including transportation of all required material to site.
4. The Company shall supply no material. All materials are required to be procured by the Contractor.
5. The work shall have to be carried out as per the 'Standard Specifications' and with best workmanship like manner and to the entire satisfaction of the Engineer-in-charge.
6. The Contractor shall be responsible for all accidents occurred / damages caused during the execution of the work He shall have to make good of the same at his own cost as directed.
7. The Contractor shall be responsible to abide all prevailing labour laws including the Workman Compensation Act.
8. The payment shall be made on the Final Bill basis.
9. The successful Contractor shall have to pay Security Deposit amounting to 5% of work order value.
10. The quantities in the Schedule - 'B' are approximate only and liable for variation.
11. The right to reject any or all quotations without assigning any reasons is reserved.

12. Any clarification pertaining to work shall be had from the undersigned before submitting the quotation.
13. The estimated cost of the work is **Rs. 100661.00 /- ( Approx )**
14. The Contractor shall have to pay Earnest Money Deposit ( **E. M. D** ) of **Rs. 1010/-** along with the quotation in the form of D. D./ cash in favour of E.E.(Civil), EHV CCCM Dn. Amravati.
15. The Income-tax and other applicable taxes per prevailing rate & rules shall be deducted from Contractor's bill, GST will be applicable as per GST rules.
16. Jurisdiction and Deduction clauses are applicable.
17. The blank quotation copy shall be available in EHV CCCM Dn. Amt. free of cost, during the working hours from **25.04.2018 to 02.05.2018**.
18. The rates quoted shall be inclusive of all taxes etc.

Enclosed : As above.

Sd/-  
**Executive Engineer ( C )**  
**EHV CCCM Division, MSETCL,**  
**Amravati**

C.s.w.rs.to :-

- 1) The Superintending Engineer ( C ), EHV CCCM Circle Amravati

Copy to :-

- 1) The Addl. Executive Engineer ( C ), EHV CCCM S/Dn. Yavatmal.
- 2) The Dy. Manager (F&A), EHV CCCM Dn. Amravati
- 3) Notice Board
- 4) Master File

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD**  
**EHV CCCM DIVISION, AMRAVATI**

Name of Work :- Deepening of open well at 220 KV S/S Yavatmal

**SCHEDULE B**

S. No.	Item of work	Unit	Quantity	Rate	Amount
1	Excavation in general in soft material comprising of soft soil, soft murum, sand, hard murum with boulders in wet and dry condition for Head Works i.e. Intake well, onnecting Pipe, Jack Well, Pump House, Supply Well, etc. for lift 1.5 M and lead of 150 M including baricating, guarding, disposing off surplus excavated stuff within a radius of 0.5 km. As directed by Engineer-in-charge, etc. complete. Excluding refilling.				
a	Lift 12.00 to 13.50 m.	cum	4.0	461.00	1844.00
b	Lift 13.50 to 15.00 m.	cum	4.00	484.00	1936.00
2	Excavation in general in hard material comprising of soft rock,hard rock,manjara rock,etc.by blasting /controlled blasting,chiselling as required in wet and dry condition for Head Works i.e. Intak Well,Connecting Pipe, Jack Well,Pump House,Supply well, etc. for lift 0 to 1.50 M and lead of 150 M includin baricating,guarding,disposing off surplus excavated stuff within a radius of 0.5 km. as directed by Engineer- in-charge, excluding refilling.				
a	Lift 13.50 to 15.00 m.	cum	7.50	791.00	5932.50
b	Lift 15.00 to 16.50 m.	cum	11.00	814.00	8954.00
c	Lift 16.50 to 18.00 m.	cum	11.00	837.00	9207.00
3	Dewatering the excavated trenches & pools of water in the building trenches/pipeline trenches well works by using pumps and other devices including disposing off water to safe distance as directed by Engineer-in-charge(including cost of machinery, labour,fuel),etc. complete.(Bd-A-9/261)	Bhp/hr	450.00	62.00	27900.00
4	Providing and supplying in standard lengths high density poly ethelene(HDPE) pipes , conforming to IS 4984/14151/12786/13488 with necessary jointing material like mechanical connector i.e. thread / insert joint quick realeser coupler joint/ compression fitting joint of flanged joint, including all sattutary duties and taxes such as GST levied by GOI and GOM in all respect, transportation and freight charges inspection charges , loading /unloading charges , conveyance to the departmental store /site and stacking the same in closed shed duly protecting from sunrays and rains.etc complete c) 10 Kg/sqcm , 63 mm dia.	Rmt	23.00	125	2875.00
5	Providing and fixing nylon rope of dia.15 mm.	Rmt	30.00	45.00	1350.00
6	Supplying , providing and fixing 3 core 2.5 sqmm PVC insulated , PVC sheathed copper conductor flat submersible cable/ supplying and erecting ,flat flexible submersible cable with copper conductor , PVC insulated ,and PVC sheathed.	Rmt	30.00	84.00	2520.00
7	Providing and fixing 40 mm dia screw down required dia wheeled stop tap of brass including necessary sockets union nut, testing etc complete .	no	2.00	655.00	1310.00

8A	Providing and laying in trenches 40mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary as directed etc. complete.	Rmt	50.00	357.00	17850.00
B	Providing and laying in trenches 50mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and as directed etc. complete.	Rmt	10.00	579.00	5790.00
9	Providing and fixing CI non return valve of dia 50 mm .	No	1.00	2715.00	2715.00
10	Providing Accessories like SS nipples, SS nut bolts, coupling, washers, cable tie, joining kit with carting	set	1.00	2000.00	2000.00
11	Provide Mandays for cutting of bushes in open well and nearby area of open well and cleaning the area	Per Day	10.00	529.00	5290.00
12	Disposing of excavated material upto lead of 2.0 Km including Loading and unloading. etc. complete.	cum	37.50	85.00	3187.50
				Total Rs.	100661.00

Sd/-  
**Executive Engineer ( C )**  
**EHV CCCM Division AMRAVATI**

I am/ we are ready to execute the above said work :----- % (in fig.)  
 \_\_\_\_\_percent ( in words) above / below/ At par the  
 estimated cost.

**Signature of the contractor**