



MAHATRANSCO

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	Office of the Executive Engineer,
Office Address	EHV (O&M) Division, 132kV S/s Campus, Jintur Road, Parbhani. Pin-431401
Contact No.	(O) 02452 - 231851, Fax-02452-233026 (Resi) 02452-246124
Email Id	ee2120@mahatransco.in / eepbn1@gmail.com
Website	www.mahatransco.in

No.EE/EHV (O&M)/PBN/TS/ 756

Date: - 16.07.2018

E-Enquiry (Date Extension)

Sub: Work of Providing & Installation of LT Power cable for newly erected station transformer at 220 kV Parbhani s/s.

Reference: First call of Enquiry floated vide T.O. letter no EE/EHV (O&M)/PBN/TS/676 dated 03.07.2018 valid up to 16.07.2018, 15:00Hrs

Dear Sir / Madam,


Sealed & Super scribed quotations are hereby invited, by undersigned, for the Work of Providing & Installation of LT Power cable for newly erected station transformer at 220 kV Parbhani s/s, under EHV (O&M) Division, Parbhani, as mentioned in Schedule-A. Submit the sealed quotations to this office on or before Dt. **19.07.2018 Up to 15:00 Hrs.**

The Other Terms & Conditions are as follows:

1. Quotations should be duly filled in all respect & to be submitted to this office, within due date.
2. Quantities mentioned in Schedule-A are approximate & may vary. However, payment will be made on the basis of actually executed works.
3. Rates should be quoted in Schedule-A, combined for Both Supply & Erection, in % Above or below the Estimated Rates.
4. Taxes (GST) will be paid extra, as applicable.
5. Enclose the copies of following documents, along with quotations:
 - Pan Card
 - Valid Electrical Contractor License
 - Service Tax Registration
 - Shop Act License
 - VAT Registration
6. Other Terms & Conditions, as per Company's Rule will be binding upon you.

Thanking You,

Yours Faithfully,


Executive Engineer,
EHV (O&M) Division, MSETCL
Parbhani

Copy s.w.rs.to:

1. The Superintending Engineer, EHV (O&M) Circle, Aurangabad.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED
EHV (O&M) DIVISION, PARBAHNI

**Schedule-A : Work of Providing & installation of LT Power Cable for newly erected station transformer,
at 220kV S/stn. Parbhani, under EHV (O&M) Division, Parbhani**

Sr. No.	Particulars	Unit	Quantity	Estimated Unit Rate in Rs.	Estimated Total Amount
	Supply of LT Power Cable				
1	3.5 core,240 sqmm,1100V,Armoured, E.C. Grade, Aluminium, PVC insulated FRLS	No.	300	600.0	180000.0
	Laying & Termination of LT Power Cable				
2	1100 V LT Power Cable Laying	Rmt	300	51	15300.0
3	Cable termination of 240 sqmm Control cable at both ends including required material such as Lugs etc.	Per cable	1	1566.0	1566.0
4	Total Estimated Amount				196866.0
Quote in % (Above or below) with respect to Total Estimated Amount (Sr. No. 4)					
Remark : GST will be Paid Extra as applicable					

Remark : GST will be Paid Extra, as applicable.

Stamp & Seal of Agency

**Executive Engineer,
EHV (O&M) Division, MSETCL,
Parbhani**