

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD. CIN No.U40109MH2005SGC153646

Name of Office: 400 kV RS Division, Kumbhargaon, Nanded.

Office Address :- Office of the Executive Engineer, Nanded-Hyderabad

Highway, Near Kapsi Gumfa Tq. Loha Dist. Nanded-

431708

Contact No.

:-8554993393 / 8554995329.

Email :- ee2270@mahatransco.in; ee400kvkumbhargaon@gmail.com Ref. No. EE/400kV RS/Div./K'gaon/Nanded/TS/File No.43/No. 7 8 5 ... ate:

E-Enquiry

To,

Subject:-E-Enquiry for Providing & fixing of Aircells for 167 MVA 400/220 kV units of ICT-I at 400 kV R S Kumbhargaon, Nanded.

Dear Sir,

Sealed & super scribed quotation are invited from date 02.08.2018, so as to reach this office up to date 09.08.2018 up to 17:00 hrs for Providing & fixing of Aircells for 167 MVA 400/220 kV units of ICT-I at 400 kV R S Kumbhargaon, Nanded on following terms & conditions:-

TERMS AND CONDITIONS:-

1. The Rate shall be quoted on firm quotation basis.

2. The quotation should be sent under sealed cover duly super scribed as QUOTATION Providing & fixing of Aircells for 167 MVA 400/220 kV units of ICT-I at 400 kV R S Kumbhargaon, Nanded.

(Enquiry No. ____ be quoted).

3. The price quoted by you in your quotation for supply of the material shall be on firm quotation basis.

4. Your quotation should reach this office on or before 09.08.2018 up to 17:00 hrs

and the same will be opened on the same day, if possible.

5. Quotation received after due date will not be considered. This office is not responsible for any postal delay.

6. Documents required:- The rate offer must be accompanied with the following

documents duly attested & signed by the Agency.

- A. Valid proof of Electrical Contractor.
- B. Valid proof of registration under GST.
- C. Valid proof Shop Act registration.
- D. PAN Card



- 7. The material shall be supplied within 30 days from the date of receipt of this office order otherwise penalty @ 1% per week subject to max.10% of the order amount will be levied at the discretion of the Competent Authority.
- 8. The rates offer submitted by you should be valid for at least 90 days from the last date of receipt of quotation.
- 9. Quantity:- Quantity shown in Schedule "A".
- 10. Payment: 100% payment will be made against receiving of bills from Addl.EE 400 kV Substation Maint. Unit K'gaon, Nanded. The bills in triplicate, advance stamp receipt, along with the MOM should be submitted to Addl.EE Substation Maint. Unit Kumbhargaon, M.B. recording / service entry will be done by Addl.EE400 kV Substation Unit K'gaon, Nanded. No part payment will be made.
- 11. Paying Office:- The payment against this contract will be effected by Executive Engineer, EHV O&M Division Nandedoffice within reasonable time as per funds availability after recording of measurements by concerned Executive Engineer.
- 12. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.
- 13.Please quote your PAN & GST No. in the quotation & provide HSN / SAC code for material or service provided by you.
- 14.Material is to be used by you for above work should be of standard make & should be good in condition.
- 15. Security Deposit: Security deposit i.e. 5% of order value to be paid within 7 days in terms of cash/DD/ cheque / Bank guarantee to the office of the Executive Engineer, EHV O&M Division Nanded from the date of issue of order.
- 16.All the MSETCL's general terms & conditions for purchase will be binding on you.

Thanking you.

Encl.:- Schedule "A"

Yours faithfully,

Extandill (S R Ramteke)

Executive Engineer
400 kV R S Division Kumbhargaon
Nanded

Copy SWRT:-

1. The Superintending Engineer, EHV O&M Circle Parli V

Copy to:-

- 1. The Dy.Mgr (F&A), 400 kV R S Division Kumbhargaon, Nanded / EHV O&M Division Nanded.
- 2. Website:- www.mahatransco.co.in



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD. EHV (O&M) DIVISION, NANDED.

Schedule "A":-

Subject:- Providing & fixing of Aircells for 167 MVA 400/220 kV units of ICT-I at 400 kV R S Kumbhargaon, Nanded.

Sr. No.	Particulars	Unit	Qty.	Rate
1	Supply of Aircell for ICT	No.	2	
2	Testing of air cell by filling dry air / N2 gas, firstly on ground & checking for any leakages visual inspection etc. After fixing / fitting of aircell refilling of N2 / Dry air at standard pressure.	No.	2	
3	Fitting & Fixing of Air Cell. By draining & refilling of oil. Checking & attending oil leakages on conservator plate if any.	No.	2	
4	Gasket - 09 m thick gastekt ring	No.	2	
5	Gasket - 06 mm	No.	2	
5	Gasket - 06 mm	No.	2	

Final Lowest Amount of all agencies will be compared irrespective of individual item rates.

(S R Ramteke)
Executive Engineer
400 kV R S Division Kumbhargaon

Nanded