


**- OFFICE OF THE -  
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building, first Floor,  
wing no.102, Aurangabad, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/

**10 - 0013**

Date:-

**4 JAN 2019**

Quotation

To,

.....  
.....  
.....

**Sub: Providing 1.60 m height chain link fencing along with necessary miscellaneous civil works behind the Administrative Building at 132 KV Sub/stn. Harsool, Aurangabad.**

**Dear Sir,**

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or **before dated 11/01/2019 Time 16.30 Hrs.**


**TERMS AND CONDITIONS:**

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(15)** days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost. and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost
- 9) The material should be got approved prior to fixing from the Engineer in-charge.

Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.

- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-II Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit 13,000.00 (5% of quotation value) as security deposit in cash or DD of any nationalized Bank within 10 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The contractor has to pay earnest money to **Rs. 3,000.00/-** in cash/In form of DD/FDR of any Nationalized Bank in favor of EE (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. If the EMD of required amount is not found in the envelop the quotation will be rejected
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is Rs. **2,50,202.00** only. (Inclusive of all Taxes)
- 23) The Contractor has to submit the Civil Works Registration Certificate, GST Registration and PAN card.

**Encl:** Schedule 'B'

  
Executive Engineer (C)  
EHV CCCM Division.  
MSETCL, Aurangabad

**Copy S.W.R.S. to:**


1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.  
...This is as per approval vide Ltr. No. 1401 Dtd. 20.12.2018



**- OFFICE OF THE -**

**EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building, first Floor,  
Wing no.102, Aurangabad, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD/Tech/

Date:-

(e-Enquiry)

**QUOTATION NOTICE**

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Aurangabad on or before Dated **11/01/2019 Time 16.30 Hrs.**

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Q. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	Providing 1.60 m height chain link fencing along with necessary miscellaneous civil works behind the Administrative Building at 132 KV Sub/stn. Harsool, Aurangabad.	Rs. 2,50,202.00	Rs. 3,000.00	15 Days

Executive Engineer (C)  
EHV CCCM Division.  
MSETCL, Aurangabad

**Copy S.W.R.S. to :**

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.

...This is as per approval vide Ltr. No. 1401 Dtd. 20.12.2018

**- OFFICE OF THE -  
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building , first Floor,  
wing no.102, Aurangabad, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/No.Date: -

**Name of Work: Providing 1.60 m height chain link fencing along with necessary miscellaneous civil works behind the Administrative Building at 132 KV Sub/stn. Harsool, Aurangabad.**

**Estimated Amount: - Rs. 2,50,202.00 (Inclusive of All Taxes)**

Executive Engineer (C)  
EHV CCCM Division.  
MSETCL, Aurangabad

**Quotation for Works**

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure) .....% above/below/Estimated Rate (in Words) ..... percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

**Signature of the contractor**

**Full Address:**




**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**  
**EHV Civil Construction Cum Maintenance Division, Aurangabad.**  
**Schedule B**

Name of work - Providing 1.60 m height chainlink fencing along with necessary miscellaneous civil works behind the Administrative Building at 132 KV Sub/stn. Harsool, Aurangabad.

Sr. No	Activity No.	Particulars	Unit	Quantity	Rate (Rs.)	Add 18% GST	Rate with GST	Amount (Rs.)
1	2	3	4	5	6	7	8	9
10		Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.)	Cum	5.50	150.15	27.03	177.18	974.47
20		Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	Cum	10.50	4848.44	872.72	5721.16	60072.17
30		Providing and erecting chain link fencing 1.6 M. height with G.I. chain link of size 50 x 50 mm, 8 gauge thick and fixed 75 mm above ground level on vertical M.S. Angles of 40 x 40 x 6 mm size, including excavating pits for foundation and embedded in C.C. block of 1:4:8 mix of size 450 x 450 x 670 mm. at 1.75 M. c/c with iron bar 16mm dia as hold fast including welding link with angle frame at 30 cm c/c with nuts and bolts and horizontal M.S. Angles at top and bottom of 25 x 25 x 5 mm size and vertical M.S. flat 35 x 5 mm and 25 x 5 mm horizontal including cross support of 40 x 40 x 6 mm angles both side at every corner or bend embedded in concrete blocks of 1:4:8 of size 450 x 450 x 670 mm including 3 coats of oil painting etc. complete.	Rmt	40.00	1850.10	333.02	2183.12	87324.72
40		Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	MT	0.05	74564.70	13421.65	87986.35	4399.32
50		Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc Complete.	Cum	4.50	6043.85	1087.89	7131.74	32092.84

		Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/ quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	Cum	1.00	5604.13	1008.74	6612.87	6612.87
70		Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.	Sqm	32.00	231.83	41.73	273.56	8753.90
80		Providing and fixing powder coated B class GI pipe material outdoor gym equipment- leg press of size 1.447X0.48X1.568 m along with all transportations, labours and necessary fixing material, etc. complete. With 1 year warranty against manufacturing defects. As per the directions given by Engineer In-charge.	EA	1.00	21175.00	3811.50	24986.50	24986.50
90		Providing and fixing powder coated B class GI pipe material outdoor gym equipment- shoulder press single of size 1.319X0.63X1.897 m along with all transportations, labours and necessary fixing material, etc. complete. With 1 year warranty against manufacturing defects. As per the directions given by Engineer In-charge.	EA	1.00	21175.00	3811.50	24986.50	24986.50
Total						Rs.		250202.00

  
 Executive Engineer(C)  
 EHVCCM Division  
 MSETCL Aurangabad