

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD**

Name of Office : EHV Project Division Nanded  
Office address : 132 Kv Jangamwadi Sub station Campus , Nanded 431605.  
Contact No. : Tel: 263105 ( O ) 260107 (P) 261981  
Emailid : [ee2630@mahatransco.in](mailto:ee2630@mahatransco.in)  
Website : [www.mahatransco.in](http://www.mahatransco.in)

No. EE/EHV/NND/Tech/867

Date:- 01/07/2019.

**E-Enquiry**

To,

.....

**Subject:- E-Enquiry** for Repairing of 33/0.4 KV 200 KVA Station Transformer at 132KV Sengaon S/s under EHV Project Division, Nanded.

**Dear Sir,**

Sealed & super scribed quotation are invited from date **03.07.2019**, so as to reach this office up to date **11.07.2019 up to 17:00 hrs** for Repairing of 33/0.4 KV 200 KVA Station Transformer at 132KV Sengaon S/s under EHV Project Division, Nanded as per Schedule 'A' given below, on following terms & conditions:-

**TERMS AND CONDITIONS:-**

1. The Rate shall be quoted on firm quotation basis.
2. The amount of Repairing of 33/0.4 KV 200 KVA Station Transformer cost is limited to **Rs. 2.0 Lakhs.(Inclusive of all Taxes)**
3. The quotation should be sent under sealed cover duly super scribed as QUOTATION FOR Repairing of 33/0.4 KV 200 KVA Station Transformer at 132KV Sengaon S/s under EHV Project Division, Nanded. (Enquiry No. \_\_\_\_ be quoted).
4. As per scope of work, you have to submit the detail repairing schedule with the supporting documents for the rates in sealed quotation.
5. Your quotation should reach this office **on or before 11.07.2019 up to 17:30 hrs** and the same will be Opened on the same day, if possible.
6. The rates offer submitted by you should be valid for at least 60 days from the last date of receipt of quotation.
7. Documents required:- The rate offer must be accompanied with the following documents duly attested & signed by the Agency.


1) Shop Act License

2) CST registration

- 4) Certificate of performance of similar work executed.
- 5) Certificate of authorized dealership/distributorship (preferably)
8. Work completion Period:- After receipt of 33/0.4 KV 200 KVA Station Transformer, the work shall be completed within 15 days otherwise penalty @ 1% per week subject to max.10% of the order amount will be levied at the discretion of the Competent Authority.
9. Please quote your PAN, GST No. in the quotation.
10. Security Deposit:- Security deposit i.e. 5% of order value to be paid within 7 days in terms of cash/DD/ cheque / Bank guarantee to the office of the Executive Engineer, EHV Project Div. Nanded from the date of issue of order.
11. Payment will be effected by this office by cheque after satisfactory execution of required work.
12. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.
13. All the MSETCL's general terms & conditions for purchase will be binding on you.

Thanking you.

Yours faithfully,

  
**Executive Engineer**  
**EHV Project Division, Nanded.**

**Copy S.w.r to:-**

- 1) The Chief Engineer, EHV Proj.C O&M Zone, Abad.
- 2) The Superintending Engineer, EHV Project circle A'bad.

**Copy to:-**

1. The Manager (F&A), EHV Project Division Nanded.
2. Website:- [www.mahatransco.co.in](http://www.mahatransco.co.in)



## MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED

### EHV Project Division, Nanded


**Estimate for :-** Work of Repairs of 33/0.430kV, 200kVA Station Transformer, at 132kV Sengaoon S/stn. under EHV Project Division, Nanded.

#### 'ANNEXURE-A'

Sr No	Particulars	Unit	Material cost in Rs	Rate for Services in Rs.	Material cost in Rs.	Service/labour cost in Rs.
1	Rewinding of HV Coil using new SE Cu Wire	Kg	609.52	60.0	Limited To Rs.2.00 lakhs. (Inclusive of GST)	
2	Rewinding of LV Coil using new SE Cu Wire	Kg	90.47	60.0		
3	Insulating Material	Kg	266.66	-		
4	HV Bushing	Nos.	685.71	-		
5	HV Bushing Rod (Brass)	Nos.	361.90	-		
6	HV Bushing Cap(Brass)	Nos.	57.14	-		
7	LV Bushing	Nos.	85.71	-		
8	LV Bushing Rod(Brass)	Nos.	619.04	-		
9	LV Bushing Cap(Brass)	Nos.	47.61	-		
10	Silica Gel Breather	Per job	266.66	-		
11	M.S. Nut Bolt Washer, Brass Nut etc. For a Job	Per job	1428.57	-		
12	Labour Charges for Repairs of Station Transformer	Nos.	-	7500.0		
13	Transformer Baking in oven, assembly of coil & core, testing, oil filling & filtration	Nos.	-	2850.0		
14	Rubber Washer, oil seal, cork sheet, oil level indicator etc.	Nos.	1495.23	-		
15	Painting of transformer tank	Nos	-	680.0		
16	Less-Burnt Copper wire scrap	Kg				

**Remark:-**

- 1) For: Less Burnt Copper wire scrap: Rate will be as per current scrap copper rates as given by MSETCL, store authority.
- 2) The Order limited to Rs. 2Lakhs including GST.

  
**Executive Engineer**  
**EHV Project Division, Nanded.**