

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)
EHV Civil Construction cum Maintenance Division Nashik
"Administrative Building", Block No. 6, 1st floor, Racca Plot,
Old Saikheda Road, Jail Road, Nashik Road-422 101.
Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-989 Date:-

122 JUL 2019

CORRIGENDUM

Sub:- Tender No. T-02/2019-20 for the work of Repairing of damaged compound wall and various civil maintenance work in staff quarter at 220 KV Soyegaon Sub station,
Dist:- Nashik
----- Correction in SRM schedule B..

Ref:- 1) Tender No. T-02/2019-20 (Rfx No. 7000013323) published on 08/07/2019.

With reference to above subject, there is a correction in in SRM schedule B.
following item read as

No.	SRM Description of Item	Unit	Correction in Description	Unit
1.A M	Dismantling stone masonry	Cum	Providing and fixing 1st class white glazed earthenware orissa type W.C. pan 580 mm. including 'P' or 'S' trap cast iron soil and soil vent pipe upto the outside face of the wall (1:5:10) cement concrete bedding 15 mm. thick with flushing system of 32 mm. dia. push cock or half turn valve with all fixtures of flushing system etc. complete. Spec. No. BDV- P.No 106 & BDV- P.No 106.	Nos.
1.AT	UCRM in CM 1:6 in foundation & plinth wall	Cum.	Providing and laying insitu/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	Cum.

No.	SRM Description of Item	Unit		Correction in Description	Unit
1.AV	Providing flush grooved CM1:3 to Stone masonry	Cum		Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	MT
1.A W	Plaster 12mm thick 1coat CM1:4 wt neeru	Cum		Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing out water manually , striking joints on un exposed faces and watering etc. complete.	Cum
1.BC	Providing Service of skilled labour /day	Per day		Providing and laying weep holes of 100 mm diameter PVC pipes as per drawing for abutment returns, return walls etc. Complete.	Rmt

Other terms and conditions of the work order/ tender remains unchanged.



(V. M. Dhore)
Executive Engineer (Civil)
EHV CCCM Din. Nasik

Copy to

- 1) Notice Board.
- 2) M.F.