

**OFFICE OF THE :-
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad.Ph. No. (0240) 2331429.

E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646

No.:EEC/EHV/CCCM/Dn./ABD//Tech/

1086

Date:- **13 SEP 2019**

E-enquiry

To,

.....
.....
.....

Sub: Construction of vehicle shed at 220 KV S/S Bhokardan, Dist.Jalna

Dear Sir,


Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Mahatransco Administration Building, first Floor, wing no.102, Aurangabad on or before dated **25/09/2019 Time 16.30 Hrs.**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(2) MONTHS** from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.

- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division Jalna to the undersigned. Payment will be made within 30 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit **13,500.00/-** (5% of quotation value) as security deposit in cash/ DD/FDR of any nationalized Bank within 3 days from the date of receipt of work order, failing which EMD will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The contractor has to pay earnest money to **Rs. 3,000.00/-** in cash/RTGS/NEFT/In form of DD/FDR of any Nationalized Bank in favor of EE (C) EHV CCCM DIVISION, MSETC Ltd. Aurangabad. If the EMD of required amount is not found in the envelop the quotation will be rejected.
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.

- 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is **Rs.2, 62,539.00/-** only. (Inclusive of all Taxes)
- 23) Contractor has to submit Valid registration certificate, GST registration certificate, PAN Card & Experience certificate as a mandatory documents at the time of submission of Quotation.



(S.P. Kamble)

Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Encl: Schedule 'B'

Copy S.W.R.S. to :

1. The Chief Engineer EHVP.C. (O&M) Zone MSETCL Aurangabad
2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.

...This is as per approval vide Ltr. No. 1190 Dtd. 09.09.2019....


Copy to:

1. The Addl. Executive Engineer (C) EHV CCCM Sub Division-Jalna.
2. The Dy. Manager (F&A) EHV CCM Division Aurangabad. The amount of this work is Chargeable to sanctioned estimate no. T- / 2019-20 Dt. under CAPEX Budget.
3. Notice Board

OFFICE OF THE :-

EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/

Date:-

(e-Enquiry)
QUOTATION NOTICE

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of the Executive Engineer (C), EHV Civil Constn. Cum Maint. Division, Mahatransco Administration Building, first Floor, wing no.102, Aurangabad on or before Dtd. 25.09.2019 up to 16.30 hrs.

The blank quotation will be issued on application to contractors, producing the Certificate of valid registration.

Q. No.	Name of work	Estimated cost	E.M.D	Time Limit
1.	Construction of vehicle shed at 220 KV S/S Bhokardan, Dist.Jalna	Rs 2,62,539.00/-	Rs3,000.00/-	2 Months

(S.P. Kamble)

Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Copy S.W.R.S. to :

1. The Chief Engineer EHVP.C. (O&M) Zone MSETCL Aurangabad
 2. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
- ...This is as per approval vide Ltr. No. 1190 Dtd. 09.09.2019


Copy to:

1. The Addl. Executive Engineer (C) EHV CCCM Sub Division-Jalna
2. The Dy. Manager (F&A) EHV CCM Division Aurangabad / The amount of this work is Chargeable to sanctioned estimate No. T- 2019-20 Dt. under CAPEX Budget.
3. Notice Board

OFFICE OF THE :-

EXECUTIVE ENGINEER (C)


EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/No.Date: -

Name of Work : Construction of vehicle shed at 220 KV S/S Bhokardan, Dist.Jalna

Estimated Amount: -Rs. 2, 62,539.00/- (Inclusive of All Taxes)


(S.P. Kamble)

Executive Engineer (C)
EHV CCCM Division.
MSETCL, Aurangabad

Declaration of Contractor:

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor

Full Address:

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION, AURANGABAD


Name of Work : Construction of vehicle shed at 220 KV S/S Bhokardan, Dist.Jalna

SCHEDULE 'B'

Quantity	Description	Rate	Unit	Amount	Activity No
7.000 Cubic Metre	Item No : 10 Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 metre beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. - (Lift upto 1.5 metre)	169.00	One Cubic Metre	1183.00	50013068
	Rate as per R. A. No. - 10				
4.000 Cubic Metre	Item No : 20 Excavation for foundation in hard murum including removing the excavated material upto a distance of 50 metre beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 metre)	185.00	One Cubic Metre	740.00	50013069
	Rate as per R. A. No. - 20				
2.000 Cubic Metre	Item No : 30 Excavation for foundation in hard murum and boulders including removing the excavated materials upto a distance of 50 metre beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5 metre to 3.0 metre)	254.00	One Cubic Metre	508.00	50014035
	Rate as per R. A. No. - 30				
9.000 Cubic Metre	Item No : 40 Providing and laying Cast in situ/Ready Mix, cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting and curing etc. complete, with fully automatic micro processor based Programmable Logic Controller with Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	5659.00	One Cubic Metre	50931.00	50013139
	Rate as per R. A. No. - 40				
2.000	Item No : 50	6213.00	One	12426.00	50013146

Cubic Metre	Providing and laying Cast in situ / Ready Mix cement concrete M-15 of trap / granite / quartzite / gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, plywood / steel formwork, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing, etc. complete. The cement mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin, etc. (Wooden centering will not be allowed.) with fully automatic micro processor based Programmable Logic Controller with Supervisory Control and Data Acquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)		Cubic Metre		
	Rate as per R. A. No. - 50				
56.000 Square Metre	Item No : 60 Providing and fixing corrugated galvalanised iron sheets of 0.63 milimetre thick (24 B.W.G) for roofing without wind tiles including fastening with galvanised iron screw and bolts and lead / bitumen washers as per drawing, etc. complete. (Weight 5.5 killogram per square meter)	809.00	One Square Metre	45304.00	50013386
	Rate as per R. A. No. - 60				
5.000 Square Metre	Item No : 70 Providing and fixing plain zinc sheeting of 0.80 milimetre thick (22 B.W.G) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt, galvanised iron screw and bolts and lead and bitumen washers, etc. complete. (Weight 6.8 killogram per square meter)	1122.00	One Square Metre	5610.00	50013387
	Rate as per R. A. No. - 70				
1.000 Metric Ton	Item No : 80 Providing and fabricting structural steel work in rolled sections like joists, channels, angles, tees, etc. as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted / welded connections without connecting plates, braces, etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade, etc. complete.	83797.00	One Metric Ton	83797.00	50013128
	Rate as per R. A. No. - 80				
53.000 Square Metre	Item No : 90 Providing and laying cement concrete flooring 40 milimetre thick with M-20 cement concrete laid to proper level and slope in alternate bays, including compaction, filling joints, marking lines to give appearance of tiles of 30 centimetre X 30 centimetre or other size laid digonally / square, etc., finishing smooth (with extra cement) in any colour as directed and curing etc. complete. - with natural sand.	492.00	One Square Metre	26076.00	50013268
	Rate as per R. A. No. - 90				
0.200 Cubic Metre	Item No : 100 Providing second class Burnt Brick masonry with conventional / Indian Standard type bricks in cement mortar 1:6 superstructure including striking joints, racking out joints, watering and scaffolding, etc. complete.	6406.00	One Cubic Metre	1281.20	50013188
	Rate as per R. A. No. - 100				
1.000	Item No : 110	578.00	One	578.00	50013242

Square Metre	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 milimetre to 15 milimetre thick in cement mortar 1:4 and routh cast treatment 12 milimetre thick in proportion 1:1.1/2:3 including scaffolding and fourteen days curing complete. Rate as per R. A. No. - 110		Square Metre		
1.000 Square Metre	Item No : 120 Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface (excluding primer coat), etc. complete. Rate as per R. A. No. - 120	92.00	One Square Metre	92.00	50013354
14.000 Cubic Metre	Item No : 130 Providing soling using 80 milimetre size trap metal in 15 centimetre layer including filling voids with crushed sand / grit, ramming, watering etc. complete. Rate as per R. A. No. - 130	1929.00	One Cubic Metre	27006.00	50013077
6.000 Cubic Metre	Item No : 140 Supplying soft murum at the road site, including conveying and stacking etc. complete. Rate as per R. A. No. - 140	933.00	One Cubic Metre	5598.00	
6.000 Cubic Metre	Item No : 150 Spreading hard murum / soft murrum / gravel or kankar for side width etc. complete. Rate as per R. A. No. - 150	67.00	One Cubic Metre	402.00	50013801
53.000 Square Metre	Item No : 160 Compacting the hard murum side widths including laying in layers on each side with vibratory roller including artificial watering etc. complete. Rate as per R. A. No. - 160	19.00	One Square Metre	1007.00	50013806
		Total Rs.		2,62,539.20	
		Say Rs.		2,62,539.00	


 (S. P. Kamble)
 Executive Engineer (C)
 EHV CCCM Division, Aurangabad.