

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**

Name of Office	:	<b>Office of the Executive Engineer</b>
Office Address	:	400kV R.S.(O&M) Division, Babhaleshwar, A&P. Pimpari Nirmal, Tq. Rahata, Dist. Ahmednagar – 423107
Contact No.	:	02422 (O) 278173 (R) 278148 (Fax) 278153
Email Id	:	ee5130@mahatransco.in
Website	:	http://www.mahatransco.in

Ref.No. EE/400kV/RS/Dn/BBLR/Tech/ **11-0080**

Date: **23 JAN 2020**

**Sub: - Enquiry for Work of Construction of cable Trench & providing and fixing cable trays at 400KV Babhaleshwar substation under 400kV R. S. Babhaleshwar.**

Dear Sir,

With ref to the above, bids are invited by the undersigned from reputed, experienced & approved vendors of MSETCL for the above works, till 19.05.2019 till 24:00Hrs, as per particulars, terms & conditions as given below & schedule is attached herewith

**TERMS & CONDITIONS:**

1. Rates quoted should be on firm quotation basis.
2. No extra charges for transportation, T&P, machinery, material required, skilled workmen etc will be paid, it will be arranged by you only.
3. Quantities mentioned in our enquiry are tentative & subject to varied.
4. Payment will be effected after completion of work & as per actual workdone.
5. Validity of your quotation should be 120days.
6. The period of completion of work will be 30days.
7. The work shall be carried out as per IS standards & procedures.
8. 5% of the order value as security deposit will have to be paid by you within 7 days from the date of firm order in the form of Cash/BG/DD of any Nationalized/Scheduled Bank in favor of "Executive Engineer, 400kV R.S.(O&M) Division, MSETCL, Babhaleshwar" in prescribed format valid for 1 year. The same will be refunded after successful completion of guarantee period of the work done.
9. In any loss occurs to MSETCL's property during execution of work, the same will be recovered as per prevailing rates from your bill.
10. The income tax & other taxes will be deducted from your bill as per prevailing rules.
11. MSETCL will not be responsible for any accident or damages to your staff during execution of work.
12. All other standard conditions of contract prevailing in MSETCL are applicable in this case also.
13. Bids received after due date will not be accepted
14. If any dispute arises, the decision of the undersigned will be final & binding on you.
15. The undersigned reserves the right to reject any or all quotations without assigning any reason




The following documents should attached along with your offer-----

- Electrical contractor License.
- GST Registration certificate with latest paid challan.
- PF Registration certificate with latest paid challan.
- Workmen's compensation policy.
- The bidder should submit work order copy with experience certificate of execution of work in 400kV Substation yard.
- PAN card with last three A.Y. IT return. (2015-16; 2016-17 & 2017-18)
- Shop Act /SSI Certificate

16. Jurisdiction: the Jurisdiction of all legal proceedings/suits as regards to the works under contract will be in Ahmednagar District Court

Thanking you.

  
Executive Engineer  
400kVR.S.(O&M)Division

Babhaleshwar

Copy s.w.r.to: (By e-mail)

- 1) The C.E.EHV CC O&M Zone, Nashik
- 2) The S.E. EHV (O&M) Circle, Nashik.

Copy to: (By e-mail)

- 1) The Addl. Ex. Engr. (Maint unit.) 400kV R.S., BBLR.
- 2) The Dy. Manager (F&A) 400kV R.S., BBLR.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**

Name of Office	:	<b>Office of the Executive Engineer</b>
Office Address	:	400kV R.S.(O&M) Division, Babhaleshwar, A&P. Pimpri Nirmal, Tq. Rahata, Dist. Ahmednagar – 423107
Contact No.	:	02422 (O) 278173 (R) 278148 (Fax) 278153
Email Id	:	ee5130@mahatransco.in
Website	:	<a href="http://www.mahatransco.in">http://www.mahatransco.in</a>

**Schedule**

**Sub: Enquiry for Work of Construction of cable Trench & providing and fixing cable trays at 400KV Babhaleshwar substation under 400kV R. S. Babhaleshwar**


Sr. No	Particulars	Unit	Qty	Rate	Total Amount
1	supply of 400X40X2 MM GI cable trays	RMT	90	645.95	<b>58135.5</b>
2	Erection of Cable Trays 400X40x2 MM	RMT	90	41.71	<b>3753.9</b>
3	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.)	CuM	19	170.42	<b>3237.98</b>
4	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m)	CuM	27	187.11	<b>5051.97</b>
5	Providing and laying in situ cement concrete in 1:4:8 of trap / granite / quartzite / gneiss metal for foundation and bedding including bailing-out water manually, formwork, compacting, covering newly laid concrete by gunny bag, plastic or tarpaulin, curing etc. complete. (Wooden planks / shuttering will not be allowed) Spec. No. : Bd.E.1 Page No. 287	CuM	3	4947.16	<b>14814.48</b>
6	Providing and laying in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including	CuM	5	6262.90	<b>31314.5</b>



	bailing out water, formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand				
7	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including centering, formwork, cover blocks, laying/pumping, compacting , curing , finishing and rougheningthem if special finish is to be provided and curing complete.(Excluding reinforcement and structural steel),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	CuM	3	13603.20	<b>40809.6</b>
8	Providing and fixing in position TMT - fE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	MT	0.5	76268.04	<b>38134.02</b>
9	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	MT	0.24	84634.48	<b>16926.89</b>
10	Providing internal cement plaster 20mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc.complete.	SqM	9	461.22	<b>4150.98</b>
11	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains	SqM	6	724.61	<b>4347.66</b>



	and curing for fourteen days scaffolding etc.complete.				
12	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to old plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.	SqM	6	69.12	414.72
13	Providing & laying prestressed concrete Cable trench covers 75 mm thick with 8 nos of 4 mm dia. HT wire & casting with M400 grade CC using contractor's own cement & compacted with 30MT hydraulic press machine incl. all taxes, loading, unloading transportation and placing them on cable trenches with all lead and lifts etc. complete. as directed by Engr In charge.	SqM	21	1831.51	38461.71
14	Conveying materials obtained from excavation including all lifts, laying in layers 20 cm to 30cm, breaking clods, dressing to the required lines, curves, grades and section for a lead of over 300m.to 500m from the site of excavation to the site of deposition as directed. Spec. No.: MORTH 305	CuM	46	60.78	2795.88
<b>Order value limited to Rs.265763.69 inclusive of all taxes.</b>					

  
**Executive Engineer**  
**400kVR.S.(O&M)Division**  
**Babhaleshwar**



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**

Name of Office	:	<b>Office of the Executive Engineer</b>
Office Address	:	400kV R.S.(O&M) Division, Babhaleshwar, A&P. Pimpri Nirmal, Tq. Rahata, Dist. Ahmednagar – 423107
Contact No.	:	02422 (O) 278173 (R) 278148 (Fax) 278153
Email Id	:	ee5130@mahatransco.in
Website	:	http://www.mahatransco.in

**Guideline for processing the SRM RFx Post GST Implementation**

- 1 RFx No :
- 2 E-enquiry NO : EE / 400kV R.S./Dn/Tech/N<sup>o</sup>80Dt:- 23-01-2020
- 3 Particulars : **Enquiry for Work of Construction of cable Trench & providing and fixing cable trays at 400KV Babhaleshwar substation under 400kV R. S. Babhaleshwar**
- 4 Estimated Cost : Limited to Rs 265763/-
- 5 Sale Period : 23.01.2020 00:00 Hrs to 30.01.2020 up to 24:00 Hrs.

**Guidelines for bidder :**

A) The Pricing Conditions have to be entered for all the Items. The % GST applicable (Tax Code) as per HSN/SAC has to be selected by the Bidder from General Data Tab under Item Details [Refer the below Table]. Alternatively, these changes can be easily carried out by Download/Upload Template functionality on the ResponsePage.

Sr. No	Vendor	Tax Code	Tax Rate	Description
1	Vendor within Maharashtra	T0	0%	GST Purchase 0%
2		T1	5%	GST Purchase 5% (SGST+CGST)
3		T3	12%	GST Purchase 12% (SGST+CGST)
4		T5	18%	GST Purchase 18% (SGST+CGST)
5		T7	28%	GST Purchase 28% (SGST+CGST)
6	Vendor Outside Maharashtra	T0	0%	GST Purchase 0%
7		T2	5%	GST Purchase 5% (IGST)
8		T4	12%	GST Purchase 12% (IGST)
9		T6	18%	GST Purchase 18% (IGST)
10		T8	28%	GST Purchase 28% (IGST)
11	Vendor within Maharashtra (In case of Reverse Charge Mechanism)	E0	0%	Reverse charge on expenses GST Cess
12		E1	5%	Reverse charge on expenses 5%(SGST+CGST)
13		E2	12%	Reverse charge on expenses 12%(SGST+CGST)
14		E3	18%	Reverse charge on expenses 18%(SGST+CGST)
15		E4	28%	Reverse charge on expenses 28%(SGST+CGST)



16	Vendor Outside Maharashtra (In case of Reverse charge mechanism)	E0	0%	Reverse charge on expenses GST Cess
17		E5	5%	Reverse charge on expenses 5%(IGST)
18		E6	12%	Reverse charge on expenses 12% (IGST)
19		E7	18%	Reverse charge on expenses 18% (IGST)
20		E8	28%	Reverse charge on expenses 28% (IGST)

A) After filling all the prices and Tax code, confirm all changes once again.

B) Save and submit the response before due date and time as per prevailing procedure. In case of any difficulty, please refer the revised version of "Guidelines to Submit eTenders", Contact MSETCL Contact Person indicated in the RFx or reach us at [sradmin@mahatransco.in](mailto:sradmin@mahatransco.in)

**Note:** - The above rates quoted in RFx are inclusive of taxes.

*Babhaleshwar*  
Executive Engineer  
400kVR.S.(O&M) Division  
Babhaleshwar