

**Maharashtra State Electricity Transmission Co. Ltd.**  
**EHV(O&M) Division, Baramati**

Ph: 02112 - 244776  
Fax: 02112 - 244775  
Email: [ee6230@mahatransco.in](mailto:ee6230@mahatransco.in)  
Web: [http:// www.mahatransco.in](http://www.mahatransco.in)

Urja Bhavan,  
Admin Bldg,  
Bhigwan Road,  
Baramati Pin- 413 102.

**Ref No: EE/EHV/O&M/DN/BMT/T/ 70**

**Date: 24.01.2020**

**E- Enquiry**

**Sub:** Work of re-wiring of residential staff quarters and replacement of metering box at staff colony at Baramati under EHV O&M Dn Baramati.

**Annexure –A Schedule..... Enclosed**

1. Due Date: The quotations complete in all respects, duly sealed & super scribed should be submitted to this office on or before **Dt: 03.02.2020 up to 16:00 Hrs positively.**
2. **Date of Opening :27.01.2020, If Possible**
3. Payment: 100% against completion of work.
4. Along with quotations following documents should be attached,
  - A. Valid Electrical contractor's license.
  - B. Valid registration under GST.
  - C. Valid PAN registration.
  - D. Valid Shop Act License or NOC from Local Govt. Body.
  - E. The Bidder must have experience for carrying out similar work Experience. (The experience certificate should be attached.)
5. List of similar works executed by the contractor elsewhere preferably with testimony from the concerned shall be attached with the documents.
6. All general /technical /commercial terms & conditions of the contract of MSETCL are applicable to this contract.

Undersigned reserves the right to accept or reject any quotations without giving any reason.

Thanking you.

Sd/-

**(Bhauso D. Ballal)**  
**Executive Engineer**  
**EHVO&M Dn. Baramati**

**Copy swrs to:** The Superintending Engineer EHVO&M Circle Solapur

**Copy to:** 1) Dy. Executive Engineer, 132kV Baramati.  
2) The Dy. Manager F&A EHV O&M DN.Baramati  
3) Notice Board  
*MF*

## Annexure –A

**Name of work: Work of re-wiring of residential staff quarters and replacement of metering box at staff colony at Baramati under EHV O&M Dn Baramati.**

Sr No	Item code	Description	Quantity	Rate	Amount
1	50004255	Dismantaling fan bell clock plug wiring. Dismantalling the existing light, fan, bell, clock independent plug point wiring with means at all types along with accessories etc. complete as per specification and as directed by Engineer incharge including collecting and stacking the material and disposed off as directed.	AS per actual		
2	50002440	Point wiring of 1mm <sup>2</sup> cu. Wire. Providing point wiring of good quality for light/fan/bell in 1 mm <sup>2</sup> copper wire in pvc casing capping with wire shock proof accessories such as ceiling rose/ sq box with 5A switches for table light etc.	AS per actual		
3	50002435	P & F plug point 16A 1 Ph sw/socket 2.5 mm <sup>2</sup> wire. Providing and fixing plug point wiring for single phase 16A pin socket and switch on PVC board with 2.5 sq.mm copper conductor PVC insulated wire with 16 SWg copper earth wire etc.	AS per actual		
4	50004220	Providing and fixing 16/20 Amp 415V main switch. Providing and fixing 16/20Amp 415V main switch of approved quality and make etc complete as directed by Engineer incharge.	AS per actual		
5	50002688	Earthing through 14 SWG wire. Providing earthing 14 SWG to outer lighting	AS per actual		
6	50004225	P/F power plug point PVC casing switch. Providing and fixing power plug point wiring with 16A indicating switch and 16A plug with 4 sqmm multistrand wire in casing capping and modular swtches mounted on surface box etc complete as directed.	AS per actual		
7	50002459	S&F Tubelight with electronic choke. Supply & Fixinf flurosent tube light set with electronic choke 40W (Da light) 1200mm 36/40 w etc complete	AS per actual		
8	50000420	WIR S/E bell. Supply and erection of bell.	AS per actual		
9	50002465	S&E Ceiling fan 1200mm. Supply and erection ceiling fan 1200mm sweep with double, ball bearing and with condensor, AC 230V 50 cycle 12mm sweep with necessary erection in position testing etc.	AS per actual		
9	50000491	P&F of Distribution box. Providing and fixing of distribution box on FTL tower with 60Amp incoming 1 no. and 50Amp outgoing 10 No. feeders	AS per actual		
10	50004812	P&F switch board. P&F switch board.	AS per actual		
11	50000416	WIR P/F Single pole MCB.	AS per actual		
12	50015500	S&E 3.5'Lx4.5'H wooden box . Supply and erection for wooden box size 3.5'Lx4.5'H feet and 12mm thickness with double door specially design approved by MSETCL	AS per actual		

13	50015501	S&E 4'Lx5'H wooden box . Supply and erection for wooden box size 4'Lx5'H feet and 12mm thickness with double door specially design approved by MSETCL	AS per actual		
14	50016900	Painting of wooden box with filler coat. Painting of wooden box any size filler coat with greay filler or liquid wood filler , transparent and bringing forward surface to smooth even finish	AS per actual		
15	50016905	S&E 50mm2 Cu Lug.	AS per actual		
16	50016904	S&E 4mm2 Cu Lug.	AS per actual		
		<b>Total in Rs.</b>			
		<b>Add CGST @ 9%</b>			
		<b>Add SGST @ 9%</b>			
		<b>Grand Total in Rs.</b>			

**1. Order Amount Limited for Rs. 2.00Lakhs only. (Inclusive of all tax)**

**2. Rates are exclusive of all taxes i.e GST extra as per prevailing rates.**

**(Shri. B.D.BALLAL)**  
**Executive Engineer**  
**EHV O&M Dn. Baramati**