

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenance Division Nashik

"Administrative Building", Block No.6, 1st floor, Racca Plot,

Old Saikheda Road, Jail Road, Nashik Road-422 101.

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

Date:-

1803

12 FEB 2020

e- Quotation

Sealed and superscripted e- quotations are invited for the work of **"Drilling the new bore well and providing 3 HP pumps at 220 KV Sonewadi & 220 KV Bhose (Belwandi), Dist:- Ahmednagar."** As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Drilling the new bore well and providing 3 HP pumps at 220 KV Sonewadi & 220 KV Bhose (Belwandi), Dist:- Ahmednagar.

The quotations should reach to this office on or before **24/02/2020** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop:(Technical Bid)

- Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government.
- GST/ GSTIN Registration Certificate.
- E.P.F. Registration Certificate – issued by competent authority of Govt.
- Experience of having successfully completed similar civil works.
- Payment of EMD Rs. 2500.00 to be made by bidder off-line only upto 14.00 hrs of **24/02/2020** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

(b) Documents in 2nd Envelop:(Price Bid)

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.

- 8) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 9) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 10) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)
Executive Engineer (Civil)
EHV Civil CCM Dn. Nashik.

. Copy s.w.r.t.-

- 1) The Chief Engineer EHV Projects cum O&M Zone, Nashik.
- 2) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer [Civil] EHV Civil S/Dn.-Ahmednagar.
- 2) The Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED

EHV Civil Construction Cum Maint. Division. Nashik.

Name of Work-Drilling the New Bore Well and providing 3HP pumps at 220KV Sonewadi and Belwandi Dist-Ahmednagar

Schedule "B"

Sr No.	Item of work	Qty	Rate	Add 18% GST	Total Rate	Unit	Amount
1	Drilling of 150mm diameter bore well in all type of soil starta including removal of soil and stacking it as directed. All as per GSDA specification.	100.00	403.00	72.54	475.54	Rmt	47554.00
2	Providing and lowering in bore well 160mm diameter heavy duty ERW "B" class P.V.C. pipe for casing to required depth. All as per GSDA specification and as directed.	15.00	645.00	116.10	761.10	Rmt	11416.50
3	Providing and erecting and giving test of 150mm dia 3HP submersible pump set 20 to 25 stages confirming to IS -8034 and motor confirming to IS-9283 with water proofing winding, pump shall be suitable for various delivery head and discharge with stainless steel pump shaft and bronze impeller. Motor suitable for working on 415V x +10% phase 50Hz, AC supply with cable guard trust. The pump set as shall be suitable for direct coupling with suitable suction strainer anti thrust /stream line non return valve. 10mtr submersible copper conductor cable 2 pair of erection clamp 65mm wide and 10mm thick shall be provided along with pump set with following accessories LT capacitor 1 to 20KVAR unit DOL starter 380 to 440 volt, 3 phase 50Hz with 40 volt cut coil and over load element upto 7.5 HP Ammeter, volt meter, 440 V main switch (Metal clad) 415V, 32 Amp rating M.S. Sheet 16 swg panel box of suitable size with locking arrangement and 2 coats of oil painting complete as directed. (Pump set of CALAMA / ATALANTA/KSB)	2.00	37672.00	6780.96	44452.96	Set	88905.92
4	Providing and fixing and erecting 3 core 2.5 Sq.mm PV sheathed flat flexible submersible type copper cable of finolex make including fixing position, testing etc complete.	150.00	126.00	22.68	148.68	Rmt	22302.00
5	Providing and laying in 32 mm diameter HDPE pipes with screwed sockets, joints, necessary fitting such as sockets, back nuts, elbows, bends, tees, reducers, enlargers, plugs, clamps etc. including necessary drilling hole in walls, slabs etc. and remaking good the demolished portion to restore the same in original condition neatly, testing etc. complete. (Prior approval of sample and brand by Executive Engineer is necessary before use) Spec. No. : Bd.V.5 Page No. 551	150.00	72.00	12.96	84.96	Rmt	12744.00

Sr No.	Item of work	Qty	Rate	Add 18% GST	Total Rate	Unit	Amount
6	Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	50.00	346.00	62.28	408.28	Rmt	20414.00
7	Providing and fixing screw down for 25 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	5.00	750.00	135.00	885.00	Nos	4425.00
8	survey for identification of bore hole spot	1.00	5303.00	954.54	6257.54	Job	6257.54
Total Rs.							214018.96
Total Rs.							214019.00


 Executive Engineer (Civil)
 EHV CCCM Dn. Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
 - Above.....% in words.....Of Estimated cost in Schedule "B"
 - Below.....% in words.....Of Estimated cost in Schedule "B"
- I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.