



MAHA TRANSCO



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Office of the Executive Engineer,
EHV Projects Division, MSETCL, Nasik
2nd Floor, Block No.08, New Administrative Building, Old Saikheda Road, Near Durga Mata
Mandir, Sailanibaba Bus Stop, Jail Road, Nashik Road, Nashik. 422 101.
Contact No.: 0253-2403141 (O), 2403143 (Fax).
e-mail: ee5610@mahatransco.in

EE/EHV/PROJ/DIV/NSK/Tech/

10-438-1

Date: 2 MAR 2020

Srm Re e-enquiry

To,

Sub: SRM Re e-enquiry for Balance work of 132KV bay at 220KV Bhose & 132KV Karjat SS for 132KV Bhose-Karjat line at risk & cost of M/s GE T&D India Ltd.

Ref: i) AdEE/SS/PROJ/SD/A.nagar/06 Dt 10.01.2020
ii) SRM e-enquiry EE/EHV/PROJ/DIV/NSK/Tech/289 Dt 13.02.2020

Dear Sir,

Online bids through Mahatransco SRM e-enquiry system from registered agencies in MSETCL SRM E-tendering system (website <https://srmetender.mahatransco.in>) are invited for Balance work of 132KV bay at 220KV Bhose & 132KV Karjat SS for 132KV Bhose-Karjat line at risk & cost of M/s GE T&D India Ltd

RFx No. 7000015368


Last date of bid is 10.03.2020

TERMS & CONDITIONS:

1. **Scope of work:** The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule-B**.
2. The rates should be quoted on firm quotation basis including labor charges, T&P etc. required for execution of the work, transportation charges, & taxes if any.
3. All the instruments, T&P, vehicles, labors etc. shall be arranged by agency. No T&P or labor will be provided by the MSETCL.
4. The Contractor should furnish details of i) Experience of work in EHV level, ii) Electrical Contractor License, iii) Shop Act, iv) GST Registration certificate. v) PAN, TAN. vi) EMD /Tender fee receipt proof etc. along with online bid.
5. Taxes will be applicable as per rule.
6. 10% Security Deposit is to be deposited in Cash/Crossed DD/Cheque before commencement of work. The same shall be refunded to you after the satisfactorily Completion of the work.
7. MSETCL will not be responsible If any damage is occurred to the contractor's equipment/T&P OR any accident to contractor's labours /personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.

8. The material should be supply from approved manufactures of MSETCL as per MSETCL standards & should be confirm to the relevant IS amendment to up to date.
9. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labour due to wrong operation shall be recovered from the bill.
10. Income tax will be deducted as per prevailing rules from the bill & a certificate to that effect will be issued to the contractor.
11. The work should be completed within 30 days from the date of handing over of clear work site, failure of such; penalty equal to ½ % per delayed week subject to the maximum of 10% of the ordered value will be levied.
12. The work should be strictly carried out as per standard specifications and up to the entire satisfaction of the Engineer-In charge.
13. The contractor will be abiding by the Rules & Regulations in force in respect of his employees & workmen under the Workmen's Compensation Act & the Contract Labour Act etc. He should be a registered contractor & documentary evidence of the same should be produced.
14. As per provision of 'Mumbai Mudrank Adhiniyam, 1958 clause No.34' an agreement on appropriate value of stamp paper shall have to be executed with MSETCL for execution of contract satisfactorily before commencing work. The amount of the fees for such an agreement shall be borne by contractor.
15. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved by the undersigned.
16. The quantities enumerated in attached Schedule 'B' are approximate & payment will be made against actual executed quantities.
17. The rates quoted should be valid for 60 days.
18. Idle charges for any reason will not be accepted.
19. Not contained herein all other terms and conditions of MSETCL will be applicable to this enquiry
20. In case of any dispute regarding this contract, the jurisdiction of the court will be Nashik.

Thanking you,

Yours faithfully,

Executive Engineer
EHV Projects Division
MSETCL, Nasik.

Copy s.w.r.to,

The Superintending Engineer, EHV Projects Circle, MSETCL, Nasik.

Copy to,


- 1) The Manager (F&A), EHV Projects Division, MSETCL, Nasik.
- 2) The Addl EE, EHV SS projects Sub division, Ahmednagar.
- 3) Notice Board.

Schedule B

Balance work of 132KV bay at 220KV Bhose & 132KV Karjat SS for 132KV Bhose-Karjat line at risk & cost of M/s GE T&D India Ltd.

Sr. No.	Particular	Unit	Qty	Unit Rate (Rs)	Total Amount (Rs)
SUPPLY PORTION					
1	Terminal Connector-C18a	Nos	1		
2	Terminal Connector-C15a	Nos	2		
3	Terminal Connector-C10b	Nos	2		
4	T-Connector for 0.2 panther on main & 0.4 Zebra on Tap	Nos	16		
5	0.4 ACSR Zebra Conductor	Km	0.14		
6	70kN Disc Insulator (Antifog type)	Nos	9		
7	1.1kV PVC FRLS 2CX2.5 Cu Ar Ctrl Cable	Km	0.07		
8	1.1kV PVC FRLS 12CX2.5 Cu Ar Ctrl Cable	Km	0.035		
9	SSN H/W through Drop Clamp - 0.4 Single Zebra	Nos	2		
10	145KV CT 800-400-200/1A, LT, 0.2S class	Nos	1		
	TOTAL SUPPLY PORTION				
ERECTION PORTION					
1	145KV CT 800-400-200/1A	Nos	1		
2	Conductor Jumpering	Nos	10		
3	laying , Dressing & clamping of 2Cx2.5Sq. Mm control cable	Km	0.07		
4	laying , Dressing & clamping of 12Cx2.5 Sq.mm control cable	Km	0.035		
5	Cable Termination at both ends (inclusive of glands, lugs, ferrule) of 2cx2.5 Sq.mm control cable	Nos	2		
6	Cable Termination at both ends (inclusive of glands, lugs, ferrule) of 12Cx2.5 Sq.mm control cable	Nos	1		
	TOTAL ERECTION PORTION				
	TOTAL (SUPPLY + ERECTION)				

Note- The quantities enumerated in Schedule 'B' are approximate.


 Executive Engineer
 EHV Projects Division
 MSETCL, Nasik.