

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)
EHV Civil Construction cum Maintenances Division Nashik
"Administrative Building", Block No. 6, 1st floor, Racca Plot,
Old Saikheda Road, Jail Road, Nashik Road-422 101.
Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

Date:-

No 3 9 2 =

4 MAY 2020

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Balance electrification work for Rest House (Phase-II) at Racca Plot, MSETCL premises, Jail Road, Nashik Road, Nashik." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Balance electrification work for Rest House (Phase-II) at Racca Plot, MSETCL premises, Jail Road, Nashik Road, Nashik.

The quotations should reach to this office on or before **11/05/2020** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop:(Technical Bid)

- (i) Valid Certificate of Electrical Contractor License.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) Experience of having successfully completed similar types of works.
- (iv) PAN card.
- (v) Shop Act certificate.
- (vi) Payment of **EMD Rs. 3000.00** to be made by bidder off-line only upto 14.00 hrs of **11/05/2020** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

(b) Documents in 2nd Envelop:(Price Bid)

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **30 days** from the date of handing over the site to commence the work, failing of which a penalty at $\frac{1}{2}\%$ per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)
Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.

Copy s.w.r.to.-

- 1) The Chief Engineer EHV Projects cum O&M Zone, Nashik.
- 2) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) The Dy. Manager [F&A] Dn. Office, Nashik.
- 2) Master File/Notice Board.


MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV CIVIL CONSTRUCTION DIVISION, NASHIK

Name of work:-Balance electrification work for Rest House (Phase-II) at Racca Plot, MSETCL premises, Jail Road, Nashik Road, Nashik

SCHEDULE 'B'

Sr.	Description	Qty.	Unit	Rate	Amount
1	Supplying and erecting LED square / circular 13 to 15W down lighter having pressure die-cast aluminum housing, opal translucent cover, mounting arrangement with board for surface type or spring loaded mounting clips for flush type complete.	13.00	EA	1189.00	15457.00
2	Supplying, fixing and commissioning MCB type change over switch 4 pole, 63A with 3 positions (I-O-II) with centre off position as per specification no. SW-SWR/MCBCOS	1.00	EA	2757.00	2757.00
3	Supplying and erecting iron, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials duly painted with one coat of red oxide and two coats of enamel paint to match the switchgears or as per directions by the authority.	12.00	KG	137.00	1644.00
4	Supplying and erecting 525 V 3 phase, 50 Hz., MPP type capacitor having minimum overcurrent capacity of 1.8 In, peak inrush current capacity 300 In and minimum life 150000 hours kVAR bank of metalised polypropylene condensers (MPP) with the standard capacities of 2, 3, 5, 7, 10, 12.5 and 15 kVAR units of P.F. correction for operation on 3 phase 50 Hz. with externally discharging resistances, earthing terminals and built on angle iron or channel iron frame work and provided with terminal cover box complete erected on provided iron bracket or on floor duly tested by licensee.	20.00	KVAR	395.00	7900.00
5	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire with 1x1.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	60.00	Mtr	56.00	3360.00
6	Supplying & laying HMS PVC conduit 25 mm dia with necessary accessories in RCC work/false ceiling/false flooring	55.00	Mtr	105.00	5775.00
7	Supplying and erecting street light Wall bracket made from 40 mm. dia 'B' class G.I. pipe 1.2 m in total length complete as per specification no. FG-BKT/WB	4.00	EA	672.00	2688.00
8	Supplying and erecting LED street light fitting suitable above 26W to 36W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/FLS2.	20.00	EA	2612.00	52240.00
9	Supplying and erecting LED street light fitting suitable for 60W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/FLS-2.	4.00	EA	5261.00	21044.00
10	Supplying and erecting LED street light fitting suitable for 100W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/FLS-2.	1.00	EA	8235.00	8235.00
11	Supplying and erecting LED flexible strip light 5m length upto 25W conforming IP 65 of any colour with driver complete	6.00	EA	2053.00	12318.00

Sr.	Description	Qty.	Unit	Rate	Amount
12	Supplying Integrated LED emergency type rechargeable table lamp of 4.5W with battery of 2000 mAh capacity with continues backup of 3hrs including with charging cord suitable for 230V AC power supply	12.00	EA	1252.00	15024.00
13	(Around Bed) Supplying and erecting moon type decorative wall/ceiling mounted fixture including LED upto 12W circular/square type with opaque diffuser and electronic driver including bracket	12.00	EA	1653.00	19836.00
14	Providing and erecting bracket fan 400 mm. sweep A. C. 230 volts 50 cycles 1350 R.P.M. Oscillating type, plastic or metal blades chrome plated guard with regulator and moisture proof treatment to winding and with 'E' class insulation.	13.00	EA	1943.00	25259.00
15	Supplying and erecting Integral post top lantern fixtures (mushroom type) suitable for upto 12W LED lamp consisting of clear acrylic top cover, cast aluminium pole cap complete with accessories on provided pole / bracket as per specification No. FG-ODF/PTL (Gate Light)	4.00	EA	1918.00	7672.00
16	Supplying & erecting jelly filled armoured telephone copper cable 20 pair with 0.5 mm dia. laid in provided trench as per specification No. WG-TW	34.00	RMT	179.00	6086.00
17	Supplying and laying (including excavation of suitable width & depth up to 90 cm) 50 mm outside dia. double wall corrugated pipes (DWC) of HDPE for enclosing cable below ground/road surface, to required depth complete.	13.00	RMT	184.00	2392.00
18	Supplying, erecting & commissioning junction box suitable for 20 pairs as per specification No. WG-TW	1.00	EA	742.00	742.00
19	Supplying, installing, testing & commissioning digital (hybrid) type EPABX of 6 x 16 extensions complete.	1.00	EA	39468.00	39468.00
20	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	21.00	RMT	36.00	756.00
21	Supplying and erecting Ceiling rose / Batten holder / Slanting holder / hanging cord switch / hanging bell push / pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box	10.00	EA	33.00	330.00
22	Supplying and erecting PVC Surface modular switch box with double mounting plate for 2 modules duly erected.	13.00	EA	121.00	1573.00
23	Supplying and erecting ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	13.00	EA	107.00	1391.00
				Total Rs.	253947.00
				Add GST 18%	45710.46
				Total Rs.	299657.46
				Say Rs.	299657.00


Executive Engineer (Civil)
EHV CECM Dn. Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.