

**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./ABD//Tech/

635

Date:-

13 AUG 2020

e- Quotation Enquiry

To,

.....
.....
.....

Sub: Cleaning & Pest Control of surrounding premises of class-II type quarters and arrangement for drain of water collected in chambers at 132 KV Chikalthana S/S, Dist. Aurangabad.

Dear Sir,


Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or before dated 20.08.2020 up to Time 16.30 Hrs.

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within (30) days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost

- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division I Dist: Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to Deposit as 5% of work order value as security deposit in cash or DD of any nationalized Bank within 07 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The contractor has to pay **earnest money of Rs. 2,000.00/-** in cash/In form of DD/FDR of any Nationalized Bank in favor of Executive Engineer (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. If the EMD of required amount is not found in the envelop the quotation will be rejected
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is **Rs. 1,72,681.20** only. (Inclusive of all Taxes)
- 23) The Contractor has to submit the Valid Civil Works Registration, GST Registration, Civil Works Experience Certificate and EMD Paid Receipt and PAN card at the time offer submission as mandatory documents.

Encl: Schedule 'B'


(S. P. Kamble)
Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Copy s.w.r.s. to:

1. The Superintending Engineer (C) EHV CCCM Circle, Aurangabad.

Copy To:

1. The Dy. Manager (F&A), EHV CCCM Division, Aurangabad.


**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad.Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.inCIN: U40109MH2005SGC153646



Name of Work: Cleaning & Pest Control of surrounding premises of class-II type quarters and arrangement for drain of water collected in chambers at 132 KV Chikalthana S/S, Dist. Aurangabad.

Estimated Amount: - **Rs. 1,72,681.20** (Inclusive of All Taxes)



(S. P. Kamble)
Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Quotation for Works

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.


Signature of the contractor

Full Address:

Schedule B

Name of Work: Cleaning & Pest control of surrounding premises of Class-II type quarters and arrangement for drain of water collected in chambers at 132 KV Chikalthana S/S, Dist. Aurangabad.

Sr No.	Description	Quantity	Rate (Inc. GST)	Unit	Amount (Inc. GST)
10	Excavation for foundation in earth, soils of all types sand, gravel and soft murum including removing the excavated material upto a distance of 100 m within the yard area and all lifts, stacking and spreading as directed, dewatering, shoring, strutting and preparing the bed for the foundations and necessary back filling, ramming, watering (Including shoring and strutting) etc. complete. For All lift Spec. No. BD.A 1 Page No.259	13.000	157.00	Cum	2408.38
20	Excavation for foundation in hard murum and boulders including removing the excavated materials up to a distance 100 m within the yard area and all lifts stacking and spreading as directed dewatering preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. For All Lift Spec. No. BD.A 3 Page No. 259	13.000	191.00	Cum	2929.94
30	Providing general pest control services to the building & surrounding premises to control the nuisance of cockroaches, lizards, pin bores and other insects etc.	1200.000	5.00	Sqm	7080.00
40	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc.	1.000	268.00	Cum	316.24
50	Conveying materials obtained from road cutting/Dismantling of brick, RCC work including all lifts, laying in layers of 20 cm to 30 cm breaking clods, dressing to the required lines, curves, grades and section, of over 50 m to 300 m.	1.000	139.00	Cum	164.02
60	Providing and laying cement concrete pipe of IS 458:2003 NP 2 class of 450 mm diameter in proper line, level and slope including providing and fixing collars in cement mortar 1:2 and curring etc. complete.	35.000	1657.00	Rmt	68434.10
70	Providing and constructing Brick Masonry/Fly ash Inspection Chamber 90 cm x 60 cm including 1:4:8 cement concrete foundation, 1:2:4 cement concrete channels, Brick Masonry, plastering from inside and airtight RCC lid with frame fixed in cement concrete, curring, testing etc. Complete	3.000	12583.00	No	44543.82
80	Labour charges for removing grass, thorney shrubs, Jungli shrub, Kubabul and alike grass along roadside making the ground clean by showel and Phavaras etc. Complete	6200.000	6.00	Sqm	43896.00
90	Providing services of Mazdoor Unskilled (Male) labour for the works to be attended in S/Yard other than the work considered in estimates etc completed including all taxes.	5.000	493.00	Nos	2908.70
	Total				172681.20


(S. P. Kamble)
Executive Engineer (C)
EHV CCCM Division, Aurangabad.