

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED.

Name of Office : Office of The Executive Engineer, EHV (O&M) Division, Aurangabad
Office Address : Old Power House Campus, Jubilee Park,
Dr. Ambedkar Road, Mill Corner, Aurangabad-431001
Contact No : 0240-2334280(O), 2343134 (R)
E-mail Id : eeabd@yahoo.com ; ee2110@mahatransco.in
Website : www.mahatransco.in

No.EE/EHV (O&M)/A'bad/Tech/T / No 1082

Date: 24 SEP 2020

To,		

Sub- Enquiry for providing and fixing yard lightning and focus for LM with fixture at 220KV Jalna S/s under EHV (O&M) Division, Aurangabad.

Ref: Addl.EE/220KV S.s/JLN/No. 198 dtd. 20.06.2020

Dear Sir,


Sealed firm quotations are invited for above works as per Annexure – A enclosed herewith,
Subject following terms and conditions:

TERMS & CONDITIONS:

- Sealed envelops must be marked as quotation for providing and fixing yard lightning and focus for LM with fixture at 220KV Jalna S/s under EHV (O&M) Division, Aurangabad
- Quotation should reach this office within 7 days from the date of dispatch of this enquiry letter and will be opened on the same day if possible.
- Work Completion period may be clearly mentioned.
- Rate should be valid for 90 days.
- Rates should be quoted both in figures and words
- Earliest work completion period will be appreciated.
- It is requested to quote your GST registration reg. No.
- Documents required:-
 - 1) Shop Act
 - 2) Pan Card
 - 3) GST Reg & returns
 - 4) IT returns
 - 5) experience
- The under signed reserves the right to reject any or all the quotations without assigning and reason thereof.

Thanking you,

yours faithfully,



**Executive Engineer,
EHV (O&M) Division, MSETCL,
AURANGABAD.**

Encl: - Annexure-A

Copy.s.w.rs.to:-


- 1) The Superintending Engineer, EHV (O&M) Circle, MSETCL, A'bad.

Copy to:-

- 2) The Dy. Manager (F&A), Trans (O&M) Division, MSETCL, A'bad.
- 3) Notice Board.

Subject:- Work of Providing & Fixing Flood Lighting on High Mast Towers & yard lightning at 220KV Jalna S/s under EHV (O&M) Division, Aurangabad

Sr.No.	Perticulers	Unit	Quantity	Material Rate	Labour Rate
1	Supplying and erecting flood light, luminaries, suitable for 400W HPSV lamp, complete with accessories on provided bracket as per specification number FG.DF/GFL	No.	4		
2	Supplying and erecting flood light, luminaries, suitable for 250W HPSV lamp, complete with accessories on provided bracket as per specification number FG.DF/GFL	No.	2		
3	supplying and erecting CFL street light fitting suitable for 1X 75W CFL lamp with accessories complte on provided bracket	No.	5		
4	Supplying and erecting VPIT heavy duty copper wound ballast for 230V, 400W HPSV /MV /MH as per specification number FG.FG/AS4	No.	20		
5	Supplying and erecting condensor for MV /SV/MH clamp 400W, 230V as per specification number FG.FG/AS7	No.	20		
6	Supplying and erecting HPSV lamp 3-Pin BC/Screwd cap head / pin type 230V 400W SONT type	No.	20		
7	Supplying and erecting VPIT compound heavy duty copper wound ballast for 230V for 250W HPSV / MV /MH as per specification number FG.FG/ AS5	No.	8		
8	Supplying and erecting condensor for MV /SV/MH clamp 250W, 230V as per specification number FG.FG/AS7	No.	8		
9	Supply and erecting HPSV lamp 3 out BC Screwed cap head/pin type 230V 250M SON T type.	No.	8		
10	Supplying and erecting marking SPMCB 6A to 32A B series (for lighting) in provided distribution board as per specification no. SW/SWR/MCB	No.	28		
11	Supplying and erecting marking FPMCB 40A to 63 A (for lighting) in provided distribution board as per specification no. SW/SWR/MCB	No.	4		
12	Supplying and erecting tripple pole iron clad HC type rewirable fuse and switch 415/ 500V , 52A with neutral link on angle iron/ GI frame as per specification no. SW/SW. R MT	No.	4		
13	Supplying and erecting and terminating PVC armoured cable 2 core , 4 Sqmm copper conductor continious 5.48Sqmm (12SWG) GI earth wire complete erected with gland and lugs and wall/ truses / pole or led in provided trench/ pipe as per specification no. CPLT/CU	Mtr	120		
14	Supplying and erecting and terminating PVC armoured cable 2 core , 2.5 Sqmm copper conductor continious 5.48Sqmm (12SWG) GI earth wire complete erected with gland and lugs and wall/ truses / pole or led in provided trench/ pipe as per specification no. CPLT/CU	Mtr	80		
15	Supplying and erecting and terminating armoured cable 4 core , 10 Sqmm Al conductor continious 5.48 Sqmm (12SWG) GI earth wire complete erected . (7-1-28)	Mtr	150		
16	Supplying and erecting ignitor suitable for 230V HPSV lamp 70/150/250/400 W as per specification number FG.FG/AS6	Nos.	25		
17	Supply and erecting brass lamnp holder complete	Nos.	25		
18	Supply and erecting metal clad box on high mast tower form protection from rain water	Nos.	10		
19	Repairing of 70/ 150/250/400W integral type lumanaries	No.	28		



Executive Engineer
EHV O&M Division
MSETCL, Aurangabad