

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD
(CIN NO- U40109MH2005SGC153646)

Office of The Executive Engineer MSETCL EHV O&M, Division,
Near Market Yard, Bapat Camp, Kolhapur
Tal: - Karvir, Dist-Kolhapur-416 005
E-mail: - ee3210@mahatransco.in, Phone No. 0231-2651529.

EE/EHVO&M/DN/KOPT/LP/899

Date:24.09.2020.

E-Enquiry

Sub:- E-Enquiry for Rewinding & repair of 200 KVA & 100 KVA station transformer at 110kV Kothali substation under EHV O&M Division Kolhapur.

Dear Sir,

Rates are called through quotation complete in all respects, dully sealed & superscribed submitted to this office for the works mentioned in Schedule 'A' on or before upto 05/10/2020 @ 15:00 Hrs. The other terms and conditions are as mentioned below.

1. **PRICES:** - The rates will be accepted as per Schedule A rates with work at 110kV Kothali substation under EHV O&M Division, Kolhapur.
2. **TAXES:** - Rates should be quoted in % only. Rates in Schedule A are Inclusive of all Taxes.
3. **WORKING PERIOD:** Work should be completed within 3 months from the date of issue of work order.
4. **VALIDITY OF OFFER:** The offer should be valid for our acceptance for a period of 60 days from the due date of opening.
5. **GUARANTEE:** - The works should be guaranteed against bad workmanship, for a period of 1 year from date of work completed and this undertaking may be sent along with the bill without fail. For any defects in workmanship, you will have to give free service within 7 days from the date of intimation within guarantee period.

Thanking You.

Executive Engineer
EHV O&M Division, Kolhapur

Encl : 1. Schedule 'A'

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD
(CIN NO- U40109MH2005SGC153646)

Office of The Executive Engineer MSETCL EHV O&M, Division,
Near Market Yard, Bapat Camp, Kolhapur
Tal: - Karvir, Dist-Kolhapur-416 005
E-mail: - ee3210@mahatransco.in, Phone No. 0231-2651529.

Terms & Condition

- 1) Security Deposit: - You will have to pay Security Deposit 5% of order value before issue of work order.
- 2) Supervision of Work: - The work shall be carried out under the Supervision of Sub-station in charge.
- 3) Scope of work –As per schedule A & as per the instruction of concern substation In-charge. Oil if any provided by METCL.

Sr. No:-	Scope of work
1	Reswinding of HV. LV Coils
2	Reinsulation of HV, LV Coils
3	Providing 33kV HV Bushings
4	Providing of 440V LV Bushing
5	Providing MOG
6	Providing Breather
7	Transformer Body repair, if any
8	Transformer internal & external Painting

- 4) Penalty: - In case of work is not completed as per schedule in specified time, the contractor shall be liable to pay penalty @ ½ % per week subject to maximum 10% of order value.
- 5) You have to provide experts for this works.
- 6) All required T&P/ Manpower should be arranged by you.
- 7) You shall abide with all Govt. rules, regulations, status for this work including workman compensation act etc.
- 8) Workmanship - The workman ship and materials used for this work should be of best quality and confirming to the Indian Standard Specification. The bad quality material will be rejected.
- 9) Agreement Bond: - You have to execute the agreement bond on Govt. Stamp paper of Rs. 500/-before issue of work order. Cost of stamp paper will be borne by you only.
- 10) Validity of Order: - The order should will be valid for period of 12 months from the date of issue of order or exhausting the order amount whichever will be earlier. 3 Days will be reckoned for Transit of this order.

- 11) Accidents:-Any accident to your labour during the execution of work, any loss/ damage to MSETCL property will be on your account and you will have to make it good at your cost.
- 12) Insurance:-The Insurance of your labour at your cost only. If fail the compensation / Claim arrears will be at your risk
- 13) MSETCL will not provide accommodation to your technicians / Supervisor, Labour, The transportation of materials / labours will have to be done at your cost.
- 14) Payments:-100 % payment against bill after satisfactory work completion & SAP recording will be paid, subject to availability of funds and by Division Office.
- 15) In case you fail to carry out the work in part or full, the balance work will be carried out through other agency and difference in cost will be recovered from your bill, Security Deposit.
- 16) All disputes / differences arising under/ out of or in connection with the contract shall be subject to the exclusive jurisdiction of Kolhapur court only.
- 17) The MSETCL Terms and Conditions of work contract are applicable for this work.
- 18) 1% labour cess & 2% GST TDS will be deducted from your bills.
- 19) Monitoring of Order amount:- You should have to monitor work order amount. If the work exceeds beyond work order amount, excess amount will not be paid at any cost.
- 20) Undersigned reserve the right to cancel order in part or full at any time without giving in notice.

Note Following documents should be Submitted with quotation only :

Sr. No.	Particular
1	Registration under GST
2	Proof regarding Income Tax Return for the AY 2019-20.
3	Certificate having successfully completed of similar type of works/Work order from an authority similar to the rank of Executive Engineer & equivalent.
4	PAN Card copy.

**Executive Engineer
EHV O&M Division, Kolhapur**

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD
(CIN NO- U40109MH2005SGC153646)

Office of The Executive Engineer MSETCL EHV O&M, Division,
Near Market Yard, Bapat Camp, Kolhapur
Tal: - Karvir, Dist-Kolhapur-416 005
E-mail: - ee3210@mahatransco.in, Phone No. 0231-2651529.

Rewinding & repair of 200 KVA & 100 KVA station transformer at 110kV Kothali substation under EHV O&M Division Kolhapur.

Schedule A

Sr. No:-	Particulars of Work	Unit	Qty	Rate per unit Incl. GST+Labour cess	Quote Rates in % Above/Below /At par
A) Service Part					
1	Charges for rewinding & repair of 200 KVA station transformer:: Dismantling of transformer, rewinding of HV coils using new conductor, reinsulation of all LV coils, replacement of all HV & LV rod & packings, reassembly, repainting & testing	No.	As per Actual	80446.50	
2	Charges for rewinding & repair of 100 KVA station transformer:: Dismantling of transformer, rewinding of HV coils using new conductor, reinsulation of all LV coils, replacement of all HV & LV rod & packings, reassembly, repainting & testing	No.	As per Actual	66144.90	

Note:

- 1) Above rates are Incl. of Labour cess @ 1% & GST @ 18%.
- 2) Please quote rates in % basis.
- 3) Quantity may vary as per site situation.

Executive Engineer
EHVO&M Division Kolhapur.