



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)
EHV Civil Construction cum Maintenances Division Nashik
"Administrative Building", Block No. 6, 1st floor, Racca Plot,
Old Saikheda Road, Jail Road, Nashik Road-422 101.
Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

990

Date: 9 NOV 2020

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Work of Carrying out detailed survey with total station machine for preparing update layout of various Sub stations under EHV CCCM Sub Division-I, MSETCL, Nashik, Dist:- Nashik (2nd call)." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Work of Carrying out detailed survey with total station machine for preparing update layout of various Sub stations under EHV CCCM Sub Division-I, MSETCL, Nashik, Dist:- Nashik (2nd call).

The quotations should reach to this office on or before 17/11/2020 up to 15.00 Hrs


- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.
- a) **Compulsory Primary Documents in 1st Envelop:(Technical Bid)**
 - (i) Shop Act certificate.
 - (ii) PAN card.
 - (iii) GST/ GSTIN Registration Certificate.
 - (iv) Experience of having successfully completed similar types of works.
 - (v) Payment of **EMD Rs. 3000.00** to be made by bidder off-line in cash only upto 14.00 hrs of 17/11/2020 in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope
- b) **Documents in 2nd Envelop:(Price Bid)**
 - i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **30 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A

- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.**

Copy s.w.r.to.-

- 1) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer (Civil) EHV CCCM Sub Division Nashik-I.
- 2) Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

EHV CCCM DIVISION, NASHIK

SCHEDULE 'B'

Name of the Work:- Carrying out detailed survey with TOTAL STATION machine for the updated layout of various Sub station under EHV CCCM Sub-Division-1, MSETCL Nashik, Dist Nashik (2nd call).

Sr. No.	Description of Item	Qty	Rate	GST 18%	Total	Unit	Amount
1	Carrying out detailed survey with TOTAL STATION machine at various sub-station under EHV CCCM sub-division I, Nashik which include following I) Taking details of all bends on the fencing / compound wall. II) All the permanent / temporary structure in premises like buildings, store sheds, transformers plinth, cable trenches, switch yard Gantry/equipment foundation and, control room, road, Gate, culvert, trees, poles, gardens, lawns, watchman cabin, pipeline, bore well stepwall, water tank, septic tank, oil tank, Employee quarter, colony area MSEDCL area, towers and demarking the details open space, parking as MSETCL premises in different colors. All the distances / areas must be shown on drawing in separate table also provide the TBM at C/R plinth, yard level, Road Type, Compound wall distance from the highway etc. complete The rate is inclusive of all necessary material, labours, lead, etc complete as directed by Engineer In-Charge.	46.00	4898.00	881.64	5779.64	Hect.	265863.44
2	Supplying 3 sheets of each sub-station on A0, survey work in colour on paper media in suitable scale & 3 soft copies in AutoCAD	17.00	1515.00	272.70	1787.70	per substation	30390.90
Total Rs.							296254.34
Say Rs.							296254.00


Executive Engineer (Civil)
EHV CCCM Division Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.