

Tender for Operations and maintenance

Information

RFx number:	7000017819
Publication:	Public RFx
Version:	2
RFx Name:	Cable pulling work at 400KV WRR Dn
Tender Subject:	WORK OF UPLIFTING OF EXISTING VARIOUS CONTROL & POWER CABLES IN CB, CT, CVT, ISOLATOR BOX,
Bid Submission:	19.11.2020
Funded By:	
Tender Fee Inc. GST:	525.00 ₹
Estimated Cost:	2,000,000.00 ₹
Basis of Prices:	
Percent Based Bid:	Yes
EMD Cost:	20,000.00 ₹
Tech Bid Open:	19.11.2020 11:00:00
Price Bid Open:	19.11.2020 15:00:00
Contact Person:	EE-8554989278, DYEE-8554993202

Additional Requested Information:

- Average Annual financial turnover during the last 03 years, ending 31st March of the previous financial year, should be at least 50 % of the estimated cost. Submit ONLY turnover certificate of C.A. (essential)
- Experience condition as per TQR sr . no.b
- Proof of Goods & Service Tax Registration (GSTIN Registration)
- Proof of Registration of Firm under Bombay shop & Establishment Act.
- Copy of SSI/NSIC Certificate with Memorandum (if applicable).The Registration Certificate as submitted by Micro and Small Enterprises should be VALID on the date of submission of bid and the validity of the same should be certified by the Chartered Acc
- Income Tax Returns of last any 03 years (2018-19/2019-20/2017-18) & Copy of PAN card.
- Undertaking of contractor as per Annexure A, Annexure I & Annexure G should be submitted.
- Valid Electrical License Certificate.

Attachments:

- TENDER DETAIL - TENDER BOOKLET
- AMENDMENT - EXTENSION E-TENDER

Tender for Operations and maintenance



Information

RFX number: 7000017819

Version: 2

RFX Details:

(*Amount in ₹)

Item	Item category Product no.	HSN/SA C No.	Description	Qty	Unit Rate	Amount
1	Outline	995461	UPLIFTING OF CABLES AT 400KV WARORA	1.000 AU	--	1879459.71
1.AA	Service 50004137	995478	Collecting screening existing metal Collecting & screening existing metal with separate out dust etc. from metal and stacking the selected metal includes all leads & lifts etc. as directed for excavation of buried tensioned live control & power cable pipe. by Manual method (size 1.8 mtr width X 0.3 mtr depth X 1.0 mtr length)	1,285.20 0 m ³	133.48	171548.50
1.AB	Service 50008575	995428	Excavation&Disposal of Excavate Material Excavation for opening & uplifting of buried tensioned live control & power cable pipe. (size 0.6 mtr width X 1.6 mtr depth X 1.0 mtr length) FOR BC SOIL	1,142.40 0 m ³	361.12	412543.49
1.AC	Service 50014564	995428	Pulling of Casing, Conduit & Cu Cable Pulling of buried tensioned live control & power cable pipe by Manual method with re-fixing the pipe with control & power cable in proper line level & position for releasing cable tension as directed Engineer In Charge.#	2,380.00 0 RMT	225.25	536095.00
1.AD	Service 50000268	995428	Spreading of Graded Stone Metal Metal spreading after laying of pipe with cable & back filling of soil & cleaning of side by removing of waste balance material & its disposal to outside switchyard area as directed by engineer incharge# (size – 1.8 mtr x0.3depthx1.0 length)	1,285.20 0 m ³	166.85	214435.62
1.AE	Service 50017911	995428	P&L in situ CC M10 (1:3:6) M10 (1:3:6) concrete bedding for placing of pipes.	71.400 m ³	6620.45	472700.13

Tender for Operations and maintenance



Information

RFX number: 7000017819

Version: 2

Item	Item category Product no.	HSN/SA C No.	Description	Qty	Unit Rate	Amount
1.AF	Service 50011680	996912	Prov. Earthing to Eqpt. Structure Earthing of equipment / support structure with provided GI Flat with bending / fabrication welding etc. making it flush with support str. / equipment as directed with connecting the same with required size nut bolts (to be provided by the agency)	300.000 EA	232.40	69720.00
1.AG	Service 50004551	995461	Laying,Dress&Clamping 10/12Cx2.5mm ² Cable Laying,Dress&Clamping 10/12C/19cx2.5mm ² Cable	1.000 RMT	29.80	29.80
1.AH	Service 50004552	995461	Laying,Dress&Clamping 4/5Cx10mm ² Cable Laying,Dress&Clamping of 4C/7cx2.5mm ² Cu Ar Cable	1.000 RMT	22.64	22.64
1.AJ	Service 50004553	996912	Laying,Dress&Clamping 2Cx2.5mm ² Cable Laying,Dress&Clamping 2Cx2.5mm ² Cable	1.000 RMT	14.30	14.30
1.AK	Service 50013053	995461	Termination 19Cx2.5mm ² Cu Ctrl Cable Termination 19C/12cx2.5mm ² LT Cable	1.000 EA	526.78	526.78
1.AL	Service 50013056	995461	Termination 10Cx2.5mm ² Cu Ctrl Cable Termination 10Cx2.5mm ² Cu Ctrl Cable	1.000 EA	438.58	438.58
1.AM	Service 50013055	995461	Termination 7Cx2.5mm ² Cu Ctrl Cable Termination 7Cx2.5mm ² LT Cable	1.000 EA	338.47	338.47
1.AN	Service 50002107	995469	Termination 4Cx2.5mm ² LT Cu Ctrl Cable Termination 4Cx2.5mm ² LT Cu Ctrl Cable	1.000 EA	303.91	303.91
1.AP	Service 50014781	995469	Termination 2Cx2.5mm ² Cu Ar Ctrl Cable Termination 2Cx2.5mm ² Cu Ar Ctrl Cable	1.000 EA	237.17	237.17
1.AQ	Service 50013947	995462	P&L 100mm Ø PVC pipe weep hole Providing and laying weep holes of 100mm diameter PVC pipe	1.000 RMT	505.32	505.32

(*Unit Rate mentioned is inclusive of all taxes)

Tender for Operations and maintenance



Information

RFx number: 7000017819

Version: 2

Annexure - I

(* NR is for Invalid Condition)

Item	Product No.	HSN/SAC	GST App. in %	Item type	Conditions*
1		995461	18.00	E	
1.AA	50004137	995478	18.00	E	EXW,
1.AB	50008575	995428	18.00	E	EXW,
1.AC	50014564	995428	18.00	E	EXW,
1.AD	50000268	995428	18.00	E	EXW,
1.AE	50017911	995428	18.00	E	EXW,
1.AF	50011680	996912	18.00	E	EXW,
1.AG	50004551	995461	18.00	E	EXW,
1.AH	50004552	995461	18.00	E	EXW,
1.AJ	50004553	996912	18.00	E	EXW,
1.AK	50013053	995461	18.00	E	EXW,
1.AL	50013056	995461	18.00	E	EXW,
1.AM	50013055	995461	18.00	E	EXW,
1.AN	50002107	995469	18.00	E	EXW,
1.AP	50014781	995469	18.00	E	EXW,
1.AQ	50013947	995462	18.00	E	EXW,

(* PFQ -> Packing and Forwarding Per Quantity FRQ-> Freight Per Quantity FR%-> Freight in Percentage,
 EXW ->Ex-Works (Basic Price), PFP-> Packing and Forwarding in Percentage, INQ-> Insurance Per Quantity,
 INP -> Insurance in Percentage, DISCQ-> Discount Per Quantity, DISCP->Discount in Percentage)