



Maharashtra State Electricity Transmission Co. Ltd. EHV(0&M) Division, Baramati

Ph: 02112 - 244776 Urja Bhavan,
Fax: 02112 - 244775 Admin Bldg,
Email: ee6230@mahatransco.in Bhigwan Road,

Web: http://www.mahatransco.in Baramati Pin- 413 102.

Ref No: EE/EHV/O&M/DN/BMT/T/ 0226

E- Enquiry

Sub: Work of rewiring of control room and replacement of distribution metering box at 220KV Kurkumbh and 132KV Bawada Substations under EHV O&M Division Baramati.

Annexure - A Schedule...... Enclosed

- 1. Due Date: The quotations complete in all respects, duly sealed & super scribed should be submitted to this office on or before **Dt: 24.03.2021 up to 16:00 Hrs positively.**
- 2. Date of Opening of quotation:24.03.2021, If Possible
- 3. Payment: 100% against completion of work.
- 4. Along with quotations following documents should be attached,
 - A. Valid Electrical contractor's license.
 - B. Valid registration under GST.
 - C. Valid PAN registration.
 - D. Valid Shop Act License or NOC from Local Govt. Body.
 - E. The Bidder must have experience for carrying out similar work Experience. (The experience certificate should be attached.)
- 5. List of similar works executed by the contractor elsewhere preferably with testimony from the concerned shall be attached with the documents.
- 6. All general /technical /commercial terms & conditions of the contract of MSETCL are applicable to this contract.

Undersigned reserves the right to accept or reject any quotations without giving any reason. Thanking you.

SD/-(Bhauso D. Ballal) Executive Engineer EHVO&M Dn. Baramati

Date: 18.03.2021

Copy swrs to: The Superintending Engineer EHVO&M Circle Solapur

Copy to: 1) Dy. Executive Engineer, 132kV Baramati.

2) The Dy. Manager F&A EHV O&M DN.Baramati

3) Notice Board

MF

Annexure -A

Name of work: Work of rewiring of control room and replacement of distribution metering box at 220KV Kurkumbh and 132KV Bawada Substations under EHV O&M Division Baramati.

| Kurkumbh and 132KV Bawada Substations under EHV O&M Division Baramati. | | | | | | |
|--|-----------|---|---------------|------------|--|--|
| Sr No | Item code | Description | Quantity | Unit price | | |
| 1 | 50004255 | Dismantaling fan bell clock plug wiring. Dismantalling the existing light, fan, bell, clock independent plug point wiring with means at all types along with acessaries etc. cmplete as per specification and as directed by Engineer incharge including collecting and stacking the material and disposed off as directed. | AS per actual | 43 | | |
| 2 | 50002440 | Point wiring of 1mm2 cu. Wire. Providing point wiring of good quality for light/fan/bell in 1 mm2 copper wire in pvc casing capping with wire shock proof accessaries such as celling rose/ sq box with 5A switchs for table light etc. | AS per actual | 335 | | |
| 3 | 50002435 | P & F plugpoint 16A 1 Ph sw/socket 2.5 mm2 wire. Providing and fixing plug point wiring for single phase 16A pin socket and switch on PVC board with 2.5 sq.mm copper conductor PVC insulated wire with 16 SWg copper earth wire etc. | AS per actual | 38 | | |
| 4 | 50004220 | Providing and fixing 16/20 Amp 415V main switch. Providing and fixing 16/20Amp 415V main switch of approved quality and make etc complete as directed by Engineer incharge. | AS per actual | 380 | | |
| 5 | 50002688 | Earthing through 14 SWG wire. Providing earthing 14 SWG to outer lighting | AS per actual | 740 | | |
| 6 | 50004225 | P/F power plug point PVC casing switch. Providing and fixing power plug point wiring with 16A indicating switch and 16A plug with 4 sqmm multistrand wire in casing capping and modular swtches mounted on surface box etc complete as directed. | AS per actual | 425 | | |
| 7 | 50002459 | S&F Tubelight with electronic choke. Supply & Fixinf fluroscent tube light set with electronic choke 40W (Da light) 1200mm 36/40 w etc complete | AS per actual | 585 | | |
| 8 | 50000420 | WIR S/E bell. Supply and erection of bell. | AS per actual | 380 | | |
| 9 | 50002465 | S&E Ceiling fan 1200mm. Supply and erection ceiling fan 1200mm sweep with double, ball bearing and with condensor, AC 230V 50 cycle 12mm sweep with necessary erection in position testing etc. | AS per actual | 1790 | | |

| 9 | 50000491 | P&F of Distribution box. Providing and fixing of distribution box on FTL tower with 60Amp incoming 1 no. and 50Amp outgoing 10 No. feeders | AS per actual | 1520 |
|----|----------|--|---------------|------|
| 10 | 50004812 | P&F switch board. P&F switch board. | AS per actual | 384 |
| 11 | 50000416 | WIR P/F Single pole MCB. | AS per actual | 413 |

- 1. Order Amount Limited for Rs. 2.00Lakhs only. (Inclusive of all tax)
- 2. Rates are inclusive of Labor Cess and exclusive of GST(as per prevailing rates).

SD/-(Shri. B.D.BALLAL) Executive Engineer EHV O&M Dn. Baramati