

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	: 400 KV R.S O&M Dn. Karad.
Office Address	: Administrative Building, Ground Floor, Vijaynagar, Post – Supane, Tal – Karad Dist – Satara, Pin No. 415114
Contact No.	: 02164-255182 Fax. No. 02164-255182
Email ID	: ee3130@mahatransco.in
Website	: www.mahatransco.in .
CIN No.	: U40109MH2005SGC153646

No.EE/400KV RS O&M/Dn/KRD/T/No. **000276**

Date : **12 MAY 2021**

Extension to E- ENQUIRY No.260 Dtd.04.05.2021

Sub :- E-Enquiry for work of Work of Repairing of Power Transformers/ICTs Cooling Fan Motors & Cooling Fan Control systems for ICT-I, II & III at 400 KV R.S.Dn. Karad.

Dear Sir,

Sealed and superscripted quotations are invited for above as per enclosed Schedule 'A'. You are requested to quote your rates for the above subjected work. The terms & conditions are as follows.

TERMS & CONDITIONS :

- DUE DATE:-** The quotation completes in all respect, duly sealed & super scribed should be submitted to this office either in person/Post on or before **Dtd.18.05.2021 upto 18:00 Hrs** Positively.
- E-QUOTATION FEES:-** Agency should have to pay Rs.105/- (Rs.100+5% GST) against E-Enquiry Quotation Fees by cash/online to EHV O&M Circle Office Karad & copy of the money receipt should attached with the quotation this office.
- DOCUMENTS TO BE SUBMITTED ALONG WITH OFFERS :-** Please submit the following documents along with offer :
 - Copy of the Money Receipt against submission of e-enquiry fees.
You may transferred the On –Line payment of the E-Enquiry fees in following account.
 - Name of Account holder: - Superintending Engineer M.S.E.T.C.Ltd. EHV (O&M) Circle, Karad.
 - Account No. :- 20077503472
 - Name of the Bank :- Bank of Maharashtra, Branch Karad.
 - IFSC Code :- MAHB0000188.
 - Valid Electrical contractor license.
 - Income Tax Return for Last 02 Financial years.
 - Registration under PAN & GST.
 - Registration under Bombay Shop & Establishment Act /NOC from Local Grampanchayat.
- ESTIMATED COST:-** The estimated cost is limited upto Rs.01,53,892/- inclusive of all.
- QUOTED RATES:-** The quoted rates should include the cost of all taxes. The taxes will be clearly mentioned, & if the taxes are not clearly mention, then it will be presumed that the rates are inclusive of all taxes.
- VALIDITY OF OFFER:-** The offer should be valid for acceptance for a period of 90 days from the due date of same.

7. **GST:-** The prevailing rates of the GST will be applicable to this order.
8. Taxes as applicable will be deducted from your bill at source.
9. **NAME OF THE WORK:-** Work of Repairing of Power Transformers/ICTs Cooling Fan Motors & Cooling Fan Control systems for ICT-I, II & III at 400 KV R.S.Dn. Karad.
10. **SCOPE OF THE WORK:-** The scope of work is be as per mentioned in Schedule 'A'.
11. **THE TIME PERIOD FOR COMPLETION OF WORK:-** The time required for the above said work is one year from the date of issue of the work order. The work order will be issued only through e-mail.
12. **QUALITY OF WORK:-** Quality of work to be carried out should be strictly confirmed to our specification & confirming to IS Standard otherwise same will be rejected and contractor has to redone the same at his cost and risk only.
13. **T&P/MANPOWER:-** All the required Tools, Skilled Manpower & T&P, Standard kit required for the job will be in your own scope.
14. **DISCARDED OFFER CONDITIONS:-** The company reserves to itself the right to reject any or all offers which does not confirm to any of the conditions.
15. **PRICE:-** The rates quoted should be firm and price variation will not be applicable at any cost.
16. **EXECUTION OF WORK:-** In the event of the offer being accepted in the whole, the successful contractor shall execute the order immediately as per the order Schedule within the time specified in the work order. The required T&P is in his own scope for execution of the said work.
17. **SECURITY DEPOSIT:-** Every bidder whose offer is accepted either in whole or in part must deposit security amount within 07 days from the date of issue of the work order, by way of Security for the due and proper fulfillment of his contract by D.D. or Cash payable to the M.S.E.T.C.L. EHV O&M Circle, Karad. The Bank Guarantee of any nationalized Bank will be accepted against Security Deposit. Security Deposit Payable at 3.00% of the amount of the order.
18. **INCOME TAX & OTHER TAXES:-** Income tax & other taxes as applicable as per the rules & prevailing rates will be deducted from the contractor's bill.
19. **TRANSPORTATION:-** The necessary & required transportation of the materials/labours will have to be done at your own cost. No any transport facility for the material / labour will be provided by MSETCL.
20. **AGREEMENT:-** The contractor will have to execute an Agreement Bond on Stamp Paper of Rs.500/- at his own cost if order is placed.
21. **BILLS:-** You will have to submit the bills in triplicate to this office as per the specifications mentioned in Schedule 'A'.

The bills submitted should be in the name of Office of **Superintending Engineer EHV O&M Circle, Karad (GST No.27AAECM2936N1Z2)** at 400 KV RS Karad along with Factory Test Result sheet, Guarantee Certificate & Authorization certificate as issued by GE T&D India Ltd.


After duly recorded by the concerned authority i.e. Addl.EE 400 KV LMSD-I & II, Karad the same will be reflected subject to availability of funds at Circle office.

Please quote your GST No. & HSN Code for the supply availed by you on bill for smooth payment along with Joint inspection & work completion report.

22. **OUTAGES :-** The necessary outages if required for above subjected work will be arrange by Ex. Engineer or concerned Addl.Ex.Engineer 400 KV (Maint.)Unit Karad.
23. **Payment :-** 100% payment against the bills for the work actually carried out will be given to you after deducting necessary taxes & duties as per Govt. rule either by cheque or NEFT/RTGS.
24. **PENALTY: -** If the supplied is not completed within the stipulated time period the penalty will be charges as per prevailing rate i.e. 1% per of the order value per week of delay maximum upto 10% of the total order value.
25. The work should be strictly executed as per the Schedule enclosed and as per instructions of the concerned authority assign by the Ex. Engineer or this representative Engineer deputed for this work.
26. MSETCL Reserve rights to add more terms during the contract period if found necessary.
27. For any dispute/differences arises, that will be subjected to jurisdiction of Karad court only.
28. Undersigned reserved the right to accept any quotation or to reject/ accept all the quotation without assigning any reason.
29. **JURISDICTION: -** In case of dispute, if any, the legal jurisdiction of the Court shall be Karad only

Thanking you.

Yours faithfully,


(Amol Ashokrao Biradar)
Executive Engineer (Charge)
400 KV R.S.(O&M) Dn. Karad.


MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
400 KV R.S. (O&M) DN. KARAD

SCHEDULE 'A'

Sub: - Work of Repairing of Power Transformers/ICTs Cooling Fan Motors & Cooling Fan Control systems for ICT-I, II & III at 400 KV R.S.Dn. Karad.

Sr. No.	Particulars	Unit	SAC code	Qty.	Rate Per Unit in Rs.	Applicable rate of GST in %	Amount in Rs.
1	Overhauling of T/F cooling fan motors- 3 Phase, 1400 RPM, 372W,0.82 A.	No		42			
2	Rewinding of T/F cooling Fan motor with moisture proof insulation coating (The original wire size should be checked & the same should be maintained(Both side) for 3 Phase, 1400 RPM, 372W,0.82 A.	No		42			
3	Replacement of ball bearing SKF/FAG (Original) for 3 Phase, 1400 RPM, 372W, 0.82 A.	No		42			
4	Painting with industrial Smoke gray colour paint for 3 Phase, 720 RPM, 1200W, 2.7 A.	No		42			
5	Overhauling of T/F cooling fan motors - 3 Phase, 720 RPM, 1200W, 2.7 A.	No		10			
6	Rewinding of T/F cooling Fan motor with moisture proof insulation coating (The original wire size should be checked & the same should be maintained (Both side) for 3 Phase, 720 RPM, 1200W, 2.7 A.	No		10			
7	Replacement of ball bearing SKF/FAG (Original) for 3 Phase, 720 RPM, 1200W, 2.7 A.	No		10			
8	Painting with industrial Smoke gray colour paint for 3 Phase, 720 RPM, 1200W, 2.7 A.	No		10			
9	To & Fro charges of Technician.	No		03			

NOTE: - Quantity mentioned in Schedule 'A' are approximate quantities and may vary depending upon actual site requirement.


(Amol Ashokrao Biradar)
Executive Engineer (Charge)
400 KV R.S.(O&M) Dn. Karad.