

Maharashtra State Electricity Transmission Company LTD.

CIN NO.U40109 MH 2005 SGC 153646

EHV O&M Division, Solapur.

From:

Name of Office: Office of the Executive Engineer,

Office address:- Adm. Building at 220 KV Bale

Premises Ambikanagar Barshi Road,

Bale Solapur-413255

Email ID:- ee6210@mahatransco.in.

Ref No: EE/EHV/ (O&M)/DN/SUR/Dy EE/ T/No. 877

DATE: - 07.07.2021

E- Enquiry

Rate must be quoted on % Basis Only (Higher/Lower/At Par).

Sub :-E-Enquiry for the Work of Repair of Faulty 33/11KV CT & PT available at Various 220/132/110Kv Substation under jurisdiction of EHV O&M Division Solapur

Estimated Amount in Rs. – 2, 90,187/- only. (Inclusive of All Taxes).

Date of publication Enquiry: - From Dtd. 08.07.2021 To Dtd.15.07.2021.

Last Date for submission of Offer: - Dtd.15.07.2021.

Technical & Commercial Opening Date:- On Dtd.16.07.2021 If possible.

Dear Sir,

MSETCL invites offline bids/Quotation (E-Enquiry) from registered contractors /agencies for above said work as per schedule 'A'. You are requested to quote your lowest rate via submission of Bid/Quotation to this office on or before dtd.15.07.2021.

TERMS & CONDITIONS

1. Offer should be submitted to this office on OR before: - Dtd.15.07.2021.
2. **% Rate must be quoted including of all taxes & duties.**
3. The bidder is in his own interest expected to visit the site of work and acquaint himself with the site conditions. Such as availability of water, electricity, labour, approach roads etc, and all other conditions which will effect the work.
4. 5% security deposit will be required to be paid before affecting the supply which will be retained till Guarantee period is over.
5. The rate quoted should be valid at least three month from the date of opening of quotation.
6. The quotation not confirming to specifications as desired below are likely to be rejected.
7. Right to accept / reject any or all Quotations or part thereof reserved by the undersigned.
8. The interpretations of undersigned on any matter of decision given by him on any disputed point will be final and binding on contractor.

Maharashtra State Electricity Transmission Company LTD.

CIN NO.U40109 MH 2005 SGC 153646

EHV O&M Division, Solapur.

9. The documents of an offer shall be written legible and free from erasures, over writing or conversion of figures, corrections where unavoidable shall be made by crossing out, rewriting initialing and dating.
10. If the bidder has any doubt the meaning of any portion of the enquiry conditions/ specifications, he should get it clarified from the office of the undersigned before submission of the offer.
11. Attested copies of following documents along with offer should be submitted.
 - a) Payment of Income Tax in SARAL FORM for financial year 2019-20.
 - b) Valid GST Registration Certificate.
 - c) **If available at least single work order along with experience certificate by the authority not below the rank of Executive Engineer for carrying out similar type of work in MSETCL/MSEDCL must be submitted along with offer/quotation.**
 - d) **Valid Electrical Contractor License/ Manufacturer Registration Certificate / SSI Registration Certificate.**

Encl:- Schedule 'A'.

Your's faithfully.

**Executive Engineer
EHV (O&M) Division, Solapur.**

Copy to:-

1. Web Master MSETCL.
2. Notice Board.

Maharashtra State Electricity Transmission Company LTD.

CIN NO.U40109 MH 2005 SGC 153646

EHV O&M Division, Solapur.

Sub: - E-Enquiry for the Work of Repair of Faulty 33/11KV CT & PT available at various 220/132/110Kv Substation under jurisdiction of EHV O&M Division Solapur.

Sr. No	Names of Item	Core	Rate	Unit	Qty	Amount in Rs
A	Current Transformer					
1	Repair of failed 33/11 KV CT 2,3&4 Core Outdoor Oil Cooled type, Vacuum Treatment , Replacement of insulation material , Providing Hardware ,terminal ,bushing ,Gasket etc. Painting, tank welding if required, oil replacement, Repairing of failed CT Coil Complete, reassembling and testing etc. Fresh oil + 3% Handling Loss will be provided by the MSETCL.					
2	CT Ratio 400-200/1 Amp 33KV	3 Core	16189.6	No	4	64758.4
3	CT Ratio 800-400/1Amp	3 Core	18271.12	No	3	54813.36
4	CT Ratio 1600-800/1A	3 Core	20583.92	No	6	123503.52
		Sub Total A				243075.28
B	Potential Transformer					
	Repair of failed 33 KV PT Outdoor Oil Cooled Type, Vacuum Treatment, and Replacement of insulation material, Providing Hardware, Terminal, Bushing, and Gasket etc. Painting, Tank welding if required, oil replacement, Repairing of failed CT Coil Complete, Reassembling and testing etc. Fresh oil + 3% Handling Loss will be provided by the MSETCL.					
	33KV PT Ratio $33/\sqrt{3}/110/\sqrt{3}$	3 Core	15703.91	No	3	47111.73
			Sub Total Amount B			47112
			Total Amount in Rs.			290187

Note:- 1) % Rate must be quoted Including of all taxes.

2) % Rate quoted should be Inclusive of all taxes like L Cess, GST, Excise Duty, etc should be mentioned clearly, if applicable.

Executive Engineer
EHV (O&M) Division, Solapur.

Maharashtra State Electricity Transmission Company LTD.

CIN NO.U40109 MH 2005 SGC 153646

EHV O&M Division, Solapur.

*** Sub:** E-Enquiry for the Work of Repair of Faulty 33/11KV CT & PT available at
Various 220/132/110Kv Substation under jurisdiction of EHV O&M Division
Solapur.

*** Estimated Cost: Rs, 2, 90,187/- only.**

(Rs. Two Lakhs Ninty Thousand One Hundred Eighty Seven Two Only) Inclusive of all taxes

Note:

- 1) If the percentage variation of estimated rates is more than (+) 5% detailed rate analysis should be submitted if so desired by the accepting authority.
- 2) if there is any discrepancy in figure and in words the rates quoted in words will be considered.

**Executive Engineer,
EHV (O&M) DIVISION, SOLAPUR**

This is to confirm that I have studied description of items in detail. I have visited the site made myself and conversant with the site & working conditions.

I am ready to execute the above prescribed work with.

- 1) % Below [In words] of the Estimated cost.
- 2) At par [In words] of the Estimated cost.
- 3) Above [In words] of the Estimated cost.

Dated

Signature of Contractor with seal

Name:

Address: