

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,**

**EHV PC O&M ZONE, KARAD**

Administrative  
Building  
1st Floor Vijaynagar  
Karad, 415114  
Dist : Satara



Tel (O) : 02164 255054  
(P) : 02164 646056  
Fax : 02164 255186  
E-mail: [cekarad@mahatransco.in](mailto:cekarad@mahatransco.in)

CE/EHV PC O&M/ZONE/KRD/T/ **NO 0893** Date :- **22 JUL 2021**

**Sub-** Enquiry for Work of Renovation of Electrical Wiring of IT, HR & F&A Section of EHV PC O&M Zone, Karad

**Dear Sirs,**

The offers from reputed Electrical Contractors are invited for the work of Renovation of Electrical Wiring of IT, HR & F&A Section of EHV PC O&M Zone, Karad, as per terms & conditions of Schedule 'A' & Schedule 'S' enclosed herewith.


- 1. DUE DATE:** The quotations complete in all respects, duly sealed & super scribed should be submitted to this office on or up to **29.07.2021, upto 05.00 PM.**
- 2. QUOTED RATES:** Rates should be inclusive of all such as material required if any, labour charges etc. The taxes applicable if any should be quoted distinctly.
- 3. COMPLETION PERIOD:** 30 days from the date of order.
- 4. VALIDITY OF OFFER:** The offer should be valid for our acceptance for a period of 60 days from the due date of opening.
- 5.** The copy of valid Electrical Contractors license, GST Registration certificate & Experience Certificate for the work under subject shall be enclosed with your offer.

The undersigned reserves the right to reject any or all quotations without assigning any reasons.

Thanking you,

**Encl:** 1. Schedule 'S'.  
2. Schedule 'A'.

Yours faithfully,

  
(Anil V. Kolap)  
Chief Engineer,  
EHV PC (O&M) Zone, Karad


**Copy to: -**

- 1) A.G.M. (F&A) PC O&M Zone Karad.
- 2) Notice Board.  
M/F T

## **Schedule (S)**

### **GENERAL TERMS AND CONDITIONS**

1. Taxes & Duties : The rates shall be inclusive of all taxes & duties. However GST 18% will be paid extra.
2. Work completion Period. : You will have to complete the allotted work during period time as above stipulated period i.e. 30 days, from handing over of the site as per the instructions issued by Executive Engineer, EHV PC O&M Zone, Karad, or his representative. There may be variations in quantity of actual work as per site required.
3. Payment. : 100% payment will be released only after satisfactory completion of work & after receipt bill. Your GST No. & Pan No. shall be quoted on Bills/ Invoice.
4. Bill. : You have to submit your Invoice in triplicate to this office for further action.
5. Penalty. : If the work is not completed within stipulated period of 30 days, the penalty @ 1% per delayed day maximum upto 10 % of contract value will be levied & deducted from your bill.
6. Tools & Plants. : All required T&P, manpower & material is to be arranged by the contractor.
7. Income tax. : Income Tax will be deducted from the bill, as per Govt. Rules.
8. Insurance. : The insurance of your labours will have to be arranged at your cost. If failed to do so any compensation for claim arise will be at your responsibility.
9. Responsibility. : The company will not be responsible for any accidents or damages caused due to the negligence of your personnel. You have to bear the Compensation to your personnel in case of any accident. You will be responsible for the safety of your employees, Insurance, Work Compensation as per Work Compensation Act 1910 & also safety for the general public & Company's property. You will have to observe at the traffic safety rules including providing of notice boards, red danger lamps, watchman etc. wherever required.
10. Booklet. : The work shall be governed as per the Company's prevailing rules, the conditions & rules made under the MSETCL booklet of "Tender & Contract" for works, shall be applicable to this order also.
11. Dispute. : In case of any disputes, the decision of the undersigned shall be final & binding on the contractor.
12. Jurisdiction. : All disputes or differences arising under / out of or in connection with this order shall be subject to exclusive jurisdiction of Karad court only.
13. Power of Authority. : The undersigned reserves the right to cancel the quotations at any stage without assigning any reason whatsoever.

  
(Anil W. Kolap)  
**Chief Engineer**  
**EHV PC (O&M) Zone, Karad**



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,**  
**EHV PC O&M ZONE, KARAD**  
**Schedule 'A'**

**Enquiry for work of Renovation of Electrical Wiring of CE's Cabin & Technical Section of EHV PC O&M Zone, Karad.**

Sr. No.	Description of Item	Qty.	Unit	Rate per unit Rs.	Amount Rs.
1	Supplying and erecting UPVC reinforced flexible conduit 25 mm in dia. conforming to I.S. with required number of couplings, PVC bushes, check nuts etc. complete.(1-2-2)	9	m		
2	Supplying and erecting HMS PVC conduit 25 mm dia. with PVC accessories on wall /ceiling as per specification No: WG-MA/CON.(1-2-7)	72	m		
3	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.(1-2-10)	165	m		
4	Supplying and erecting mains with 2x1.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WG- MA/BW(1-3-1)	320	m		
5	Supplying and erecting mains with 1x1.5 sq.mm F.R copper PVC insulated EARTH wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WG	530	m		
6	Supplying and erecting mains with 2x2.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WG-MA/BW(1-3-3)	160	m		
7	Supplying and erecting mains with 1x2.5 sq.mm F.R copper PVC insulated EATR wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No:WG-MA/BW(1-3-3)	140	m		
8	Supplying and erecting mains with 2x4 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WG-MA/BW(1-3-5)	140	m		
9	Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.(1-8-1)	72	each		


10	Supplying and erecting ISI mark modular type switch 16 / 20 A with indicator, duly erected on provided plate and box with wiring connections complete.(1-8-6)	96	each		
11	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.(1-8-11)	27	each		
12	Supplying and erecting ISI marked modular type telephone socket one gang with safety shutter, duly erected on provided plate and box with wiring connections complete(1-8-15)	27	each		
13	Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required(1-8-23)	17	each		
14	Supplying and erecting PVC Surface modular switch box with double mounting plate for 1 module complete duly erected.(1-8-26)	28	each		
15	Supplying and erecting PVC Surface modular 149.10 switch box with double mounting plate for 3 modules duly erected.(1-8-28)	14	each		
16	Supplying and erecting PVC Surface modular switch box with double mounting plate for 6 modules duly erected.(1-8-30)	10	each		
17	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 modules duly erected.(1-8-32)	20	each		
18	Wiring for plug on board with MODULAR Switch socket, copper wiring and earthing as per specification No: WG-PW/SW(1-9-13)	25	point		
19	Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW(1-9-25)	115	point		
20	Supplying and erecting telephone copper cable 2 pair with 0.5 mm dia. laid in provided PVC casing capping/ conduit as per specification No. WG-TW(1-10-1)	140	m		
21	Supplying and installing UTP networking cat-6 cable suitable for LAN / WAN Computer net-working as per specification No. WG-COC/NC(1-12-1)	140	m		



22	Supplying and erecting square / round shaped CRCA /die-cast aluminium powder coated housing LED panel ( slim edge-lit) light suitable for 13W to18W with provision for plane front frame with translucent cover fixed to the housing complete.(2-1-8)	46	each		
23	Supplying and erecting ding dong / electronic musical type call bell with heavy duty coil suitable to operate on 230V A.C. supply erected on polished double wooden block/sunmica block of suitable size(2-4-13)	15	each		
24	Supplying, erecting and marking SPMCB 6A to 32A, B- series (for lighting) in provided distribution board as per specification no. SWSWR/MCB(5-3-3)	32	m		
25	Supplying, erecting and marking DPMCB 6A to 32A, C- series (for motor/power) in provided distribution board as per specification no. SW-SWR/MCB(5-3-6)	6	each		
26	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface/flush mounted with 2 ways for incoming and 6 ways for outgoing SP MCB's on iron/ GI frame as per specification no. SW-SWR/MCBD (5-4-18)	5	each		
27	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm complete with all materials, testing & recording the results as per specification no. EA-EP(9-1-1)	1	each		
Total amount					
GST @___%					
Grand Total					

**Remark :-** 1. The agency shall quote the rate per unit separately for each item.  
2. The taxes such as GST shall be mentioned separately

Seal and signature of **Agency**  
GST Reg. No. of agency \_\_\_\_\_  
PAN NO. of agency \_\_\_\_\_

  
(Anil V. Kolap)  
Chief Engineer,  
EHV PC O&M Zone, Karad.