



MAHATRANS CO

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenances Division Nashik

"Administrative Building", Block No. 6, 1st floor, Racca Plot,

Old Saikheda Road, Jail Road, Nashik Road-422 101:

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID : ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech

NO - 834

Date:-

13 AUG 2021

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Work of electrification & fabrication work for new Cricket, Volley Ball, Kabaddi, Green Gym at Racca Plot, MSETCL premises, Nashik." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Work of electrification & fabrication work for new Cricket, Volley Ball, Kabaddi, Green Gym at Racca Plot, MSETCL premises, Nashik.

The quotations should reach to this office on or before **20/08/2021** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop:(Technical Bid)

- Valid Certificate of Electrical Contractor License.
- GST/ GSTIN Registration Certificate.
- Experience of having successfully completed similar types of works.
- PAN card.
- Shop Act certificate/ Udyog Adhar Registration.
- Payment of **EMD Rs. 3000.00** to be made by bidder off-line only upto 14.00 hrs of **20/08/2021** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

(b) Documents in 2nd Envelop:(Price Bid)


- Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- The work should be completed within **30 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned. ,
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.**

Copy s.w.r.to.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Dy. Manager [F&A] Dn. Office, Nashik.
- 2) Master File/Notice Board.


MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD
EHV CIVIL CONSTRUCTION DIVISION, NASHIK

**Name of work:-Work of electrification & fabrication work for new Cricket, Volley Ball, Kabaddi, Green Gym
at Racca Plot, MSETCL premises, Nashik**

SCHEDULE 'B'

Sr.	Description	Qty.	Unit	Price	Amount
Cables					
1	Supplying, erecting & terminating XLPE armoured cable 3½ core 50 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	62.00	Mtr	325.00	20150.00
2	Supplying, erecting & terminating XLPE armoured cable 3½ core 25 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	102.70	Mtr	207.00	21258.90
3	Supplying, erecting & terminating XLPE armoured cable 3 core 4 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	510.00	Mtr	104.00	53040.00
4	Supplying and laying (including excavation of suitable width & depth up to 90 cm) 50 mm outside dia. double wall corrugated pipes (DWC) of HDPE for enclosing cable below ground/road surface, to required depth complete	208.00	Mtr	184.00	38272.00
Switchgears					
5	Supplying & erecting triple pole and neutral distribution board (TPNDB) with door surface/ flush mounted SP / TP MCBs of 12 poles/ 4 ways, on iron/ GI frame (vertical busbar type) as per specification no. SW-SWR/MCBDB	1.00	EA	4305.00	4305.00
6	Supplying erecting and marking triple pole isolators only switch version of miniature circuit breaker of 63A with required wiring connections and lugs etc. in provided distribution board complete.	2.00	EA	584.00	1168.00
7	Supplying erecting and marking double pole isolator only switch version of miniature circuit breaker of 40A with required wiring connections and lugs etc. in provided distribution board complete .	1.00	EA	277.00	277.00
	Supplying, erecting & marking SPN MCB 6A to 32A, C- series (for motor/power) in provided distribution board as per specification no. SW-SWR/MCB	7.00	EA	427.00	2989.00
Point wiring					
9	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	32.00	Mtr	58.00	1856.00
Fixtures					
10	Supplying and erecting LED street light fitting 100W, including lamp, with PF > 0.95, class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FG-ODF/FLS-2.	1.00	EA	8235.00	8235.00
11	Supplying and erecting LED flood light fitting of 90-100W, including lamp, with PF > 0.95, class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FG-ODF/FLS-2	7.00	EA	9514.00	66598.00

Sr.	Description	Qty.	Unit	Price	Amount
12	Supplying and erecting LED street light fitting suitable for 60W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/ FLS-2.	1.00	EA	5261.00	5261.00
13	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover complete with all materials, testing & recording the results as per specification no. EA-EP	2.00	EA	5159.00	10318.00
14	Supplying and erecting GI strip of required size used for earthing on wall and/or any other purpose with necessary GI clamps fixed on wall painted with bituminous paint in an approved manner with joints required. As per specification no EA-EP.	8.40	KG	194.00	1629.60
15	Supplying & erecting G.I. pipe 'A' class 50 mm dia. erected for enclosing XLPE armoured cable on wall/pole as per specification no. CB-CE	12.00	Mtr	380.00	4560.00
16	Supplying & erecting FRP box of size 150 x 125 x 100 mm, 2.7 mm thick complete on pole/wall as per specification no. CB-SB	1.00	EA	447.00	447.00
17	Supplying and erecting ISI mark G.I. pipe pole 'B' grade 80 mm dia 6 m long with pole cap, base plate in provided foundation as per specification no. OH-PL/GIP	1.00	EA	4582.00	4582.00
18	Making cement concrete foundation including excavation (45 x 45 x 120) cm deep in 1:3:6 cement concrete, 20 to 25 mm stone metal, (45 x 45 x 45) cm / 45 cm dia. x 45 cm height plinth duly plastered, with necessary curing and finishing complete. (for 6 m pole)	1.00	EA	1173.00	1173.00
19	Supplying and erecting street light bracket for erection of single fitting on tubular welded pole with 40 mm. dia 1.0 m long —BI grade G.I. pipe along with pole cap of 125mm dia 600 mm long duly welded as per specification no. FG-BKT/BPC	6.00	EA	1350.00	8100.00
				Total Rs	254219.50
				Add 18% GST	45759.51
				Total Rs	299979.01
				Say Rs.	299979.00


Executive Engineer (Civil)
EHV CCCM Division Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.