

(CIN No. U40109MH2005SGC153646)

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.

INTRA OFFICE COMMUNICATION

Name of Office Office address Contact No.	• \	Executive Engineer, EHV Projects Division, Kolhapur Vidyut Bhavan, Admm. Building, 2nd Floor, Tarabai Park, 0231-2665320 (P), 0231-2655937 (O), 0231-2666798	oor, Tarabai Park, Kolhapur.
E-Mail		ee3610@mahatransco.in	
	1.10	IVan IT Franing/No 001	Date : 17.08.2021

Ref.: EE/EHV Projects/Dn./Kop/E-Enquiry/No. 994

Sub: E-Enquiry for the Supply & Erection work of Providing LT 3 phase 4 wire AC supply connection for construction of 132 KVTraction S/stn. at Kharepatan (Chinchawali), Dist. Sindhudurg.

Dear Sir,

The sealed & subscribed quotations are invited for Supply & Erection work of Providing LT 3 phase 4 wire AC supply connection for construction of 132 KV Traction S/stn. at Kharepatan (Chinchawali) as per the Schedule 'A' attached herewith subject to following terms & conditions.

TERMS AND CONDITIONS :

- The quotations should reach to this office on or before 25.08.2021 upto 16.00 Hrs. 1) This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- The contractor has to furnish GST, PAN No. in the offer. 2)
- The following documents shall be submitted with the offer, 3)
 - Valid copy of Electrical contractors license issued by Govt. of Maharashtra. a.
 - Registration under works contract Act. b.
- The bidder should have an experience of more than 3 years in execution of similar 4) work
- The rates quoted by the bidder, shall be considered as inclusive of GST & all other 5) duties, taxes other levies LBW Cess, IT etc. which are payable by the contractor as per statutory regulations.
- Income tax & Labour welfare cess shall be deducted from the bills at prevailing rates, as 6) per Income Tax Act 1961.
- Bids shall remain valid for 60 days after the date of bid opening prescribed by the 7) employer.
- The estimated amount towards the said work by MSEDCL is 54,222/-8)
- Security Deposit 9)

Within Fifteen (15) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 5% of the contract value by cash/ cheque/DD.

10) Period : The time period for completion of the item under Schedule 'A' under this contract will be 1 Month. The period shall be entitled from date of handing over of the site.

- 11) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.
- 12) Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer after proper measurements and scrutiny of bills at concerned Sub-Division Office.
- 13) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 14) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost.
- 15) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 16) The contractor shall not sub-let the works awarded on him under this contract.
- 17) The contractor shall arrange for posting his own security personnel at his own cost to safeguard the material handed over to him not only at his storage yard but also at the work site till such time the complete job is ultimately handed over to Maharashtra State Electricity Transmission Company Ltd.
- 18) Guarantee The work executed under this contract shall be guaranteed for 12 months from the date of completion of work.
- 19) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 20) Quotation incomplete in any respect shall be rejected.
- 21) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 22) Quotation received late or with incomplete details against above clauses will not be considered.
- 23) Labour welfare cess /GST/other statutory payment etc. considered in contract value will be deducted at appropriate rate prevailing during tenure of contract.

Thanking You.

Yours faithfully,

Executive Engineer(rlc) EHV Projects Dn. Kolhapur.

Nam

Encl. : Schedule A.

Copy s.w.rs. to : The Suptd. Engineer, EHV Projects Circle, Kolhapur. Copy to :

- 1) The Addl. Executive Engineer, EHV S/s. Projects S/Dn., Kolhapur.
- 2) The Manager (F&A) EHV Projects Dn. Kolhapur.
- 3) Notice Board.
- MSETCL, Website.

M/F. D\GCK\O\ORDER\E- ENQUIRY\Kharepatan\E- Enquiry \ 2

EHV PROJECTS DIVISION, KOLHAPUR

"SCHEDULE - A"

Name of Work : Supply & Erection work of Providing LT 3 phase 4 wire connection for construction of 132 KV Traction S/stn. at Kharepatan (Chinchwali), Dist. Sindhudurg.

Sr. No.	Description of work	Unit	Quantity	Amount In Rs.
1	Supply & Erection work of providing LT 3 phase 4 wire AC connection for proposed 132 KV Traction S/stn. at Kharepatan (Chinchwali) Dist. Sindhudurg including supply & erection of 3 Nos. RSJ poles, stay wire, brackets, angles, G.I. Flat Shackle Insulators, Earthing sets, hardwares, Nut bolts all required material alongwith required civil foundation painting & all allied works. As per the Annexure - I, as directed by the Engineer Incharge.	No	LS	

Note: (1) All the required T&P shall be arranged by the contractor.

(2) The work shall be executed strictly as per the norms of MSEDCL.

Subbars

Executive Engineer(rlc) EHV Projects Dn. Kolhapur.

EHV PROJECTS DIVISION, KOLHAPUR

"ANNEXURE - I"

Sr. No.	Description of Materials Required	Unit	Quantity
1	P.S.C. 8 mtr. Pole	No.	3
2	M.S. Angle 50*50*6	Kg.	27
3	M.S.Flat 50 X 6	Kg.	22
4	G.I. Nutbolts	Kg.	10
5	Concreting & Muffling of poles & stay ratio 1:4:8	Cmt.	1
6	G.I. Wire 8 swg	Kg.	20
7	U CLAMPS	No.	12
8	Stay wire 7/10 swg	Kg.	25
9	Stay Insulator	No.	3
10	Shackle Insulators	No.	12
11	L.T. Shackle H.W.	PR	4
12	AL Bobbin	No.	4
13	A. A. C. Ant.	Km.	0.72
14	L.T. Earthing Set	Set	2
15	L. T. Stay set	Set	3

: