



The Maharashtra State Electricity Transmission Company Limited.
(ISO- 9001:2008 Certified)

From :

Name of Office : The Executive Engineer, 400 kV RS DIVISION, Waluj.

Official Address : Plot No. L2-L3, NEAR SAT, WALUJ MIDC, MSETCL,
AURANGABAD-431 136

Contact No. : (O) - 0240-2 56 31 51
(P) - 0240-2 55 25 33

Fax No. : 0240-2 55 57 50

Control Room : 0240-2 56 31 51

Email Id : ee2130@mahatransco.in

Website : www.mahatransco.in

Ref.No. EE/400KV/RSDn/WLJ/Tech/

W-0410

Date: 06 SEP 2021

E-enquiry

Sub: Work of overhauling of 33/04 kv,500kVA station transformers at 400KV R.S. Division Waluj.

Dear Sir / Madam,

Sealed & Super scribed quotations are hereby invited, by undersigned, for the work of overhauling of 33/04 kv,500kVA station transformers at 400KV R.S. Division Waluj, amounting to **Rs. 2,51,470/- (Two Lakh Fifty One Thousand Four hundred Seventy only) Inclusive of GST.** Submit the sealed quotations to this office during Dt. 06.09.2021 at 11:00 Hrs. to Dt. 13.09.2021 Up to 17:00 Hrs.

The Other Terms & Conditions are as follows:

1. Quotations should be duly filled in all respect & to be submitted to this office, within due date.
2. Work order is Rs. 2,51,470/- (Two Lakhs Fifty One Thousand Four hundred Seventy only) Inclusive of GST. Works will be carried out as per actual requirement of 400KV R.S. Dn., Waluj. Payment will be made on the basis of actually executed works.
3. Rates should be quoted in Schedule-A, combinedly for all particulars, in the Estimated Rates.
4. Enclose the copies of following documents, along with quotations:
 - Valid Labour Contractor License
 - Valid Electrical License
 - Shop Act License
 - ESIC Registration
 - Pan Card
 - GST Registration
 - EPFO Registration
 - Experience Certificate : for relevant work
5. Other Terms & Conditions, as per Company's Rule will be binding upon you.

Thanking You,

Yours Faithfully,

Executive Engineer,
400KV R.S Division, Waluj


Schedule "A" for Enquiry

Sub:- Work of overhauling of 33/04 kv,500kVA station transformers at 400KV R.S. Division Waluj.

Sr. No.	Particular	Unit	Qty	Rate	Amount
1	Dismantling including removal of core coil assembly and rebuilding after cleaning of all healthy parts of complete T/f, comprising of tank, radiators tubes/fins, insulating sleeves, conservator, breather etc.Labor Cost .	L.S.	2	30000	60,000.00
2	Oven drying of assembled core assembly of complete transformer	L.S.	2	20000	40,000.00
3	Replacement of all gaskets such as inspection window, all HV LV Rod etc	L.S.	2	20000	40,000.00
4	Testing as per I.S. for Repaired Transformer	L.S.	2	15000	30,000.00
5	Painting of the transformer externally	L.S.	2	9000	18,000.00
6	Transportation TO & FRO	L.S.	2	5000	10,000.00
7	Silica Gel Breather	No	2	1500	3,000.00
8	Rental charges for 500 kVA, 33/0.433 kV Transformer	No	2	5000	10,000.00
				Total	211000.00
				Labour cess @ 1%	2110.00
				Sub Total	213110.00
				GST @ 18%	38359.80
				Grand Total	251469.80
				Rounf off	251470

The order amount to Rs. 2,51,470/- (Two Lakhs Fifty One Thousand Four hundred Seventy only) Inclusive of GST.

Stamp & Signature of the Agency


Executive Engineer
400KV R.S. Division, Waluj