



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office: 400kV RS (O&M) Dn., Girwali.

Office Address: Executive Engineer,

400kV RS (O&M) Division, Girwali Tq. Ambajogai Dist: Beed. PIN code: 431519.

Contact No: 02446-259670. Fax No: 02446-259689.

Email ID: ee2210@mahatransco.in Website: www.mahatransco.in

Ref: -EE/400kV/RS(O&M)/Dn/GRL/Tech/562

Date:- 08.09.2021

E-Enquiry

Enquiry No. EE/400kV/RS/Dn/GRL/E-Enquiry2021-22/15

Sub: - Firm quotation for work of 132kv TBC bay at 220kV Girwali Substation under 400kV RS (O&M) Division, Girwali.

Dear Sir,

The Sealed & Super scribed quotations are invited from supplier/ vendors for subject items as per details given in schedule 'A' subject to following conditions:-

1) DUE DATE: - The quotations complete in all respects i.e. offer rates should be filled in given work Schedule "A" format copy duly signed, sealed & super scribed, along with covering letter of bidder/agency with above mentioned subject shall be submitted to this office on or before **14.09.2021** up to **17:00 Hrs** positively.

Estimated Cost: Rs. 291552/- (In Words: Two Lakhs Ninety One Thousand Five Hundred Fifty Two Only) Including Taxes.

2) SCOPE: - As detailed in schedule 'A'.

3) QUOTED RATES: - The quoted rates should consider as per specification for work mentioned in Schedule "A". Taxes & Charges shall be mentioned clearly. If not mentioned it will be considered inclusive of all taxes & charges.

4) GST TAX: - GST tax will be as applicable as per the rules.

5) TIME OF CONTRACT: - The time will be reckoned from the date of actual commencement/ of work & will lasts for next 12 months.

6) PAYMENT: - 100% payment will be made after satisfactorily completion of work order, subject availability of funds by MSETCL.

7) SECURITY DEPOSITE: - The successful bidder will have to pay an amount equivalent to 5 % of contract value towards S.D. at concerned Division office.

8) VALIDITY OF OFFER: - The offer should be valid for our acceptance for a period of 60 days from the Due date of same.

9) SIGNING OF CONTRACT: - Agreement contract between MSETCL authority & you should be carried out on Rs.500 bond paper within 7 days from the date of receipt of the work order. You will have to borne the charges for agreement bond

10) DOCUMENT REQUIRED: - The rate offer must be accompanied with following documents duly attested & signed by vendor.

1. Electrical Contractor License.
2. Shop act.
3. GST Registration certificate.
4. Copy of PAN card.
5. Experience certificate: Experience certificates regarding executed the similar work from the rank not below the Executive Engineer or Equivalent under MSETCL should be enclosed.

11) The undersigned have the reserve right for relaxation of any condition mention above.

12) The undersigned reserved the rights for cancellation of any or all quotations without assigning any reason.

13) No advance payment shall be made in any case.

Yours faithfully,

s/d
P D Jaybhay
Executive Engineer
400kV R.S. (O&M) Division, Girwali

Encl.:- Schedule 'A'.

Copy s.w.r. to: -

- 1) The Superintending Engineer, EHV (O&M), Circle, Parli (V).

Copy to: -

- 1) The Dy. Manager (F&A), 400KV RS (O&M), Division, Girwali.



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office: 400kV RS (O&M) Dn., Girwali.

Office Address: Executive Engineer,
400kV RS (O&M) Division, Girwali Tq. Ambajogai Dist: Beed. PIN code: 431519.

Contact No: 02446-259670. Fax No: 02446-259689.

Email ID: ee2210@mahatransco.in Website: www.mahatransco.in

Enquiry No. EE/400kV/RS/Dn/GRL/E-Enquiry2021-22/15

Schedule "A"

Scope of Work: Work of 132kv TBC bay at 220kV Girwali Substation under 400kV RS (O&M) Division, Girwali.

Sr. No.	Particular	Unit	Qty	Rate	Amount
1	Terminal block for 2.5 Sq. mm. cable (SAP mat. No.500025618)	No.	1		
2	Isolator				
a	Erection of isolator without support structure tightening, leveling, support insulator erection, erection of male-female contacts, piping, MOM box fixing, cable laying & termination with alignment of isolator mechanically & electrically as per mfg. manual complete for 145KV	Set	1		
3	Crimping works				
a	Crimping works on conductor with suitable size capacity crimping machine (overhead) with suitable size dies for main bus jumpers T-clamps for twin	Nos.	1		
b	Crimping works on conductor with suitable size capacity crimping machine (overhead) with suitable size dies for main bus jumpers T-clamps for single	Nos.	1		
4	Stringing of Spans				
a	Stringing of conductor span with hoisting of disc insulator along with hardware, crimping of conductor in dead end cone with suitable size crimping machine & dies with required hardware for single	Rmt	1		

5	Earthwire				
a	Stringing of earthwire on gantry peaks as per drawing with required tension hardware & crimping etc. complete with suitable sag tension as directed	Rmt	1		
b	Connecting earthwire from gantry peak to ground with suitable lugs & flushing the earthwire with gantry structure & making connection at both ends with suitable size nut bolts	No.	1		
6	Disc insulator string				
a	Replacement of suspension disc insulator string with removal of hardware connected, jumpers connected & its re-erection with new insulators & making the connection of all earlier jumpers etc.	No.	1		
7	Gantry Cone				
a	Fabrication & erection of Gantry structure	Per MT	1		
8	Painting				
a	Painting of Gantry & Equipment support structure by applying one coat red oxide & two coats of Epoxy paint as directed	Sq. meter	1		
b	Termination 19Cx2.5mm ² LT cable Installation of cable termination with 1.1kV single compression cable gland. The rate shall include crimping of lugs, drilling of gland plates, dressing of cables inside panel / Terminal box 19core x 2.5mm ² YWY	No.	1		
c	NIT/NT Switch	No.	1		

Taxes if any:

1.

Name, Signature and seal of Agency.

Address : _____

Mobile No. _____

**Signature of Agency
with rubber stamp**

**S/d
Executive Engineer
400kV R.S.(O&M) Division, Girwali**