

(CIN No.U40109MH2005SGC153646)

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED

Office of the Executive Engineer,
EHV Projects Division, Amravati.
"Prakash Sarita", "A Wing", Ground Floor,
220 kV Sub Station Campus, Morshi Road, Amravati - 444603.
Email ID:- ee1620@mahatransco.in

No.: - MSETCL/EE/EHV/PROJ/DN/AMT/DyEE(O)-II/Warud-1/No.

No 0 3 4 4 1

; Date:

23 SEP 2021

Enquiry for Quotations

To,

Sub: - Enquiry for work of "Rectification and Balance Electrification Works of control room, store shed, security room at 132/33kV Ralegaon S/stn, Dist. Yavatmal" at risk and cost of M/s. Swati Enterprises, Nashik.

Dear Sir,

Please quote your lowest rates (Inclusive of all taxes) for the enquiry for work of "Rectification and Balance Electrification Works of control room, store shed, security room at 132/33kV Ralegaon S/stn, Dist. Yavatmal" at risk and cost of M/s. Swati Enterprises, Nashik, as per M.S.E.T.C.L. rules on the Schedule 'A' annexed herewith and terms and conditions given below. The bidders should submit their sealed and super scribed quotation, so as to reach this office on or before Dt.01.10.2021 up to 13:00 Hrs. and same will be opened on Dt. 01.10.2021 at 15.00 Hrs. onwards, if possible. In case of hand delivery, Quotation should be handed over to receipt clerk of this office. M.S.E.T.C.L. will not be responsible in any manner for the postal delay of any type.

TERMS AND CONDITIONS –

1. **Scope of work:** - The said work should be carried out in accordance with the particulars and description enlisted in the enclosed **Schedule 'A'**.
2. The rates should be quoted on firm basis including T&P, vehicle, transportation, wires, lugs & its termination work charges etc. required for execution of work in all respect.
3. Work should be carried out as per approved drawings and standard specifications of MSETCL.
4. No advance payment will be made for this work.
5. Actual quantity of the work may be changed as per site conditions.
6. The work mentioned in this enquiry will be carried out at site of 132/33kV Ralegaon S/stn, Dist. Yavatmal.
7. Bidder should not submit 'Conditional Quotation'. Such conditional offer shall be liable for rejection.
8. All the transportation shall be arranged by agency. Transportation will not be provided by the MSETCL.
9. The bidders are required to submit scanned copies of following certificates
 - 1) Experience of similar nature of work in EHV S/stn in the organization MSETCL/MSEDCL/Govt/Semi Govt.
 - 2) GST Registration certificate.
 - 3) PAN, TAN etc. along with online bid.
10. All taxes will be applicable as per rule.
11. The rates should be quoted in figures as well as in words.

12. The agency shall have to pay the prescribe Security Deposit amounting to 10% of the total value of the contract i.e. Rs.9,804.00 (Rupees Nine Thousand Eight Hundred Four Only) in the form of cash/cheque/D.D./FDR/BG of any nationalized / Schedule bank in the name of Executive Engineer, EHV Projects Division, Amravati payable at Amravati. The same will be refunded to you after the satisfactorily completion of the work. Security Deposit will not be deducted from bills.
13. Work should be done at destination of 132/33kV Ralegaon S/stn, Dist. Yavatmal and transportation cost of the same should be borne by agency and **approval to the sample material be supplied for above mentioned work should be obtained from MSETCL and material should be supplied as per MSETCL's approved specifications.**
14. MSETCL will not be responsible if any damage is occurred to the contractor's equipment's, T&P or any accident to contractor's labors/personnel during work execution. Also, MSETCL will not be responsible if any theft/loss of contractor's material is occurred.
15. Any kind of loss to the MSETCL's property observed during the course of execution of work, by contractor's labour due to wrong operation shall be recovered from the bills or any kind of payment to be made to contractor from MSETCL.
16. Income tax will be deducted as per prevailing rules from bills and a certificate to that effect will be issued to the contractor. All statutory deduction should be deducted from your bill as per applicable rate.
17. **The work shall be completed within 01 month from the date of handing over of site to agency**, failure of such; penalty equal to ½% per delayed week subject to the maximum of 10% of the work order value will be levied.
18. In the case you fail to complete work fully and partly within stipulated time, the balance work will be got completed under your risk and cost from other agency at the prevailing rates and difference in cost will be recovered from your bill and security deposit in this case will be forfeited.
19. The work should be strictly carried out as per standard MSETCL specifications and up to the entire satisfaction of the Engineer-In charge.
20. The contractor will be abiding by the Rules and Regulations in force in respect of his employees and workmen under the Workmen's Compensation Act and the Contract Labor Act etc. He should be a registered contractor and documentary evidence of the same should be produced.
21. The quantities enumerated in attached schedule "A" are approximate and payment will be made against actual supplied quantities.
22. The work should be guaranteed for the period of 01 year from the date of commissioning of the work. During this period if any defects arises in material and workmanship, those should be attended and rectified by you with free of cost immediately.
23. **Agreement:-**You have to execute the agreements as per the provision of "Mumbai Mudrank Adhiniyam 1958, clause no.34" with requisite stamp of Rs.500.00 duly within 7 days from receipt of order. You will have to enter into an agreement with MSETCL for the above work& until such agreement is executed between MSETCL & Contractor, MSETCL shall not be liable to pay nor you shall be entitled for any amount due for put under this contract. The cost of stamp Paper requires shall be borne by you. The necessary documents, for the agreement should be completed in consultation with Executive Engineer, EHV Projects Division, Amravati.
24. The quotations without the documents as enlisted in Schedule 'A' are likely to be rejected. The quotations should be properly sealed and super scribed with the Envelopes Enquiry for work of "Rectification and Balance Electrification


Works of control room, store shed, security room at 132/33kV Ralegaon S/stn, Dist. Yavatmal" at risk and cost of M/s. Swati Enterprises, Nashik."

25. Quotations not complying to the requirements and certificates enlisted in terms and conditions sr. no.09 may not be considered. Right to accept / reject any or all quotations or part thereof is reserved by the undersigned.
26. While submitting the offer, documents (Xerox copies) enlisted in terms and conditions sr. no.09 must be self-attested.
27. In case of difference opinion, about interpretation of terms & conditions between Owner/Agency & MSETCL, the decision of order placing authority will be final & binding on the Owner / Agency.
28. Validity of the offer should be minimum for three months from the date of opening of the quotations.
29. Idle charges for any reason will not be accepted.
30. In addition to above Company's General Terms and Conditions about the Work Contract will be applicable to this enquiry.
31. In case of any dispute regarding this contract, the jurisdiction of the court will be **Amravati**.
32. The above work shall be carried out under the supervision of Additional Executive, Engineer, EHV S/stn Project S/Dn, Amravati.
33. The undersigned reserves the right to cancel the work partly/fully without assigning any reason.

Thanking you.

Encl: - Schedule 'A'

Yours Sincerely


(Arun V. Sonar)
Executive Engineer

Copy s.w.rs. to: -

1. The Chief Engineer, EHV PC O&M Zone, Amravati.
2. The Superintending Engineer, EHV Projects Circle, Amravati.

Copy to :-

1. The Additional EE, EHV S/stn Projects S/Dn, Amravati.
2. The Manager (F&A), EHV Projects Division, Amravati.
- ✓ 3. Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LIMITED

EHV Projects Division, Amravati

SCHEDULE 'A'

Sub: - Enquiry for work of "Rectification and Balance Electrification Works of control room, store shed, security room at 132/33kV Ralegaon S/stn, Dist. Yavatmal" at risk and cost of M/s. Swati Enterprises, Nashik.

Sr No	Item / Description	Unit	Total QTY	Ex-Works	LC @1% on (5)	Freight @1% on (5+6)	Insurance @1% on (5+6)	GST @18% on (5+6+7+8)	Per Unit Rate (5+6+7+8+9)	Amount in Rs. on (4*10)
1	2	3	4	5	6	7	8	9	10	11
Schedule - A- Supply										
1	Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW	Each	14	346.00	3.46	3.49	3.49	64.16	420.61	5,888.54
2	Supplying of ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.	Each	12	50	0.50	0.51	0.51	9.27	60.78	729.38
3	Supplying PVC Surface modular switch box with double mounting & front plate for 8 modules complete duly connected.	Each	3	219	2.19	2.21	2.21	40.61	266.22	798.67
4	Supplying PVC trunking (PVC casing-n-capping) of size 32 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	Meter	100	29	0.29	0.29	0.29	5.38	35.25	3,525.34
5	Supplying mains with 2x2.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WG-MA/BW	Meter	300	40	0.40	0.40	0.40	7.42	48.63	14,587.63
6	Supplying ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required.	Each	2	330.00	3.30	3.33	3.33	61.19	401.16	802.32
7	Supplying ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	Each	2	91	0.91	0.92	0.92	16.87	110.62	221.25
8	Supplying regular/ standard model ceiling fan of 900 /1050 mm. sweep complete erected in position as per specification no. FG-FN/CF	Each	2	1717.00	17.17	17.34	17.34	318.39	2,087.25	4,174.49
9	Supplying LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete.	Each	24	839.00	8.39	8.47	8.47	155.58	1,019.92	24,478.05
10	Supplying DPMCB 40A to 63A, C-series (for motor/power) in provided distribution board as per specification No. SW- SWR/MCB	Each	4	593.00	5.93	5.99	5.99	109.96	720.87	2,883.49
11	Supplying Exhaust fan heavy duty 230 V A.C. 50 cycles 450 mm. 1400 RPM complete erected in position as per specification no. FG-FN/EXF	Each	2	3869.00	38.69	39.08	39.08	717.45	4,703.30	9,406.59
12	Supplying and erecting GI earth wire of high purity of different sizes used for earthing or any other purposes on wall with necessary G. I. Clamps fixed on wall/cable/ conduit with screws in an approved manner.	Kg	10	69.00	0.69	0.70	0.70	12.80	83.88	838.79

13	Supplying XLPE armoured cable 2 core 4 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	MTR	150	78	0.78	0.79	0.79	14.46	94.82	14,222.94
Total amount of Schedule - A- Supply (Including LC@1% F&I@1%and GST@18%) in Rs.										82,557.49
Schedule - B - ETC Works										
1	Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW	Each	14	98.00	0.98			17.82	116.80	1,635.15
2	Erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.	Each	12	17.00	0.17			3.09	20.26	243.13
3	Erecting PVC Surface modular switch box with double mounting & front plate for 8 modules complete duly connected.	Each	3	25.00	0.25			4.55	29.80	89.39
4	Erecting PVC trunking (PVC casing-n-capping) of size 32 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	Meter	100	15.00	0.15			2.73	17.88	1,787.70
5	Erecting mains with 2x2.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WG-MA/BW	Meter	300	15.00	0.15			2.73	17.88	5,363.10
6	Erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required.	Each	2	20.00	0.20			3.64	23.84	47.67
7	Erecting ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	Each	2	17.00	0.17			3.09	20.26	40.52
8	Erecting regular/ standard model ceiling fan of 900 /1050 mm. sweep complete erected in position as per specification no. FG-FN/CF	Each	2	89.00	0.89			16.18	106.07	212.14
9	Erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete.	Each	24	44.00	0.44			8.00	52.44	1,258.54
10	Erecting DPMCB 40A to 63A, C-series (for motor/power) in provided distribution board as per specification No. SW- SWR/MCB	Each	4	40.00	0.40			7.27	47.67	190.69
11	Erecting Exhaust fan heavy duty 230 V A.C. 50 cycles 450 mm. 1400 RPM complete erected in position as per specification no. FG-FN/EXF	Each	2	134.00	1.34			24.36	159.70	319.40
12	Erecting GI earth wire of high purity of different sizes used for earthing or any other purposes on wall with necessary G. I. Clamps fixed on wall/cable/ conduit with screws in an approved manner.	Kg	10	75.00	0.75			13.64	89.39	893.85
13	Erecting & terminating XLPE armoured cable 2 core 4 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	MTR	150	19.00	0.19			3.45	22.64	3,396.63

Total amount of Schedule - B - ETC Works (Including (LC@1% and GST@18%) in Rs.	15,477.91
Grand Total amount of Schedule - A- Supply & Schedule - B - ETC Works (Including (LC@1% F&I@1%and GST@18%) in Rs.	98,035.39
Grand Total amount in words: - Rupees Ninety-Eight Thousand Thirty-Five Only (Including (LC@1% F&I@1%and GST@18%).	

Note: -

- 1) Above rates are inclusive of taxes.
- 2) Schedule is enclosed for reference only.
- 3) T&P required for the work will be provided by agency and no extra charges will be paid to agency.

Address for correspondence:-

Seal & Signature of Bidder

Valid E-mail Id:-

Valid Mobile no.:-