

<u>- OFFICE OF THE -</u> EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division, Mahatransco Administration Building, first Floor, wing no.102, Aurangabad,Ph. No. (0240) 2331429, E-mail: ee2710@mahatransco.inCIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./ABD//Tech/ No 0 0 7 6 3

Date:-

8 OCT 2021

e- Quotation Enquiry

To,	
•••••	
Sub:	Renovation & Modification of Ladies Toilet & Rest room at 132kV Chikhalthana, Dist-Aurangabad.(2 nd call)
	call)
Dear Si	r.

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or before dated 26.10.2021 up to Time 17.30 Hrs.

TERMS AND CONDITIONS:

- The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within (30) days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost
- 9) The material should be got approved prior to fixing from the Engineer in-charge.

- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division IDist: Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- You will have to Depositas 3% of work order value as security deposit in cash or DD of any nationalized Bank within 07 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- The contractor has to pay earnest money to Rs.3,000.00/- in cash/In form of DD/FDR of any Nationalized Bank in favor of Executive Engineer (C) EHV CCCM DIV. MSETC Ltd. Aurangabad or via Online to this office Bank of Baroda Account No.04600200000009, IFSC Code:BARB0AURANG, Aurangabad-431001. If the EMD of required amount is not found in the envelop the quotation will be rejected.
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- GST will be recovered from your bill as per GST norms.
- Special condition: The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is Rs. 2,84,246.97 only. (Inclusive of all Taxes)
- The Contractor has to submit the Valid Civil Works Registration, GST Registration, Civil Works Experience Certificate and EMD Paid Receipt at the time offer submission as mandatory documents.

Encl: Schedule'B'

Executive Engineer (C)

EHV CCCM Division, Aurangabad.

Copy s.w.r.s. to:

The Superintending Engineer (C) EHV CCCM Circle, Aurangabad.

Copy To:

The Dy. Manager (F&A), EHV CCCM Division, Aurangabad.



- OFFICE OF THE -EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,

Mahatransco Administration Building, first Floor, wing no.102, Aurangabad, Ph. No. (0240) 2331429,

E-mail: ee2710@mahatransco.inCIN: U40109MH2005SGC153646



Name of Work: Renovation & Modification of Ladies Toilet & Rest room at 132kV Chikhalthana, Dist-Aurangabad.(2nd call)

Estimated Amount: -

Rs. 2,84,246.97 (Inclusive of All Taxes)

(J. P. Patil)
Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Quotation for Works

I/We hereby que	ote for	the exec	cution of the	specified in the ab	ove written memorandum w	ithin time	specifie	ed in such
memorandum	at	(at	Figure)	%	above/below/Estimated	Rate	(in	Words)
			percent	above/Below/Estin	nated rate (to be struck which	hever is n	ot appli	cable) the
					ing item of work to be carrie			
instruction in w	riting f	rom the	Engineer –	in – Charge.				
I/We have read	the ge	eneral co	onditions of	contracts & the co	nditions enumerated in the	quotation	and the	same are
binding on us.								

Full Address:

Signature of the contractor

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

EHV CCCM Division Aurangabad.

Name of Work: Renovation & modification of Ladies Toilet & Rest room at 132kV Chikalthana,
Dist- Aurangabad (2nd call)

Scl	hed	ul	e"	'B"

Sr. No.	Particulars	Qty.	Rate	Add 18% GST on Col 4)	Final Rate (Col.4 + Col.5)	Unit	Amount Rs. (Col.3 x Col.6)
1	3	4	5	6	7	8	9
1	Removing door & windows with frames and stacking the materials as directed with all leads, lifts etc. complete. As directed by engineer in-charge.	1,00	143,42	25,82	169,24	No	169,24
2	Removing shahabad or Tabdur stones from floor without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	27,00	41,41	7,45	48,86	Sqm	1319,22
3	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.	50,00	277,53	49,96	327,49	Sqm	16374,73
4	Providing and fixing in position, double/single shutter aluminium extruded powder coated openable door of specified size with aluminium door frame of powder coated section 101.60x44.75 mm, 3.18 mm thick and shutter comprising of powder coated section having bottom and lock rail of size 150mmx44.5mm,3.00 mm thick top rails 47.62x44.45mm, 3.00 mm thick, vertical style 47.62x44.45mm, 3.00 mm thick and for shutter plain glass panes 5 mm thick for top panels and 12mm thick both side laminated phenol bonded particle board panels for bottom panels etc., I.S.I. mark, heavy duty, Hydraulic floor spring of 150 kg capacity, having heavy duty concealed lock, necessary beeding, glazing clips, PVC gaskets, 250mm length aluminium tower bolts, 150mm dia. aluminium pad handle, etc. as per detailed design and drawing or as directed by engineer in charge including all materials, labours, and equipments etc. complete.	3,00	7330,00	1319,40	8649,40	Sqm	25948,20
5	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete	2,00	2869,41	516,49	3385,90	Sqm	6771,80
6	Labour charges for removing false ceilling tiles of any size and shape including all tools and plants including scafolding, stacking the useful material neetly as directed and dispossing of the un suitable material out side of the premises with all lead and lift etc complete as per the directive of Engineer In charge.	24,00	55,55	10,00	65,55	Sqm	1573,20
7	Labour charges for fixing false ceilling tiles of any size and shape available with department, including all tools and plants including scafolding with all lead and lift etc complete as per the directive of Engineer In charge.	3,00	303,00	54,54	357,54	Sqm	1072,62
8	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	99 00	33,33	6,00	39,33	Sqm	3893,67
9	Providing and applying Two coats of wall care Putty or plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etcomplete.	00 00	87,87	15,82	103,69	Sqm	10265,31

Sr. No.	Particulars	Qty.	Rate	Add 18% GST on Col 4)	Final Rate (Col.4+ Col.5)	Unit	Amount Rs. (Col.3 x Col.6)
10	approved quality, colour and shade to old / new surfaces in two coats including scaffolding, preparing the surface (excluding the primer coat) etc. complete. Spec.No.Bd.P.6 Page No.414	99,00	69,69	12,54	82,23	Sqm	8140,77
11	Providing and applying priming coat on concrete/masonary/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	99,00	34,34	6,18	40,52	Sqm	4011,48
	Providing and fixing P.V.C. Rain water pipes of 160mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, inluding fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete.		1264,52	227,61	1492,13	Rmt	70130,11
13	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete	6,00	577,72	103,99	681,71	No	4090,26
14	Engaging of labours for various civil maintenance works unskilled male labour	13,00	565,60	101,81	667,41	Per man Day	8676,33
	Providing and laying matt finish ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	10,00	1239,09	223,04	1462,13	Sqm	14621,30
	Providing and laying ceramic tiles of having size 30 cm. x 30 cm. and confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	22,00	1306,76	235,22	1541,98	Sqm	33923,56
	Providing and fixing in position anodised extruded aluminum partitions, partly glazed and partly laminated having frame made out of extruded tubular section of size 40 mm x 60 mm with 12 mm thick three layered flat pressed teak wood particle board bonded with BWP type exterior grade phenol formaldehyde synthetic resin conforming to IS 128231990, laminated on both sides, Novateakor equivalent and 5 mm thick selected quality plain/ float glass panels fixed with aluminum glass clips 12 mm x 12 mm and rubber cushioning beading to glass partitions as per approved drawing etc.	3,00	3053,23	549,58	3602,81	Sqm	10808,43

Sr. No.	Particulars	Qty.	Rate	Add 18% GST on Col 4)	Final Rate (Col.4 + Col.5)	Unit	Amount Rs. (Col.3 x Col.6)	
	Providing and fixing false ceiling of 15mm thick as per drawings including powder coated G.I. wall angle of 20 mm x 20 mm x 0.60 mm size, G.I. grid runners of size 15 mm x 38 mm at 600 mm center to center both ways and suspended using G.I. 3 mm wire including fixing using butterfly clips and fasteners including transporting, scaffolding all necessary labour and machinery, finishing etc. complete	24,00	1579,64	284,34	1863,98	Sqm	44735,52	
	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete		7508,99	1351,62	8860,61	Cum	17721,21	
	Total Rs.						284246,97	1

Executive Engineer (C) EHV CCCM Division MSETCL Aurangabad