

- OFFICE OF THE -

EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./ABD//Tech/

No 0 0 7 7 4

Date:-

20 OCT 2021

e- Quotation Enquiry

To,

.....

.....

.....

Sub: E-Quotation Enquiry for Scraping and levelling the 33KV Switchyard & its peripheral area at 400 KV (Aurangabad-II) Thapti Tanda, Dist:Aurangabad.

Dear Sir,

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors in Civil works as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or **before dated 29.10.2021 Time 17.30 Hrs.**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per PWD specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work which is of bad workmanship quality will not be measured and paid.

- 4) Other material such as require tools and plant will have to arrange by the contractor at his own cost.
- 5) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 6) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 7) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 8) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-I Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 9) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work and final terms & conditions will be mentioned in Work Order.
- 10) You will have to deposit (3% of work order value) as security deposit in cash or DD of any nationalized Bank within 10 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- 11) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 12) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 13) The contractor has to pay earnest money to Rs.3,000.00/- in cash/In form of DD/FDR of any Nationalized Bank in favor of Executive Engineer (C) EHV CCCM DIV. MSETC Ltd. Aurangabad or via Online to this office Bank of Baroda Account No.04600200000009, IFSC Code:BARB0AURANG, Aurangabad-431001. If the EMD of required amount is not found in the envelop the quotation will be rejected.
- 14) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.

- 15) GST will be recovered from your bill as per GST norms.
- 16) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 17) The estimated cost of the work is **Rs.2,92,784.25** only. (Inclusive of all Taxes)
- 18) The Contractor has to submit the self-attested copies of valid Civil Works Registration Certificate, Works Experience Certificate, GST Registration, PAN card and EMD paid receipts/DD at the time of submission as mandatory documents.

Encl: Schedule 'B'


(J.P. Patil) 18/10/21

Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Copy s.w.r.s. to:

1. The Superintending Engineer (C) EHV CCCM Circle, Aurangabad.

Copy To:

1. The Dy. Manager (F&A), EHV CCCM Division, Aurangabad.

- OFFICE OF THE -

EXECUTIVE ENGINEER (C)

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



Name of Work: E-Quotation Enquiry for Scraping and levelling the 33KV Switchyard & its peripheral Area at 400 KV (Aurangabad-II) Thapti Tanda, Dist:Aurangabad

Estimated Amount: - Rs. 2,92,784.25 (Inclusive of All Taxes)

(J.P. Patil)

Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Quotation for Works

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor


Full Address:

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION , AURANGABAD**

"Schedule B"

**Scrapping and levelling the 33KV Switchyard & its peripheral area at 400 KV (Aurangabad-II) Thapti
Tanda, Dist:Aurangabad**

Sr No.	Particulars	Qty	Rate	Add 18% GST on Col 4	Final Rate(Col.4 +Col.5)	Unit	Amount (Rs.)
1	3	4	5	8	9		
1	Cutting of thorny bushes & shrubs with scrapping & levelling the area in earth, soil of all sorts, sand, gravel or soft murum including dressing section upto a depth of 300mm with all lifts and conveying the excavated materials with all lifts upto a lead of 50m. and spreading for embankment or stacking as directed(By manual means)	1676.00	82.42	14.84	97.26	Sqm	163007.76
2	Conveying materials obtained from road cutting including all lifts, laying in layers of 20cm. To 30cm. Breaking clods, dressing to the required lines, curves, grades and section, watering and compacting to not less than 97% of standard proctor density for a lead of 300m. to 500m. inclusive, from the site of excavation to the deposition as directed.	327.00	336.33	60.54	396.87	Cum	129776.49
					Total	Rs.	292784.25


Executive Engineer (C)
EHV CCCM Division
MSETCL, Aurangabad.

