



**MAHAtransco**

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenances Division Nashik

"Administrative Building", Block No. 6, 1<sup>st</sup> floor, Racca Plot,

Old Saikheda Road, Jail Road, Nashik Road-422 101.

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

No - 1161

Date:- 01 NOV 2021

**e- Quotation**

Sealed and superscripted e- quotations are invited for the work of "**Electrification work for control room at 220 KV Satana, Nashik MSETCL.**" As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

**Name of Work:- Electrification work for control room at 220 KV Satana, Nashik MSETCL**

The quotations should reach to this office on or before **08/11/2021** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

**(a) Compulsory Primary Documents in 1<sup>st</sup> Envelop:(Technical Bid)**

- Valid Certificate of Electrical Contractor License.
- GST/ GSTIN Registration Certificate.
- Experience of having successfully completed similar types of works.
- PAN card.
- Shop Act certificate/ Udyog Adhar Registration.
- Payment of **EMD Rs. 3000.00** to be made by bidder off-line only upto 14.00 hrs of **08/11/2021** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope

**(b) Documents in 2<sup>nd</sup> Envelop:(Price Bid)**

- Price bid only where in the rates/percentage should be quoted in figures as well as in words.


**NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1**

- The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.



- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer [Civil]  
EHV Civil CCM Dn Nashik.**

Copy s.w.r.to.-

- 1) The Superintending Engineer EHV CCCM Circle, Nashik.

Copy to-

- 1) The Dy. Manager [F&A] Dn. Office, Nashik.
- 2) Master File/Notice Board.



**MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD**  
**EHV CIVIL CONSTRUCTION DIVISION, NASHIK**

**Name of work:-Electrification work for control room at 220 KV Satana, Nashik MSETCL**

**SCHEDULE 'B'**


Sr.	Description	Qty.	Unit	Rate	Amount
1	Supplying & erecting mains with 2x4 sq.mm F.R copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WGMA/BW	12.00	Mtr	107.00	1284.00
2	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	40.00	Mtr	86.00	3440.00
3	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire with 1x1.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	98.00	Mtr	60.00	5880.00
4	Supplying & laying HMS PVC conduit 20 mm dia with necessary accessories in RCC work/false ceiling/false flooring	80.00	RMT	88.00	7040.00
5	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 20 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	67.00	RMT	36.00	2412.00
6	Supplying and erecting Ceiling rose / Batten holder / Slanting holder / hanging cord switch / hanging bell push / pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box	5.00	EA	35.00	175.00
7	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 3 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	2.00	EA	231.00	462.00
8	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 4 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	1.00	EA	251.00	251.00



Sr.	Description	Qty.	Unit	Rate	Amount
9	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 6 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	1.00	EA	375.00	375.00
10	Supplying and erecting unbreakable concealed type modular switch box with double mounting plate for 12 module duly erected flush to wall with required chiselling and finishing with cement mortar / POP as per required to match the background.	7.00	EA	476.00	3332.00
11	Supplying and erecting ISI mark modular type switch 16 / 20 A with indicator, duly erected on provided plate and box with wiring connections complete.	8.00	EA	134.00	1072.00
12	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	8.00	EA	166.00	1328.00
13	Point wiring for light/fan/bell concealed type in min 20 mm ISI marked HMS PVC conduit with 1.5 sq.mm. (2+1E) FR grade copper wires, modular type switch, earthing and required accessories as per specification No: WG-PW/CW	39.00	Point	635.00	24765.00
14	Point wiring for independent plug, concealed type in min 20 mm ISI marked HMS PVC conduit with 1.5 sq.mm (2+1E) FR grade copper wires, modular type switch and socket, earthing and required accessories as per specification No WGPW/ SW	15.00	Point	687.00	10305.00
15	Supplying & erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete.	35.00	EA	926.00	32410.00
16	Supplying and erecting corridor/passage light fitting (2 feet) including 18W LED lamp, comprises of extruded channel in plastic silver grey colour & with same plastic end cap on provided PVC block / wooden board.	2.00	EA	730.00	1460.00
17	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	8.00	EA	2042.00	16336.00
18	Supplying and erecting Square / rectangular shaped CRCA / die cast aluminium powder coated housing LED panel lights (slim edged lit) 600 X 600 mm suitable for 36-40 W with provision for plane front frame with translucent cover fixed to the housing.	35.00	EA	3741.00	130935.00



Sr.	Description	Qty.	Unit	Rate	Amount
19	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover complete with all materials, testing & recording the results as per specification no. EA-EP	2.00	EA	5476.00	10952.00
Total Rs.					254214.00
GST @ 18 %					45758.52
Total Rs.					299972.52
Say Rs.					299973.00

  
**Executive Engineer (Civil)**  
**EHV CCCM Division Nashik.**

I / We hereby agree to carryout the above work as under :-

- a) At estimated cost.
- b) Above.....% in words.....Of Estimated cost in Schedule "B"
- c) Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.