



**MAHA TRANSCO**

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)  
EHV Civil Construction cum Maintenances Division Nashik  
"Administrative Building", Block No.6, 1<sup>st</sup> floor, Racea Plot,  
Old Saikheda Road, Jail Road, Nashik Road-422 101.  
Ph No:-0253-2403101 (O), Extension Phone No, 0253-2403110  
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech

**NO - 2131**

Date:- **30 DEC 2021**

**e- Quotation**

Sealed and superscripted e- quotations are invited for the work of **"Providing & installation of pump, miscellaneous works at 132 KV Dindori Sub station, Dist:- Nashik."** As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

**Name of Work:- Providing & installation of pump, miscellaneous works at 132 KV Dindori Sub station, Dist:- Nashik.**

The quotations should reach to this office on or before **05/01/2022** up to 15.00 Hrs.

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

**(a) Compulsory Primary Documents in 1<sup>st</sup> Envelop:(Technical Bid)**

- (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government and registered vendor of MSETCL.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) PAN Card
- (iv) E.P.F. Registration Certificate – issued by competent authority of Govt.
- (v) Experience of having successfully completed similar civil works.
- (vi) Payment of **EMD Rs. 4500.00** to be made by bidder off-line only upto 14.00 hrs of **05/01/2022** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope.

**(b) Documents in 2<sup>nd</sup> Envelop:(Price Bid)**

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

**NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1**

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.



- 5) Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- 6) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule B
- 7) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 8) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 9) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 10) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer (Civil)**  
**EHV Civil CCM Dn.Nashik.**

Copy s.w.r.t.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer (Civil) EHV CCCM Sub Division Nashik-II.
- 2) Dy. Manager (F&A) EHV CCCM Division Nashik.
- 3) Master File/Notice Board.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD**  
EHV CCCM Division, Nashik

Name of work :- Providing & installation of pump, miscellaneous works at 132 KV Dindori Sub station, Dist:- Nashik

**SCHEDULE 'B'**


Sr No.	Description	Qty	Unit	Rate without GST	GST 18%	Rate with - GST	Amount
1	Removing old damaged Submersible pump from bore well including pipe	1.00	Each	4040.00	727.20	4767.20	4767.20
2	Supplying and erecting submersible pumpset of 2.25 KW/3 HP with 415 V, 50 c/s AC supply suitable for 150 mm dia. borewell suitable for 100 to 250 LPM discharge at 45 to 24 m head & (max. efficiency at 38 m head & 250 lpm) discharge & delivery Pipe Size-50mm diameter with a necessary H type clamps as per specification no. WP-SMP	1.00	Each	30576.00	5503.68	36079.68	36079.68
3	Supplying and erecting thermal Overload Relay for motor starter suitable for up to 12.5 HP	1.00	Each	1104.00	198.72	1302.72	1302.72
4	Supplying & erecting contactor for DOL motor starter from 7.5 H.P. to 10 H.P.	1.00	Each	1011.00	181.98	1192.98	1192.98
5	Providing and supplying in standard lengths Polyethylene Pipes, conforming to IS 4984 / 14151 / 12786 / 13488 with necessary jointing material like mechanical connector i. e. thread / insert joint / quick release coupler joint / compression fitting joint or flanged joint excluding coupler/specials, including transportation and freight charges, inspection charges, loading / unloading charges, conveyance to the departmental stores & stacking the same in closed shade duly protecting from sunrays & rains, excluding GST levied by GI & GOM in all respect etc. complete -PE-100 a) 6 Kg/Sq. cm : 63 mm	149.00	RMT	96.96	17.45	114.41	17047.09
6	Supplying and erecting PVC insulated PVC round sheathed 2.5 sq.mm (50 no. x 0.25 mm dia.) 3 core flexible multi stranded copper Industrial cable for voltage grade up to 1.1 kV	105.00	RMT	86.00	15.48	101.48	10655.40
7	Removing wire fencing with iron/C.C.fencing post and stacking the materials as directed with all leads, lifts etc. complete.	20.00	RMT	63.63	11.45	75.08	1501.60
8	Cutting down trees including trunks and branches with girths above 90cm to 180cm and stacking the materials neatly with all lifts and lead of 1000m. as directed and earth filling in the depression/pit if any.	1.00	Each	1649.33	296.88	1946.21	1946.21
9	Providing and laying in situ cement concrete of 1:4:8 proportion with trap/ granite/ quartzite/ gneiss metal in foundation including necessary form work, compacting and curing etc. complete. (with reversible drum type mixer with SCADA with fine aggregates of required specifications (Natural sand / VSI sand finely washed etc)	1.37	Cu.M	6504.24	1170.76	7675.00	10507.08
10	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces, in all position including scaffolding and curing etc. complete.	44.40	Sq.M	287.70	51.79	339.49	15073.36
11	Providing fine cement finish 1.5 mm thick over green plaster surface including scaffolding curing etc. complete.	44.40	Sq.M	79.64	14.34	93.98	4172.71



Sr No.	Description	Qty	Unit	Rate without GST	GST 18%	Rate with GST	Amount
12	Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	1.00	Nos	5371.18	966.81	6337.99	6337.99
13	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/ bolted/welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	0.05	MT	90072.81	16213.11	106285.92	5314.30
14	Providing and laying in trenches 50mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	RMT	730.23	131.44	861.67	4308.35
15	Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	20.00	RMT	384.81	69.27	454.08	9081.60
16	Providing and laying in trenches 15 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	RMT	255.53	46.00	301.53	3015.30
17	Providing and fixing reinforced cement concrete cover of size 90 cm x 45 cm with frame over inspection chamber etc. complete. Heavy duty (225 Kilogram)	1.00	Nos	5015.66	902.82	5918.48	5918.48
18	Providing and fixing screw down 15 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete	5.00	Nos	472.68	85.08	557.76	2788.80
19	Providing and fixing screw down for 25 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	Nos	792.85	142.71	935.56	935.56
20	Providing and fixing screw down for 50 mm dia. wheeled stop tap of brass including necessary sockets/ union nut complete.	2.00	Nos	1815.98	326.88	2142.86	4285.72
21	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means	50.40	Cu.M	194.93	35.09	230.02	11593.01
22	Removing the tar or coba and disposing of the material as directed etc. complete.	44.40	Sq.M	25.25	4.55	29.80	1323.12



Sr No.	Description	Qty	Unit	Rate without GST	GST 18%	Rate with GST	Amount
23	Providing and fixing in position (as per 1868/1982) Aluminum sliding window of three tracks with rectangular pipe 95x38.10x 0.90 mm at weight 0.637 Kilogram/Running meter. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 Kilogram/ Running meter. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 Kilogram/Running meter. The shutter should be of bearing bottom 40x18x1.25 mm at weight 0.417 Kilogram/ Running meter. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 Kilogram/Running meter. and handle and top section 40x18x1.25mm at weight 0.417 Kilogram/ Running meter. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminum sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminum mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With colour Anodising without box	26.00	Sq.M	5525.71	994.63	6520.34	169528.84
24	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	20.00	Sq.M	4412.15	794.19	5206.34	104126.80
25	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	17.00	Nos	163.08	29.35	192.43	3271.31
Total Rs							436075.20
Say Rs.							436075.00

  
 Executive Engineer (Civil)  
 EHY CCCM Dn Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.