



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)
EHV Civil Construction cum Maintenance Division Nashik
"Administrative Building", Block No.6, 1st floor, Racea Plot,
Old Saikheda Road, Jail Road, Nashik Road-422 101.
Ph No:-0253-2403101 (O), Extension Phone No, 0253-2403110
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech-

Date:- 30 DEC 2021

No - 2130

e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Various maintenance works at 220 KV Manmad Sub, station, Dist:- Nashik" As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Various maintenance works at 220 KV Manmad Sub station, Dist:- Nashik.

The quotations should reach to this office on or before **05/01/2022** up to 15.00 Hrs.

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop:(Technical Bid)

- (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government and registered vendor of MSETCL.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) PAN Card
- (iv) E.P.F. Registration Certificate – issued by competent authority of Govt.
- (v) Experience of having successfully completed similar civil works.
- (vi) Payment of EMD Rs. 3000.00 to be made by bidder off-line only upto 14.00 hrs of **05/01/2022** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope.

(b) Documents in 2nd Envelop:(Price Bid)

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) Cement of approved make OF MANIKGARH/ACC/Orient/Rajshree as per IS 8912-1989 i.e.43-grade OPC or equivalent approved make will be procured & used.
- 6) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule B
- 7) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 8) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 9) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 10) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 11) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 12) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 13) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)
Executive Engineer (Civil)
EHV Civil CCM Dn.Nashik.

Copy s.w.r.t.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer (Civil) EHV CCCM Sub Division Nashik-II.
- 2) Dy. Manager (F&A) EHV CCCM Division Nashik.
- 3) Master File/Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
EHV CCCM Division, Nashik

Name of work :- Various maintenance works at 220 KV Manmad Sub station, Dist:- Nashik

SCHEDULE 'B'

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	24.480	Cum.	202.73	36.49	239.22	5,856.11
2	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	0.500	Cum.	222.68	40.08	262.76	131.38
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.630	Cum.	6,196.49	1,115.37	7,311.86	11,918.33
4	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.360	Cum.	7,332.94	1,319.93	8,652.87	11,767.90
5	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap / granite /quartzite/ gneiss metal for R.C.C. slab and landing as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compactionand roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	4.230	Cum.	15,156.32	2,728.14	17,884.46	75,651.27

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
6	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting, curing, finishing and roughening them if special finish is to be provided and curing complete.(Excluding reinforcement and structural steel) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	3.808	Cum.	15,763.45	2,837.42	18,600.87	70,832.11
7	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.616	MT.	75,395.61	13,571.21	88,966.82	54,803.56
8	Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1 Kg per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete.	0.100	Sqm.	1,134.43	204.20	1,338.63	133.86
9	Dismantling the R.C.C. Work 1:2:4 and sorting out the materials such as steel etc. as directed and stacking them within the specified lead as directed etc. complete.	5.000	Cum.	1,434.85	258.27	1,693.12	8,465.60

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
10	Providing & laying APP modified water proofing memberane with non woven ployster reinforcement 3mm thick water proofing treatment (Dr. fixit Torch shield or super theomolay of STP make) approved by Engineer Incharge, to the roof including cleaning the roof surface with wire/ coir brush & with air blower repairing pot holes cracks if any over Siporex/ RCC slab by using polymer base mortar by adding SBR latex @ 5 ltr/bag in cm 1:4 applying a coat of oil base bitumen primer Dr. fixit/Shalitex @200 gms/M2 by brush or with roller after removing of dust completely including providing & laying 3 mm thick App shit (Pidilite/STP make) as per the manufacturers instruction by heating with torch at a specified temprature including providing 100 mm overlap in all sides as directed by Engineer In charge etc. complete & applying two coats of silver shield @ 0.1 kg/Sqm etc. complete as directed by Engineer In charge	78.000	Sqm.	604.23	108.76	712.99	55,613.22
						Total Rs.	295,173.34
						Say Rs.	295173.00


 Executive Engineer (Civil)
 EHV CCCM Dn Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.