



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office: 400kV RS (O&M) Dn., Girwali.  
Office Address: Executive Engineer,  
400kV RS (O&M) Division, Girwali Tq. Ambajogai Dist: Beed. PIN code: 431519.  
Contact No: 02446-259670. Fax No: 02446-259689.  
Email ID: [ee2210@mahatransco.in](mailto:ee2210@mahatransco.in) Website: [www.mahatransco.in](http://www.mahatransco.in)

Ref: -EE/400kV/RS(O&M)/Dn/GRL/Tech/727

Date:- 30.12.2021

**E-Enquiry**

**Enquiry No. EE/400kV/RS/Dn/GRL/E-Enquiry2021-22/22**

**Sub:** - Firm quotation for work of emergency replacement of failed 400kV TELK make circuit breaker of 400kV Solapur line at 400kV Substation Girwali under 400kV RS O&M Div., Girwali.

**Dear Sir,**

The Sealed & Super scribed quotations are invited from supplier/ vendors for subject items as per details given in schedule 'A' subject to following conditions:-

**1) DUE DATE:** - The quotations complete in all respects i.e. offer rates should be filled in given work Schedule "A" format copy duly signed, sealed & super scribed, along with covering letter of bidder/agency with above mentioned subject shall be submitted to this office on or before **03.01.2022** up to **17:00 Hrs** positively.

**2) SCOPE:** - As detailed in schedule 'A'.

**3) QUOTED RATES:** - The quoted rates should consider as per specification for work mentioned in Schedule "A". Taxes & Charges shall be mentioned clearly. If not mentioned it will be considered inclusive of all taxes & charges.

**4) GST TAX:** - GST tax will be as applicable as per the rules.

**5) TIME OF CONTRACT:** The time will be reckoned from the date of actual commencement/ of work & will lasts for next 12 months.

**6) PAYMENT:** - 100% payment will be made after satisfactorily completion of work order, subject availability of funds by MSETCL.

**7) SECURITY DEPOSITE:** - The successful bidder will have to pay an amount equivalent to 3 % of contract value towards S.D. at concerned Division office.

**8) VALIDITY OF OFFER:** - The offer should be valid for our acceptance for a period of 60 days from the Due date of same.

**9) SIGNING OF CONTRACT:** - Agreement contract between MSETCL authority & you should be carried out on Rs.500 bond paper within 7 days from the date of receipt of the work order. You will have to borne the charges for agreement bond

**10) DOCUMENT REQUIRED:** - The rate offer must be accompanied with following documents duly attested & signed by vendor.

1. Electrical Contractor License.
2. Shop act.
3. GST Registration certificate.
4. Copy of PAN card.
5. Experience Certificate: Experience certificate of similar work carried out from the rank not below Executive Engineer under MSETCL should be submitted.

**11)** The undersigned have the reserve right for relaxation of any condition mention above.

**12)** The undersigned reserved the rights for cancellation of any or all quotations without assigning any reason.

**13)** No advance payment shall be made in any case.

Yours faithfully,

s/d  
**Executive Engineer**  
**400kV R.S. (O&M) Division, Girwali**

**Encl.:-** Schedule 'A'.

**Copy s.w.r. to: -**

- 1) The Superintending Engineer, EHV (O&M), Circle, Parli (V).

**Copy to: -**

- 1) The Dy. Manager (F&A), 400KV RS (O&M), Division, Girwali.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

Name of Office: 400kV RS (O&M) Dn., Girwali.

Office Address: Executive Engineer,

400kV RS (O&M) Division, Girwali Tq. Ambajogai Dist: Beed. PIN code: 431519.

Contact No: 02446-259670. Fax No: 02446-259689.

Email ID: ee2210@mahatransco.in Website: www.mahatransco.in

**Enquiry No. EE/400kV/RS/Dn/GRL/E-Enquiry2021-22/22**

**Schedule "A"**

**Scope of Work:** Work of emergency replacement of failed 400kV TELK make circuit breaker of 400kV Solapur line at 400kV Substation Girwali under 400kV RS O&M Div., Girwali.

Sr. No.	Particulars	Unit	Qty	Rate
1	Expansion type terminal connector on CB to suit 4"IPS AL tube. 3150 Amps	No.	1	
2	Terminal connector on CB to suit 0.5moose conductor 3150 Amps	No.	1	
3	Supply of New SF6 Gas Cylinder (25kg)	No.	1	
4	Erection of Circuit breaker with required modifications of existing foundations as per drawing with erection of support structure its leveling, mechanism, pole, required piping, cabling and termination up to MB, earthing of CB poles and structures , MB etc. with filling of SF6 if required to specified pressure, fixing of related accessories etc. complete as directed by the Mfg. manual and assisting testing and attending the problems if any up to commissioning for (SF6 shall be supplied by MSETCL.)	No.	1	
5	Expansion type terminal connector on CB to suit 4"IPS AL tube. 3150 Amps	No.	1	
6	Terminal connector on CB to suit 0.5moose conductor 3150 Amps	No.	1	

7	Dismantling of Circuit Breaker with removal of SF6 / Oil and removal of pole, mechanism, wiring and cabling and piping, removal of support structure etc. complete for 420kV Circuit Breaker	Set	1	
8	Dismantling of expansion type terminal connector on CB to suit 4"IPS AL tube. 3150 Amps	No.	1	

Taxes applicable (if any): -

1)

2)

**Name, Signature and seal of Agency.**

Address: \_\_\_\_\_  
 \_\_\_\_\_

Mobile No. \_\_\_\_\_

**Signature of Agency  
 with rubber stamp**

s/d  
**Executive Engineer  
 400kV R.S.(O&M) Dn., Girwali**