



The Maharashtra State Electricity Transmission Company Limited.

From :

Name of Office : The Executive Engineer, 400 kV RS DIVISION, Waluj.

Official Address : Plot No. L2-L3, NEAR SAT, WALUJ MIDC, MSETCL,
AURANGABAD-431 136

Contact No. : (O) - 0240-2 56 31 51
(P) - 0240-2 55 25 33

Fax No. : 0240-2 55 57 50

Control Room : 0240-2 56 31 51

Email Id : ee2130@mahatransco.in

Website : www.mahatransco.in

Ref.No. EE/400KV/RSDn/WLJ/Tech/ **No - 002 1,**

Date: **14 JAN 2022**

Enquiry

Sub: Work for repairs & maintenance of FCC box of ICT at 400 KV Waluj S/S under 400 KV R. S. Division, Waluj..

Dear Sir / Madam,

Sealed & Super scribed quotations are hereby invited, by undersigned, for the Work of repairs & maintenance of FCC box of ICT at 400 KV Waluj S/S under 400 KV R. S. Division, Waluj , amounting to **Rs. 99,628/-(Ninety Nine Thousand Six Hundred Twenty Eight Only)** Inclusive of GST. Submit the sealed quotations to this office during Dt. 14.01.2022 at 11:00 Hrs. to Dt. 20.01.2022 Up to 17:00 Hrs.

The Other Terms & Conditions are as follows:

1. Quotations should be duly filled in all respect & to be submitted to this office, within due date.
2. Work order is Rs. **99,628/-(Ninety Nine Thousand Six Hundred Twenty Eight Only)** Inclusive of GST. Works will be carried out as per actual requirement of 400KV R.S. Dn., Waluj. Payment will be made on the basis of actually executed works.
3. Rates should be quoted in Schedule-A, combinedly for all particulars, in the Estimated Rates.
4. Enclose the copies of following documents, along with quotations:
 - Valid Electrical License
 - Shop Act License
 - Pan Card
 - GST Registration
 - ESIC Registration
 - Experience If any
5. Other Terms & Conditions, as per Company's Rule will be binding upon you.'

Thanking You,

Yours Faithfully,

Executive Engineer,
400KV R.S Division, Waluj

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

400KV R. S. Division Waluj

Schedule "A" for Enquiry

Sub:- Work for repairs & maintenance of FCC box of ICT at 400 KV Waluj S/S under 400 KV R. S. Division, Waluj.

SR NO.	DESCRIPTION	UNIT	QTY	UNIT RATE	Labour Cess 1%	F & I @ 2 %	Sub total	GST @ 18 %	Net Unit Rate	TOTAL AMOUNT
A	Supply Portion									
1	63A TPN SFU IN SHEET STEEL ENCLOSURE	NOS.	1	4700	47	94	4841	871	5712	5712.38
2	40A CYLINDRICAL FUSE LINK (HF TYPE)	NOS.	3	3750	38	75	3863	695	4558	13673.25
3	50 A, AC-3 , CONTACTOR, 3 POLE WITH 240V AC COIL VOLTAGE	NOS.	1	5900	59	118	6077	1094	7171	7170.86
4	9 A, AC-3 , CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 415 AC COIL VOLTAGE	NOS.	1	1550	16	31	1597	287	1884	1883.87
5	OFF DELAY TIMER	NOS.	1	3930	39	79	4048	729	4777	4776.522
6	9 A, AC-3 , CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 240 AC COIL VOLTAGE	NOS.	1	950	10	19	979	176	1155	1154.63
7	ON DELAY TIMER	NOS.	1	2900	29	58	2987	538	3525	3524.66
8	9 A, AC-3 , CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 240 AC COIL VOLTAGE (FAN MOTOR CONTACTOR)	NOS.	1	950	10	19	979	176	1155	1154.63
9	4 NO ADD ON BLOCK FOR MNX 9 CONTACTOR (FRONT MOUNTING)	NOS.	1	560	6	11	577	104	681	680.624
10	1 NO + 1 NC ADD ON BLOCK FOR MNX 9 CONTACTOR (SIDE MOUNTING)-FIRST LEFT	NOS.	1	460	5	9	474	85	559	559.084
11	18 A, AC-3 , CONTACTOR, 3 POLE, INBUILT 1 NC AUX. CONTACT WITH 240 AC COIL VOLTAGE(PUMP MOTOR CONTACTOR)	NOS.	1	1740	17	35	1792	323	2115	2114.796
12	4 NO ADD ON BLOCK FOR MNX 18 CONTACTOR (FRONT MOUNTING)	NOS.	1	560	6	11	577	104	681	680.624
13	1 NO ADD ON BLOCK FOR MNX 18 CONTACTOR (FRONT MOUNTING)	NOS.	1	320	3	6	330	59	389	388.928

14	1 NO + 1 NC ADD ON BLOCK FOR MNX 9 CONTACTOR (SIDE MOUNTING)-FIRST LEFT	NOS.	1	460	5	9	474	85	559	559.084
15	MCB. 6A, 4P, 10 KA, C- CURVE FOR FAN MOTOR CIRCUIT BREAKER	NOS.	1	1200	12	24	1236	222	1458	1458.48
16	MCB. 25A, 4P, 10 KA, C- CURVE FOR PUMP MOTOR CIRCUIT BREAKER	NOS.	1	1900	19	38	1957	352	2309	2309.26
17	0.9-1.5A (FAN MOTOR) THERMAL OVERLOAD RELAY WITH INBUILT SINGLE PHASING PROTECTION (MN2- DIRECTLY OPERATED)	NOS.	1	1550	16	31	1597	287	1884	1883.87
18	3-5A (PUMP MOTOR) THERMAL OVERLOAD RELAY WITH INBUILT SINGLE PHASING PROTECTION (MN2- DIRECTLY OPERATED)	NOS.	1	1350	14	27	1391	250	1641	1640.79
19	16A, 4-POLE, 2-WAY SELECTOR SWITCH WITH CENTER OFF(60*) FOR COOLER CONTROL	NOS.	1	800	8	16	824	148	972	972.32
20	16A, 1-POLE ON-OFF SELECTOR SWITCH(60* OPERATION) FOR HEATER	NOS.	1	725	7	15	747	134	881	881.165
21	16A, 2-POLE, 2-WAY SELECTOR SWITCH WITH CENTER OFF(60*) FOR COOLER CONTROL	NOS.	1	820	8	16	845	152	997	996.628
22	16A, 3-POLE, 2-WAY SELECTOR SWITCH WITH CENTER OFF(60*) FOR COOLER CONTROL	NOS.	1	730	7	15	752	135	887	887.242
23	THERMOSTAT	NOS.	1	800	8	16	824	148	972	972.32
24	SPACE HEATER	NOS.	1	900	9	18	927	167	1094	1093.86
25	LED PANEL LIGHT (FLOURSCENT TUBE)	NOS.	1	500	5	10	515	93	608	607.7
26	LIMIT SWITCH FOR LED PANEL LIGHT	NOS.	1	300	3	6	309	56	365	364.62
27	SS COMBINED AC PLUG SOCKET	NOS.	1	340	3	7	350	63	413	413.236
28	1.5-6 SQMM 41A, 800 V,M4 CAPTIVE NUT STUD TYPE TERMINAL	NOS.	1	45	0	1	46	8	55	54.69
29	SINGLE PHASE PROTECTOR	NOS.	1	2500	25	50	2575	464	3039	3038.5
Total										61608.626

SR NO.	DESCRIPTION	QTY	UNIT	Labour Ex Rate	Labour Cess 1%	Total	GST 18%	Net Unit rate	TOTAL AMOUNT	Remarks
B Labour Portion										
1	63A TPN SFU IN SHEETSTEEL ENCLOSURE	1	NOS.	650	7	657	118	775	775	
2	40A CYLINDRICAL FUSELINK (HF TYPE)	3	NOS.	450	5	455	82	536	1609	
3	50 A, AC-3 , CONTACTOR, 3 POLE WITH 240V AC COIL VOLTAGE	1	NOS.	750	8	758	136	894	894	
4	9 A, AC-3 , CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 415 AC COIL VOLTAGE	1	NOS.	650	7	657	118	775	775	

5	OFF DELAY TIMER	1	NOS.	650	7	657	118	775	775	
6	9 A, AC-3, CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 240 AC COIL VOLTAGE	1	NOS.	550	6	556	100	655	655	
7	ON DELAY TIMER	1	NOS.	650	7	657	118	775	775	
8	9 A, AC-3, CONTACTOR, 3 POLE, INBUILT 1 NO AUX. CONTACT WITH 240 AC COIL VOLTAGE (FAN MOTOR CONTACTOR)	1	NOS.	550	6	556	100	655	655	
9	4 NO ADD ON BLOCK FOR MNX 9 CONTACTOR (FRONT MOUNTING)	1	NOS.	200	2	202	36	238	238	
10	1 NO + 1 NC ADD ONBLOCK FOR MNX 9 CONTACTOR (SIDE MOUNTING)-FIRST LEFT	1	NOS.	150	2	152	27	179	179	
11	18 A, AC-3, CONTACTOR, 3 POLE, INBUILT 1 NC AUX. CONTACT WITH 240 AC COIL VOLTAGE(PUMP MOTOR CONTACTOR)	1	NOS.	150	2	152	27	179	179	
12	4 NO ADD ON BLOCKFOR MNX 18 CONTACTOR (FRONT MOUNTING)	1	NOS.	150	2	152	27	179	179	
13	1 NO ADD ON BLOCKFOR MNX 18 CONTACTOR (FRONT MOUNTING)	1	NOS.	150	2	152	27	179	179	
14	1 NO + 1 NC ADD ONBLOCK FOR MNX 9 CONTACTOR (SIDE MOUNTING)-FIRST LEFT	1	NOS.	150	2	152	27	179	179	
15	MCB: 6A, 4P, 10 KA, C- CURVE FOR FAN MOTORCIRCUIT BREAKER	1	NOS.	550	6	556	100	655	655	
16	MCB: 25A, 4P, 10 KA, C-CURVE FOR PUMP MOTOR CIRCUIT BREAKER	1	NOS.	650	7	657	118	775	775	
17	0.9-1.5A (FAN MOTOR) THERMAL OVERLOAD RELAY WITH INBUILT SINGLE PHASING PROTECTION (MN2- DIRECTLY OPERATED)	1	NOS.	650	7	657	118	775	775	
18	3-5A (PUMP MOTOR) THERMAL OVERLOADRELAY WITH INBUILT SINGLE PHASING PROTECTION (MN2- DIRECTLY OPERATED)	1	NOS.	650	7	657	118	775	775	
19	16A, 4-POLE, 2-WAY SELECTOR SWITCH WITHCENTER OFF(60*) FOR COOLER CONTROL	1	NOS.	350	4	354	64	417	417	
20	16A, 1-POLE ON-OFF SELECTOR SWITCH(60* OPERATION) FOR HEATER.	1	NOS.	350	4	354	64	417	417	
21	16A, 2-POLE, 2-WAY SELECTOR SWITCH WITHCENTER OFF(60*) FOR COOLER CONTROL.	1	NOS.	350	4	354	64	417	417	
22	16A, 3-POLE, 2-WAY SELECTOR SWITCH WITHCENTER OFF(60*) FOR COOLER CONTROL	1	NOS.	350	4	354	64	417	417	
23	THERMOSTAT	1	NOS.	250	3	253	45	298	298	

24	SPACE HEATER	1	NOS.	200	2	202	36	238	238	
25	LED PANEL LIGHT (FLOURSCENT TUBE)	1	NOS.	200	2	202	36	238	238	
26	LIMIT SWITCH FOR LEDPANEL LIGHT	1	NOS.	150	2	152	27	179	179	
27	SS COMBINED AC PLUGSOCKET	1	NOS.	150	2	152	27	179	179	
29	1.5-6 SQMM 41A, 800 V,M4 CAPTIVE NUT STUD TYPE TERMINAL.	1	NOS.	150	2	152	27	179	179	
30	SINGLE PHASE PROTECTOR	1	NOS.	650	7	657	118	775	775	
31	COMPLETE WIRING LABOUR CHARGES	1	NOS.	12000	120	12120	2182	14302	14302	
32	PARTIAL WIRING LABOUR CHARGES	1	NOS.	7500	75	7575	1364	8939	8939	
Total								38018		

Absrtact

	A) Supply portion	61608.626
	B) Labour Portion	38018
	Grand Total (Rounded off)	99628

The work order amount in Rs. 99628/- (Ninety Nine Thousand Six Hundred Twenty Eight only) Inclusive of GST.

Stamp & Signature of the Agency


 Executive Engineer
 400KV R.S. Division, Waluj