

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	: Executive Engineer, EHV O&M Division, Latur.
Office Address	: 132 kV Latur(MIDC) S/s Premises, Near Kirti Gold Mill, MIDC Road, Latur-413512
Contact No.	: 02382-222208 (O), 8956304905/8956304912
Email ID	: eelaturdn@gmail.com, ee2220@mahatransco.in.

Ref. No. : EE/EHV/O&M/LTR/TS/ **No 0 0 0 7 9** Date: - **20 JAN 2022**

E-Enquiry

Sub :- E-Enquiry for Work of Earthing Renovation & Supply, Laying, Commissioning of Earthing Strip & risers of existing earth pits at 132 kV AUSA & 132 kV Koyna S/s under EHV (O&M) Dn, Latur

Dear Sirs,

Sealed and super scribed quotations are invited for the work as specification given below. The quotation giving full particulars should reach this office on or before. **27.01.2022** up to 15.00 Hrs positively. The Taxation liability should show separately. Rights of cancellation/modification of E-Enquiry at any stage, is reserved at this office.

Schedule 'A'


Sr No.	Particulars	Unit	Qty	Rate/Unit (Excl. GST)	Rate/Unit (Incl. GST)	Amount in Rs.
A	Supply:-		A	B	C	D
1	75 x 10 mm, MS Earthing Strips	Rmt	410			
2	50 x 8 mm M.S. Earthing Strips	Rmt	320			
B	Laying & Commissioning					
1	Renovation of existing earth pits in S/s Switch yard area with required materials charcoal, salt, black cotton, bentonite with removal of connection on both side to earth main mat, removal of clamps, removal of CI Pipe, G.I. Perforated pipe if available with excavation of earlier of earlier material and its re-erection to C.I. Pipe along with G.I. Pipe with prescribe method of earth pit filling-with old earthing pipe	Per Pit	9			

2	Laying the provided M.S. Flat in ground at @ 0.6 Meter below ground with welding as per prescribed method at required place, bends and with required fabrication and connecting the same to the earth pit / or at any other place as directed.	Rmt	207			
3	Taking out the riser connection with provided M.S.Flat with excavation at required place up to main mat and welding the riser to main mat with required bending, drilling /fabrication etc and taking this riser to the required place of support structure foundation with making it flush with the foundation surface.	Per Riser	157			
4	Painting of Earthing risers & Laying Strip by applying one coat red oxide and two coats of Epoxy paints as directed.	Sq.M eter	155			
Total (Including all Taxes & Cess) (Rs.)						

Estimated amount for the above work: Rs. 4,69,261.72 (Including all Taxes & Cess)

- Note:-**
1. Rate of GST shall be mentioned by Bidder on their Offer with SAC Code.
 2. No Conditional bid shall be Accepted.
 3. Xerox signed copies of below mentioned documents should be attached along with quotation.
 4. Quotation shall be submit on Agency Letterhead along with Authorized Signature and Seal.

- a) PAN Card.
- b) GST registration Certificate
- c) Bombay Shop Act License
- d) Electrical Contractor License
- e) Experience certificate of similar work, issued by not below the rank of Executive Engineer


Executive Engineer,
EHV O&M Division Latur