

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,**  
(CIN No. U40109 MH 2005 SFC 153646)

**EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI**

EXECUTIVE ENGINEER (Civil)  
MSETCL, EHV CCCM Division,  
Old Power House Premises, Jintur Road, Parbhani (431 401).  
Parbhani Dist :Parbhani -431 401

Tel (0) : 02452-242002 (0)  
E-mail : [ee2720@mahatransco.in](mailto:ee2720@mahatransco.in)  
Web: www.mahatransco.in

**No. EEC/Dn./PBN /Tech/W-70/No. 103**


**Date :- 23.02.2022**

**E-Enquiry**  
**QUOTATION NOTICE**

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of The Executive Engineer (Civil) EHV CCCM Division, MSETCL, Parbhani, Old Power House Premises, Jintur Road, Parbhani on or **before Dated 04/03/2022 up to 16.00 Hrs. (Time).**

The required blank quotation to be submitted is attached herewith.

Sr. No.	Name of work	Estimated cost	E.M.D.	Time Limit
1.	The work of repairing & renovation of ladies & Gents toilet block and Internal painting to Control room at 132 kV Elichpur sub-station, Dist. Nanded.	Rs. 4,07,283.70/-	Rs. 4,080.00/-	01 Month



(V.G. Avhad)  
**Executive Engineer (C) (I/C)**  
**EHV CCCM Dn. Parbhani.**

**Copy S.W.R.S. To:**

1. The Superintending Engineer (C), EHV CCCM Circle, MSETCL, Aurangabad.  
...This is as per approval vide Ltr. No. 0208 Dt. 17.02.2022.

**Copy To:**

1. The I.T. section zone office Aurangabad.  
...**For Publication of E-enquiry on MSETCL website.**
2. The Addl. Executive Engineer (C) EHV CCCM Sub Division-I, Nanded.
3. The Dy. Manager (F&A), EHV CCM Division, Parbhani.  
-The amount of this work is Chargeable to sanctioned estimate No. T-29/ 2021-22 Dt. 23.02.2022.  
under R&M Budget.
4. Notice Board.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,**  
(CIN No. U40109 MH 2005 SFC 153646)

**EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI**

EXECUTIVE ENGINEER (Civil)  
MSETCL, EHV CCCM Division,  
Old Power House Premises, Jintur Road, Parbhani (431 401).  
Parbhani Dist :Parbhani -431 401

Tel (0) : **02452-242002** (0)  
**E-mail :**  
[ee2720@mahatransco.in](mailto:ee2720@mahatransco.in)  
Web: [www.mahatransco.in](http://www.mahatransco.in)

---

**Date :- 23.02.2022**

**E-enquiry**

To,

.....  
.....  
.....

**Subject:** The work of repairing & renovation of ladies & Gent's toilet block and Internal painting to Control room at 132 kV Elichpur sub-station, Dist. Nanded.

**Dear Sir,**

The Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of the Executive Engineer (Civil) EHV CCCM Division, MSETCL, Parbhani, Old Power House Premises, Jintur Road, Parbhani on or **before Dated 04/03/2022 up to 16.00 Hrs. (Time)**.

**TERMS AND CONDITIONS:**

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(01) MONTH** from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.

- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require any equipment, cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require labour, tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) The contractor should submit the purchase vouchers for cement, steel with the bill invariably.
- 11) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 12) As per corporate office Circular No. 7199 Dt. 30.06.2016, the deduction of the labour cess 1% will be effected from each RA bill and as per any amendment from time to time will be applicable.
- 13) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 14) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-I, Nanded to the undersigned. Payment will be made within 30 days period from the date of receipts of bill to this office.
- 15) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 16) You will have to deposit **5.00 %** of quotation value as a security deposit against the amount of work order in cash/ DD of any nationalized Bank within 07 days from the date of receipt of LOI, if you will stand successful bidder, failing which EMD will stand forfeited.
- 17) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 18) Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 19) The contractor has to pay earnest money to **Rs. 4,080.00/-** in cash/RTGS/NEFT/In form of DD of any Nationalized Bank in favor of the EE (C), EHV CCCM DIVISION, MSETC Ltd. PARBHANI. If the EMD receipt of required amount is not found in an envelope, quotation will be rejected.
- 20) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.

- 21) GST will be recovered from your bill as per GST norms.
- 22) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 23) The estimated cost of the work is **Rs. 4,07,283.70** /- only. (Inclusive of all Taxes)
- 24) As per revised circular issued by Dy. Directorate of Insurance Maharashtra State, the contractor shall, apart from other relevant insurance, submit labour insurance @ 1% of contract value to EHV CCCM Division Parbhani before starting of the work. The insurance cover shall be procured by the contractor from Director of insurance Govt, Insurance Fund, Govt of Maharashtra or from United India Insurance Company. Ltd.
- 25) Contractor has to submit the valid registration, Work Experience of similar work under Govt. body, GST registration certificate, EMD Paid Receipt as mandatory documents at the time of submission of Quotation.

**Encl.** : Schedule 'B'



**Executive Engineer (C)  
EHV CCCM Dn. Parbhani.**

Copy S.W.R.S. To :

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.  
...This is as per approval vide Ltr. No. 0208 Dt. 17.02.2022.



**MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,**  
**(CIN No. U40109 MH 2005 SFC 153646)**

**EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI**

EXECUTIVE ENGINEER (Civil)  
MSETCL, EHV CCCM Division,  
Old Power House Premises, Jintur Road, Parbhani (431 401).  
Parbhani Dist :Parbhani -431 401

Tel (O) : **02452-242002** (O)  
**E-mail :**  
[ee2720@mahatransco.in](mailto:ee2720@mahatransco.in)  
Web: [www.mahatransco.in](http://www.mahatransco.in)

**Work:** The work of repairing & renovation of ladies & Gents toilet block and Internal painting to Control room at 132 kV Elichpur Sub-Station, Dist. Nanded.

**Estimated Amount:** - Rs. 4,07,283.70 /- (Inclusive of All Taxes)

Executive Engineer (C)  
EHV CCCM Division,  
MSETCL, Parbhani.

**Quotation for Works**

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure) .....% above/ below/ Estimated Rate (in Words) ..... percent above/ Below/ Estimated rate (to be struck whichever is not applicable) the estimated rates (Incl. GST) entered in schedule “B” (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

**Signature of the contractor :** \_\_\_\_\_

**Name & Firm Seal :** \_\_\_\_\_

**Full Address :** \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

**EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI**

**Work:** The work of repairing & renovation of ladies & Gents toilet block and Internal painting to Control room at 132 kV Elichpur sub-station, Dist. Nanded.

**Abstract**

S. N.	Description	Unit	Quantity	Rate (Inl. GST)	Amount
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete.	Sqm	41.73	50.00	2086.50
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC without SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	Cum	0.98	7097.0	6955.05
3	Providing and laying Antiskid Ceramic tiles of RAK/Kajaria/Nitco/AGL approved quality of size 30 cm x 30 cm and confirming to IS 15622-2006 (Group-B IIA) for antiskid flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.	Sqm	13.08	1421.00	18586.68
4	Providing and laying ceramic tiles of RAK/Kajaria/Nitco/AGL having size 30cm.x60cm.. and confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete	Sqm	45.89	1533.00	70349.37
5	Providing and fixing W.C.PAN Coloured glazed 64CM.(Orissa) type including Strap with earthenware foot rests,cast iron soil and vent pipe upto outside face of the wall 1:2:4 brick bat lime concrete bedding without flushing tank and its accessories etc. complete.	No	1.00	3624.00	3624.00
6	Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	No	1.00	6338.00	6338.00
7	Providing and fixing 10cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete.	No	3.00	1316.00	3948.00

8	Providing and fixing fiber glass reinforced polyester door shutter 30 mm thick as per IS 14856(2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc complete	Sqm	2.10	3563.00	7482.30
9	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.	Sqm	2.52	3365.00	8479.80
10	Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm conforming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete.	Rmt	25.00	598.00	14950.00
11	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density polythylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet,outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	Lit	1000.00	15.00	15000.00
12	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and C.I. lid cover of 75Kilogram with lid and frame fixed in cement concrete	Nos	2.00	9317.00	18634.00
13	Providing and fixing at required opening GI steel French door frame section 1.2mm thick,100mm section.1mm door shutter with 4mm glass as per detailed drawing and design or as directed including providing 10mm bar for safety as per technical specifications etc.. necessary fixtures and fastening i.e SS aldrops, tadipatti,towerbolt and handle hold fasts, stoppers, locking arrangement etc. completed as directed by Engineer-in-Charge.	Sqm	10.56	8068.00	85198.08
14	Providing and fixing on walls/ceiling/floor 15mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipeline if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Rmt	10.00	293.00	2930.00

15	Providing and fixing on walls/ceiling/floor 20 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipeline if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Rmt	20.00	340.00	6800.00
16	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.	Nos	5.00	759.00	3795.00
17	Providing and fixing screw down for 25 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	Nos	3.00	936.00	2808.00
18	Replacement of damaged Aldrop 300 mm Chromium plated of approved quality and make to door shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-charge	Nos	2.00	405.00	810.00
19	Replacement of damaged Tower Bolt 300 mm Chromium plated of approved quality and make to door/window shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-charge.	Nos	2.00	205.00	410.00
20	Replacement of damaged Alluminium Handle 125 mm of approved quality and make to door/window shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer incharge.	Nos	2.00	194.00	388.00
21	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	Nos	5.00	175.00	875.00
22	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materials outside etc. carefully and throwing out the refusal outside etc. complete.	Nos	1.00	232.00	232.00
23	Providing and fixing M40 grade thick vibrated pull cast or similar type concrete frame with chamfer conforming to I.S. 65241983 having 6 mm dia. bars 3 Nos. And stirrups @250 mm c/c and fixing in wall with 6 Nos of hold fast of 12 mm dia bars 500 mm long including primer and oil painting etc, complete) frame size 60 mm x 100 mm .	Rmt	4.90	1071.00	5247.90
24	Providing and fixing glass to opening as per requirement and as directed by Engineer in charge.(glass obscured (bajara) 5mm)	Sqm	0.90	755.00	679.50
25	Providing and fixing in position powder coated aluminium louvered windows/ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames80x38mmx1.22mmboxtype,5mm thick sheet glass louvers, of approved quality etc. complete.With	Sqm	0.63	3703.00	2332.89



	removing and repairing if required				
26	Manually clearing the chokes from under ground drainage line including Inspection chambers with the help of required tools for proper functioning line chamber to chamber etc. complete.	Rmt	50.00	55.00	2750.00
27	Providing internal cement plaster 20mm thick in Single coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete.	Sqm	5.00	534.00	2670.00
28	Providing and fixing 75 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc.	Rmt	5.00	642.00	3210.00
29	Removing old paint from steel/cement plaster and other metal surfaces and making the surface even with hand scrapping, scaffolding, etc. complete.	Sqm	582.00	19.00	11058.04
30	Providing and applying priming coat on concrete/masonry/Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	Sqm	582.00	41.00	23862.08
31	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in two coats including scaffolding, preparing the surface (excluding primer coat), etc. complete.	Sqm	741.21	83.00	61520.18
32	Providing and applying two coats of lead / zinc base oil paint / bituminous paint of approved colour to new structural steel work and iron work in buildings including scaffolding if necessary, cleaning and preparing the surface, etc. complete. (excluding primer coat).	Sqm	131.42	101.00	13273.42
	Total Rs. =				<b>4,07,283.70</b>

  
**Executive Engineer (C)**  
**EHV CCCM Division, MSETCL,**  
**Parbhani**