



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

CIN U40109MH2005SGC153646

EHV (O&M) DIVISION, SOLAPUR

From:

Name of Office: Office of the Executive Engineer,

Office address: Adm. Building at 220 KV Bale premises, Ambikanagar Barshi
Road Bale Solapur-413255.

Phone No. 0217- 2351827 (O) 0217- 2350673 (P) Fax No. 0217- 2351827

Email ID: ee6210@mahatransco.in

Ref No: EE/EHV/(O&M)/DN/SUR/T/ No-0608 Date:- 29 APR 2022

Enquiry

Sub: - E-Enquiry for the work of renovation of existing Electric wiring of Control Room, Battery Room, Charger Room and various offices available at 132Kv Degaon Substation under jurisdiction of Trans O&M Division, Solapur..

Estimated Amount in Rs. – Rs. 5,24,124/-only. (Inclusive of All Taxes).

Date of Publication Enquiry: - From Dtd. 29.04.2022 To Dtd.08.05.2022.

Last Date for Submission of Offer: - Dtd.08.05.2022.

Dear Sir,

MSETCL invites offline bids (Quotation) from registered contractors /agencies for above said work as per schedule 'A'. You are requested to quote your lowest rate for the same via submission of quotation to this office on or before Dtd. 08.05.2022.

TERMS & CONDITIONS

1. Offer should be submitted via Quotation to this office on OR before dtd.08.05.2022.
2. Rate must be quoted including of all taxes & duties.
3. 5% security deposit will be required to be paid before affecting the work which will be retained till Guarantee period is over.
4. The rate quoted should be valid at least for three month from the date of opening of quotation.
5. The quotation not confirming to specifications as desired below are likely to be rejected.
6. Right to accept / reject any or all Quotations or part thereof reserved by the undersigned.
7. The interpretations of undersigned on any matter of decision given by him on any disputed point will be final and binding on contractor.
8. The documents of an offer shall be written legible and free from erasures, over writing or conversion of figures, corrections where unavoidable shall be made by crossing out, rewriting initialing and dating.
9. If the bidder has any doubt the meaning of any portion of the enquiry conditions/ specifications, he should get it clarified from the office of the undersigned before submission of the offer.
10. Contractors are permitted to be present at the time of opening of quotations.

11. Attested copies of following documents along with offer should be submitted.

- a) Valid registration of firm under Bombay Shop Act and Establishment Act if available.
- b) Valid GST Registration Certificate.
- c) Income Tax Return of Last F. Y Saral form (FY-2020-21).
- d) Valid Electrical Contractor License.
- e) If available Work order along with Experience certificate for carrying out similar type of work shall be enclosed along with Quotation. However preference shall be given to experienced contractor.

Encl:- Schedule 'A' & B.

Your's Faithfully.

R.T. Shelke
Executive Engineer
EHV (O&M) Division, Solapur.

Copy to:-

1. Notice Board.
2. MSETCL WEBSITE/ SRM Portal.

Maharashtra State Electricity Transmission Company LTD.

CIN NO.U40109 MH 2005 SGC 153646

EHV O&M Division, Solapur.

Schedule 'A'

Sub :- E-Enquiry for the work of renovation of existing Electric wiring of Control Room, Battery Room, Charger Room and various offices available at 132Kv Degaon Substation under jurisdiction of Trans O&M Division, Solapur.

SR. No.	Name of item	Qty	UNIT	Rate	Amount
PART - A					
1	Supplying and erecting mains with 3 x 6 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-16 P No. 13 (6)	100	Mtr.	171	17100
2	Providing & erecting 3 Pole MCCB upto 100A, 415V capacity with S.C. rating 25 kA (Ics=100% of Icu), thermal setting with specification No. SW-SWR/MCCB provided leads on iron /G.I. frame as per specification No. SW-SWR/MCCB specification No. SW-SWR/MCCB DSR I. No. 5-5-1 P. No. 109 (98)	4	Each	4771	19084
3	Supplying and erecting mains with 3 x 4 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-14 P. No. 13 (6)	100	Mtr.	121	12100
4	Supplying and erecting mains with 3 x 2.5 sq.mm. F.R. L.S. copper PVC insulated wire laid in provided conduit / trunking / inside pole / Bus bars or any other places as per specification No. WG-MA/BW DSR I. No. 1-3-12 P. No. 13 (6)	250	Mtr.	84	21000
5	Point wiring for light / fan / bell in min 25mm casing - n - capping with 1.5 sq.mm. FR grade copper wires with modular type switch and required accessories as per specification No. WG-PW/SW DSR I. No. 1-9-6 P. No. 32	200	Point	437	87400
6	Wiring for plung on board with Switch socket with copper wiring, earthing as per specification No. WG-PW/SW DSR I. No. 1-9-13 P. No. 17	30	Point	102	3060

7	Point wiring for independent plug in min 20 mm PVC conduit with 1.5 sq.mm FR grade copper wires with modular type switch and socket and required accessories as per specification No. WG-PW/SW DSR I. No. 1-9-27 P. No. 18.	150	Point	627	94050
8	Supplying and erecting PVC trunking (PVC casing-n-caping) of size 25mm with accessories on wall / ceiling as per specification No. WG-MA/CON, para no. DSR I. No. 1-2-7 P. No. 4.	200	Mtr.	81	16200
9	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface / flush mounted with 2 ways for incoming and 10 ways for outgoing SP MCB's on iron frame / wooden board as per specification No. SW-SWR/MCBDB DSR I. No. 5-4-19 P. No. 108 (97)	3	Nos	1347	4041
10	Supplying and erecting original 1.25 mm CRCA sheet metal enclosures with 20A, 2 pin plug & earth socket and 20A, 3 pin plug top with 20A/30A single pole MCB complete erected on angle iron frame. DSR I. No. 5-4-20 P. No. 97	10	Nos	747	7470
11	Supplying and erecting modular type electronic step regulator for fan two module ISI mark approved make duly erected on provided plate and box with wiring connections complete. DSR I. No. 1-8-23 P. No. 21 (14)	16	Nos	368	5888
12	Providing earthing with Copper earth plate size 30 x 30 x 0.315cm complete with all material, testing & recording the results as per specification No. EA-EP DSR I. No. 9-1-2 P. No. 174 (159)	7	Nos	5872	41104
13	Supplying & erecting Ding Dong/ electronic musical type call bell with heavy duty coil suitable to operate on 230V AC supply erected on polished double wooden block/sunmica block of suitable size.DSR I. No. 2-4-13 P. No. 33	4	Each	131	524
14	Supplying & erecting 2 light wall bracket Aluminum body& arm anodized/ power coated complete with lamp holder and decorative glass shade suitably erected on polised wiiden/ plywood pasted with laminated DSR I. No. 2-2-8 P. No. 31	18	Each	379	6822

15	Supplying & erecting 2 x 36/40W FTL corrosion proof capsule type in non corrosive poly carbonate housing and prismatic polycarbonate cover with individual high power electronic ballast saving power factor >0.9 and working voltage range of 170-270V ACIP 65 protection suitable for cold storage area to be fixed in false ceiling or at ceiling or on wall complete DSR I. No. 2-3-1 P. No. 32	20	Each	3503	70060
16	Supplying & erecting regular/ standard model ceiling fan of 1400mm sweep complete ercetd in position as per specification no. FG-FN/CF DSR I. No. 2-12-21 P. No. 142	16	Each	2042	32672
17	Dismantling & Stacking existing Wiring DSR I. No. 1-15-1 P. No. 27	150	point	8	1200
				Sub Total	439775
				Labours Cess @ 1%	4398
				Sub Total	444173
				CGST @ 9 %	39976
				CGST @ 9 %	39976
				Grand Total	524124

* Estimated Cost: Rs,5,24,124- only. (Rs. Five Lakh Twenty Four One Hundred Twenty Four Only) Inclusive of all taxes.

Note:-

- 1) % Rate must be quoted including of all taxes.
- 2) If the percentage variation of estimated rates is more than (+) 5% detailed rate analysis should be submitted if so desired by the accepting authority.
- 3) if there is any discrepancy in figure and in words the rates quoted in words will be considered.

Executive Engineer,
EHV (O&M) DIVISION, SOLAPUR

This is to confirm that I have studied description of items in detail. I have visited the site made myself and conversant with the site & working conditions.

I am ready to execute the above prescribed work with.

- 1) % Below [In words] of the Estimated cost.
- 2) At par [In words] of the Estimated cost.
- 3) Above [In words] of the Estimated cost.

Dated

Signature of Contractor with seal

Name:

Address: