

- OFFICE OF THE -
EXECUTIVE ENGINEER (C)
EHV Civil Construction Cum Maintenance Division,
Maharashtra State Electricity Transmission Company Ltd.
Plot No.P21,132 KV S/Stn. Premises, MIDC,
Latur-413 531.
Tel. No. 02382 – 222373,
E_mail :ee2730@mahatransco.in

No.: EEC/EHV/CCCM Dn./LTR/T/No **235**

Date:- **11.05.2022**

E-Enquiry

Sub: Work of renovation & repair of electrical wiring of class III staff quarters (4T) at 132kV Substation Ahemedpur, Dist. Latur.

Sealed and super scribed Item Rate quotations are invited for above work as per the Schedule 'B' attached so as to reach this office on or before 18.05.2022 up to 14.00 hrs. The Quotations will be opened on the same day if possible.

TERMS AND CONDITONS:

1. Work is to be done at **132kV Substation Ahemedpur, Dist. Latur.**
2. The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop: (Technical Bid)

- Valid Certificate of Registration of appropriate class for Civil works from PWD/MES/ Railways/Jeevan Pradhikaran Etc Or From Any Govt./ Central Government and registered vendor of MSETCL.
- GST/ GSTIN Registration Certificate.
- Experience of having successfully completed similar civil works.
- Payment of EMD Rs. 5000.00 to be made by bidder off-line in cash only up to **14.00 hrs of 18.05.2022** in the office of EE(C), Dn, **Latur**. EMD Amount and MR No. should be super-scribed on the Envelope & having registered vendor of MSETCL

(b) Documents in 2 Envelop: (Price Bid)


- Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE :- Envelop No.2 (Price Bid) will be opened after qualifying in Envelop No. 1 i.e. in Technical Bid.

3. Work is to be completed within 30 Days from the date of handing over of site. If it is not completed within this period, penalty will be charged at the rate of half percent per week, maximum up to 10% of work order amount.
4. Quantities mentioned in Schedule 'B' of e-enquiry are approximate and payment will be made on actual quantities of the work executed.
5. Payments will be made in first and final bill/ R. A. bills at the discretion of undersigned & as per the availability of funds.
6. Our rates are inclusive of GST. GST will be paid / deducted through / from your bills as applicable as per prevailing rate, rules and Act.
7. Work is to be carried out strictly as per the standard specification and as directed by the Engineer in charge.
8. In case of any dispute, the decision of the Executive Engineer (C), EHV CCCM Division, Latur will be final and binding on the contractor.
9. If any damages occur to the Company's property, during execution, contractor will have to make them good at his own cost.
10. In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL.
11. Income tax at prevailing rate as applicable on basic amount of bill will be recovered from your bill.
12. All terms and conditions as per the Company's rules including those in the booklet, Tender and contract for works are applicable in this case also.
13. Right to reject any or all quotations without assigning any reasons is reserved by the undersigned.
14. Lowest bidder will have to pay 5% S.D. on value of the work order in the form of F.D.R of scheduled or Nationalized Bank / Bank guarantee prior to starting of work.
15. Water charges @ 0.25% and energy charges @ 0.25% will be recovered from your bill wherever water / energy supplied departmentally.
16. No material will be supplied by MSETCL.
17. The material to be utilized should be used after getting approval from Engineer-in-charge.
18. Labour cess @ 1% of the value of work executed will be recovered through contractor's bill as per G.R. of Government.
19. You have to submit labour insurance amounting to 1% of work order amount before starting of work.

20. As per the rules of MSETCL, you will have to enter into an agreement with the company before starting of work on stamp paper of Rs. 500/- the cost of which will be borne by the agency.

21. All the compulsory documents are to be submitted while submitting bid, non-submission of any compulsory document will result in disqualification of bidder & no further correspondence will be made in this regards. Hence the bidder should ensure that all the required documents/information is enclosed properly while submitting the bid.


(N. L. Namde)
Executive Engineer (C)
EHV CCCM Division
Latur

Encl: Schedule 'B'

Copy s. w. r. to:-

The Superintending Engineer (C), EHV, CCCM Circle, Aurangabad.

Copy to:-

- 1) Addl. Executive Engineer (C), EHV CCCM S/Dn, **Latur**.
- 2) The Dy. Manager (F&A), EHV, CCCM Division, Beed.

MAHARSASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**EHV CIVIL CONSTRUCTION DIVISION LATUR.**

Name of work :- Renovation & repairs of electrical wiring CL - III Staff quarters (4 Ten.) at 132kV Ahemadpur Dist-Latur.


SCHEDULE " B"

It No.	Description of item	Unit	Qty.	Basic Rate	GST 18%	Rate incl GST 18%	Amount
10	Providing and fixing light point wiring in P.V.C. casing capping by using 1.00 Sqm. Multistrand unilay wire with modular type approved make switches fixed in plate on PVC box with necessary fixture and fastening and labour complete as directed by Engineer in charge.	Each	72.00	469.00	84.42	553.42	39846.24
20	Providing and fixing independent plug point wiring in P.V.C. casing capping by using 1.00 Sqm. Multistrand unilay wire with modular type approved make switches fixed in plate on PVC box with necessary fixture and fastening and labour complete as directed by Engineer in charge.	Each	4.00	627.00	112.86	739.86	2959.44
30	Providing and fixing plug on board point (surface) wiring in P.V.C. casing capping by using 1.00 Sqm. Multistrand unilay wire with modular type approved make switches fixed in plate on PVC box with necessary fixture and fastening and labour complete as directed by Engineer in charge.	Each	18.00	481.00	86.58	567.58	10216.44
40	Providing and fixing Bell POINT WIRING in PVC casing, capping by using 1.00 Sqm. Multistrand unilay wire with modular type bell switch Anchor Roma make fixed on plate and PVC box and wooden board for fixing bell including all fixtures & labour as directed by the Engineer in charge. (Average length of wiring 14.00 mtr.)	Each	4.00	393.00	70.74	463.74	1854.96
50	Providing and fixing two way point wiring by using 1.00 Sqm. Unilay wire concealed in PVC casing capping with modular type approved make two way switches, plates and PVC box etc. complete with all fixtures and labour as directed by the Engineer in charge.	Each	1.00	703.50	126.63	830.13	830.13
60	Providing and fixing power light point concealed in PVC casing capping by using 4.00 Sqmm. Unilay make wire with approved make switches fixed in plate and box with all labour and fixtures complete as directed by the Engineer in charge.	Each	12.00	1646.00	296.28	1942.28	23307.36
70	Providing and fixing main wiring from Circuit board to switch by using 1.50 Sqm. unilay make main wire and 1.00 Sqm. Unilay make earthing wire etc. complete with all labour fixtures etc. complete as directed by the Engineer in charge.	Rmt	108.00	130.50	23.49	153.99	16630.92
80	Providing and fixing circuit Board on T.W. Board of 12" x 10" in a 6 way metal box with 10 to 20 A approved make MCB- 4 nos. and 1 no. of Anchor make 2 pole isolator / MCB with all labour screw and fixtures etc. complete as directed by the Engineer in charge.	Each	4.00	4401.63	792.29	5193.92	20775.69

It No.	Description of item	Unit	Qty.	Basic Rate	GST 18%	Rate incl GST 18%	Amount
90	Providing and fixing main wiring from Circuit board to switch by 4 Sqmm unilay make main wire and 1.00 Sqm. Unilex make earthing wire using 1.50 Sqm. unilay make main wire and 1.00 Sqm. Unilex make earthing wire etc. complete with all labour fixtures etc. complete as directed by the Engineer in charge.	Rmt	104.00	193.50	34.83	228.33	23746.32
100	Providing and fixing extra wiring for light point, power point, telephone point wiring including casing, capping extra wire for point etc. completed. for light point with PVC casing	Rmt	48.00	130.50	23.49	153.99	7391.52
110	Providing and fixing electrical fixtures Philips make 1200 mm long Tarang brand tube light	Each	12.00	926.00	166.68	1092.68	13112.16
120	Providing and fixing electrical call bell of Anchor make or equivalent.	Each	4.00	131.00	23.58	154.58	618.32
130	Supplying and erecting regular/ standard model ceiling fan of 1400mm. sweep complete erected in position as per specification no. FG-FN/CF	Each	8.00	2042.00	367.56	2409.56	19276.48
140	Providing and fixing electrical fixtures Bajaj, Crompton make Bulk- heads	Each	4.00	1425.00	256.50	1681.50	6726.00
150	Providing and fixing step type regulator for	Each	12.00	525.00	94.50	619.50	7434.00
160	Supplying and erecting corridor/passage light fitting (2 feet) including 9W LED lamp, comprises of extruded channel in plastic silver grey colour & with same plastic end cap on provided PVC block / wooden board.	Each	32.00	521.00	93.78	614.78	19672.96
170	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover complete with all materials, testing & recording the results as per specification no. EA-EP	Each	1.00	5476.00	985.68	6461.68	6461.68
180	Removing old wiring and connections care fully from ceiling and wall stacking the material at required place as directed by Engineer in charge. Electrician	Each	10.00	641.00	115.38	756.38	7563.80
190	Removing old wiring and connections care fully from ceiling and wall stacking the material at required place as directed by Engineer in charge. Helper - unskilled	Each	10.00	611.00	109.98	720.98	7209.80
200	Providing and fixing 100 Amp., 415 V busbar, Ravi make for controlling supply of electricity for building etc. complete as directed by the Engineer in charge.	Each	1.00	5444.00	979.92	6423.92	6423.92
210	Providing and fixing 6 to 32 amp DP MCB with enclosure 16 Amp., 240 V approved make on meter board with all accessories etc. complete as directed by the Engineer in charge.	Each	5.00	1457.00	262.26	1719.26	8596.30
220	Providing and fixing 100 W. LED ISI mark street light fittings with bracket etc. complete.	Each	3.00	8657.00	1558.26	10215.26	30645.78

Sl No.	Description of item	Unit	Qty.	Basic Rate	GST 18%	Rate Incl GST 18%	Amount
230	Providing and fixing plywood meter box for providing 7 nos of meters with its fuse box, main switch, kitkat, one no bus bar with 19mm plywood on back side and box of 300 mm depth and required size length and breadth suitable for provide at available space with T.W. shutters & frames with welded mesh and locking arrangement including painting with two coats for oil paint etc as directed by Engineer in charge.	Each	1.00	1800.00	324.00	2124.00	2124.00
						Total Rs.	283424.22

Note: Rates are inclusive of 18% GST & 1% labor insurance.


 (N. L. Namde)
 Executive Engineer ©
 EHV CCCM Division
 Latur

I/We ready to work/supply

In words _____

In figure _____ % Above/Below/At par with Schedule B.

Signature of Contractor