

- OFFICE OF THE -
EXECUTIVE ENGINEER (C)

EHV Civil Construction Cum Maintenance Division,
Maharashtra State Electricity Transmission Company Ltd.
Plot No.P21,132 KV S/Stn. Premises, MIDC,
Latur-413 531.
Tel. No. 02382 – 222373,
E mail :ee2730@mahatransco.in

No.: EEC/EHV/CCCM Dn./LTR/T/No. 248

Date:- 11.05.2022

E-Enquiry

Sub: Various civil maintenance works of subdivision office, Beed at 220kV Substation Beed.

Sealed and super scribed Item Rate quotations are invited for above work as per the Schedule 'B' attached so as to reach this office on or before 18.05.2022 up to 14.00 hrs. The Quotations will be opened on the same day if possible.

TERMS AND CONDITONS:

1. Work is to be done at **220kV Substation Beed, Dist:-Beed.**
2. The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

(a) Compulsory Primary Documents in 1st Envelop: (Technical Bid)

- Valid Certificate of Registration of appropriate class for Civil works from PWD/MES/ Railways/Jeevan Pradhikaran Etc Or From Any Govt./ Central Government and registered vendor of MSETCL.
- GST/ GSTIN Registration Certificate.
- Experience of having successfully completed similar civil works.
- Payment of EMD Rs. 5000.00 to be made by bidder off-line in cash only up to 14.00 hrs of 18.05.2022 in the office of EE(C), Dn, **Latur**. EMD Amount and MR No. should be super-scribed on the Envelope & having registered vendor of MSETCL.

(b) Documents in 2 Envelop: (Price Bid)

- Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE :- Envelop No.2 (Price Bid) will be opened after qualifying in Envelop No. 1 i.e. in Technical Bid.

3. Work is to be completed within 30 Days from the date of handing over of site. If it is not completed within this period, penalty will be charged at the rate of half percent per week, maximum up to 10% of work order amount.
4. Quantities mentioned in Schedule 'B' of e-enquiry are approximate and payment will be made on actual quantities of the work executed.
5. Payments will be made in first and final bill/ R. A. bills at the discretion of undersigned & as per the availability of funds.
6. Our rates are inclusive of GST. GST will be paid / deducted through / from your bills as applicable as per prevailing rate, rules and Act.
7. Work is to be carried out strictly as per the standard specification and as directed by the Engineer in charge.
8. In case of any dispute, the decision of the Executive Engineer (C), EHV CCCM Division, Latur will be final and binding on the contractor.
9. If any damages occur to the Company's property, during execution, contractor will have to make them good at his own cost.
10. In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL.
11. Income tax at prevailing rate as applicable on basic amount of bill will be recovered from your bill.
12. All terms and conditions as per the Company's rules including those in the booklet, Tender and contract for works are applicable in this case also.
13. Right to reject any or all quotations without assigning any reasons is reserved by the undersigned.
14. Lowest bidder will have to pay 5% S.D. on value of the work order in the form of F.D.R of scheduled or Nationalized Bank / Bank guarantee prior to starting of work.
15. Water charges @ 0.25% and energy charges @ 0.25% will be recovered from your bill wherever water / energy supplied departmentally.
16. No material will be supplied by MSETCL.
17. The material to be utilized should be used after getting approval from Engineer-in-charge.
18. Labour cess @ 1% of the value of work executed will be recovered through contractor's bill as per G.R. of Government.
19. You have to submit labour insurance amounting to 1% of work order amount before starting of work.

20. As per the rules of MSETCL, you will have to enter into an agreement with the company before starting of work on stamp paper of Rs. 500/- the cost of which will be borne by the agency.

21. All the compulsory documents are to be submitted while submitting bid, non-submission of any compulsory document will result in disqualification of bidder & no further correspondence will be made in this regards. Hence the bidder should ensure that all the required documents/information is enclosed properly while submitting the bid.



(N. L. Namde)
Executive Engineer (C)
EHV CCCM Division
Latur

Encl: Schedule 'B'

Copy s. w. r. to:-

The Superintending Engineer (C), EHV, CCCM Circle, Aurangabad.

Copy to:-

- 1) Addl. Executive Engineer (C), EHV CCCM S/Dn, **Beed**.
- 2) The Dy. Manager (F&A), EHV, CCCM Division, **Beed**.

Maharashtra State Electricity Transmission Co. Ltd.

EHV CCCM Division, MSETCL, Latur

Name of work: Various Civil Maintenance of Subdivision office Beed @ 220kV S/Stn Beed.

Schedule B

SR NO	ITEM OF WORK	QTY	RATE	Add GST 18%	Rate including GST	Unit	Amount
1	Removing grass, gazer grass and disposing off out of building premises including making clean the ground by showel and phavaras, etc. complete.	15.000	6.78	1.22	8.00	Square Metre	120.00
2	Providing and fixing high density polyethylen container of approved make one piece moulded water tank "SINTEX" made out of high density polyethylen and built corrugated inclusive of delivery upto destination housing, fixing of accessories such as inlet, outlet, overflow pipe inclusive of all Taxes. Capacity between 200 litres to 1000 litres. (For Ground Floor)	1000.000	12.71	2.29	15.00	Litre	15000.00
3	Providing and applying two coats of wall care putty on plastered surface and ceiling and walls to prepare surface even and smooth approved make etc complete. (For Ground Floor)	160.508	88.14	15.86	104.00	Square Metre	16692.83
4	Providing and applying priming coat on concrete / masonry / Asbestos Cement / plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matters and sand papering as required, etc. complete. (For Ground Floor)	160.508	34.75	6.25	41.00	Square Metre	6580.83
5	Providing and applying plastic emulsiton paint of "ASIAN PAINT" approved quality, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surface (excluding the primer coat), etc. complete. (For Ground Floor)	160.508	70.34	12.66	83.00	Square Metre	13322.16
6	Providing and applying washable oil bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces (excluding the primer coat), etc. complete. (For Ground Floor)	5.923	43.22	7.78	51.00	Square Metre	302.07
7	Providing and applying external raincoat painting "ASIAN PAINT" with crack filling acrylic polymer based chemical compound coating to the external surface of walls to prevent water seepage in the masonry walls during monsoon added with required shade Steiner to give required shade to the surface in two coats. Including providing three coat of priming of polymer base primer including preparing surface scrapping the existing loose old paint, removing loose particles of sand on the surface opening and cleaning the cracks developed in the external plaster, removing loose particles by chiseling, filling cracks by chemicals compound of approved make with proper penetration etc. Coating of Raincoat with the help of brush and as per instructions and specification given by manufacturer and with instruction from Engineer in-charge. Work shall be executed by certified applicator only and covering gurantee of 3 years on court stamp paper of Rs. 500/- and necessary testing, etc. complete. (For Ground Floor)	114.700	243.41	43.81	287.22	Square Metre	32944.13

8	Providing and fixing False ceiling of 12mm thick Laminated board with frame of M.S. angle 40x40x5mm and Tee of size 40x40x6mm at 60 cm/c including 12 mm dia. hangers, T.W. battens 50x25 mm and beading 25x15mm thick scaffolding if necessary, all Iron work etc. complete.	33.670	2259.37	406.69	2666.06	Square Metre	89766.24
9	Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24B.W.G.) for roofing without wind tiles including fastening with galvanised iron screw sand bolts, lead and bitumen washers as per drawing etc. complete. (Weight of 5.5 Kilogram/sq.m.).	105.000	824.16	148.35	972.51	Square Metre	102113.55
10	Providing JCB JS140/Tata Hitachi EX120 or equivalent on rental basis for cutting down humps and hillrocks within the formation of approach road to the towers locations including transportation and fuel cost etc. completed as directed by Engineer incharge.	2.000	1506.92	271.25	1778.17	One Hour	3556.34
11	Providing and fixing sheet glass of 24 oz. for all size including putty etc. complete	5.000	884.76	159.26	1044.02	Square Metre	5220.10
						Total=	285618.25

Note: Rates are inclusive of 18% GST & 1% labor insurance.



(N. L. Namde)
Executive Engineer ©
EHV CCCM Division
Latur

I/We ready to work/supply

In words _____

In figure _____ **% Above/Below/At par with Schedule B.**

Signature of Contractor