

ph

**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building, first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,

E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.:EEC/EHV/CCCM/Dn./ABD//Tech/

No 0 0 4 6 1

Date:-

13 MAY 2022

e- Quotation Enquiry

To,

.....
.....
.....

Sub: E-Quotation Enquiry for

- 1) Repair and Maintenance activities at RTC Waluj, MSETCL, Aurangabad &
- 2) Epoxy tile grout filling of Bath WC & Water cooler area at RTC Waluj, Aurangabad.

Dear Sir,

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or **before dated 23.05.2022 Time 11.30 Hrs.**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(30)** days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as required tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost. And it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost
- 9) The material should be got approved prior to fixing from the Engineer in-charge.

- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-I Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit 30,000.00 (5% of quotation value) as security deposit in cash or DD of any nationalized Bank within 10 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The Payment of EMD Rs.6,000.00/- to be made by bidder in cash upto 13:00 Hrs Dt.23.05.2022 in office of Executive Engineer (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. EMD Amount & MR No. Should be super-scribed on the Envelope & having registered vendor of MSETCL. else bid will be rejected.
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is Rs. **5,07,668.2**only. (Inclusive of all Taxes)
- 23) The Contractor has to submit the Civil Works Registration Certificate, GST Registration and PAN card at the time offer submission as mandatory documents.

Encl: Schedule 'B'

(S/d)
(J.P.Patil)
Executive Engineer (C)
EHV CCCM Division, Aurangabad

Copy S.W.R.S. to :

1. The Superintending Engineer (C). EHV CCCM Circle, Aurangabad

Copy to:

1. The Dy. Manager (F&A) EHV CCCM Division, Aurangabad
2. I.T Section Zone office Aurangabad-For Publishing on MSETCL Website.
3. Notice Board Division Office Aurangabad.

**- OFFICE OF THE -
EXECUTIVE ENGINEER (C)**

**EHV Civil Constn. Cum Maintenance Division,
Mahatransco Administration Building , first Floor,
wing no.102, Aurangabad, Ph. No. (0240) 2331429,
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646**



Name of Work: E-Quotation Enquiry for
1) Repair and Maintenance activities at RTC Waluj, MSETCL, Aurangabad &
2) Epoxy tile grout filling of Bath WC & Water cooler area at RTC Waluj, Aurangabad.

Estimated Amount: -Rs.5,07,668.2 (Inclusive of All Taxes)

(S/d)

Executive Engineer (C)
EHV CCCM Division, Aurangabad.

Quotation for Works

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/below/Estimated Rate (in Words) percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor

Full Address:

MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED

EHV CCCM SUB-DIVISION-II, AURANGABAD

ABSTRACT

Name of the work:- Repair and maintenance activities at RTC Waluj, MSETCL, Aurangabad.


As per SSR 2021-22


Sr.NO.	Activity NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	Add 18% GST	Rate with GST	AMOUNT
10	50013701	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	18.75	Sqm	42.42	7.64	50.06	938.63
20	50004085	Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete. a) Flooring	18.75	Sqm	1173.73	211.27	1385.00	25968.75
30	50004086	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete. b) Skirting	2.50	Sqm	1246.45	224.36	1470.81	3677.03
40	50004161	Rapairing of doors and chairs with all necessary fixing materials such as hinges, nuts, bolts, tower bolt, etc. Including removing & refixation, all material, labour and lead charges.	2.00	EA	800.93	144.17	945.10	1890.20
50	50012476	Providing and fixing C.P. 2 Way BIB cock with wall flange of approved make including necessary sockets/ union nut etc. complete as directed by Engineer in charge.	5.00	EA	2382.59	428.87	2811.46	14057.30
60	50018601	Providing and fixing Hand shower (health faucet) with 8mm dia. 1m long flexible tube having wall hook with approved make including necessary sockets/ union nut etc. complete as directed by Engineer in charge.	5.00	EA	1877.59	337.97	2215.56	11077.80
70	50007529	Providing and fixing C.P. BIB cock with wall flange of approved make including necessary sockets/ union nut etc. complete as directed by Engineer in charge.	5.00	EA	1704.88	306.88	2011.76	10058.80
80	50008249	Providing and fixing C.P. Angular stop cock with wall flange of approved make continental including necessary sockets/union nut etc. complete.	1.00	EA	2697.71	485.59	3183.30	3183.30
90	50013560	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.	3.00	EA	643.37	115.81	759.18	2277.54
100	50004125	Providing and fixing PVC flexible waste pipe 32 mm dia including necessary socket union nut, etc. complete.	5.00	EA	76.36	13.74	90.10	450.50
110	50012473	Providing and fixing 12 mm flexible inlet pipe connection including necessary socket union nut, etc. complete.	5.00	EA	415.72	74.83	490.55	2452.75
120	50004146	Providing and fixing C.P. pillar cock long neck with aerator of approed make including necessary sockets/union nut etc. complete.	1.00	EA	1763.26	317.39	2080.65	2080.65
130	50013613	Providing and fixing 10cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete.	12.00	EA	1115.04	200.71	1315.75	15789.00
140	50014199	Conveying of debris, excavated material like soft murum, boulders by any means including load- ing, unloading & spreading /stacking up to a lead of 300 to 500m Or as directed by Engr. in charge	5.00	Cum	157.86	28.41	186.27	931.35

Sr.NO.	Activity NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	Add 18% GST	Rate with GST	AMOUNT
150	50014016	Providing carpenter/plumber/welder services for completing all unforeseen work as directed by Engineer In-charge.	2.00	Mandays	647.41	116.53	763.94	1527.88
160	50000305	Providing unskilled labour for completing all unforeseen work as directed by Engineer In-charge.	2.00	Mandays	584.79	105.26	690.05	1380.10
170	50013235	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete	50.00	Sqm	272.02	48.96	320.98	16049.00
180	50014541	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface	850.00	Sqm	87.87	15.82	103.69	88136.50
190	50013345	Providing and applying priming coat on concrete/masonry/ Asbestos Cement plastered surfaces including	850.00	Sqm	34.34	6.18	40.52	34442.00
200	50013353	Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in two	850.00	Sqm	70.70	12.73	83.43	70915.50
210	50006001	Providing and fixing in position (as per 1868 / 1982) Aluminium sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 kg/Rmt. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 kg/Rmt.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Interlocking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineerincharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With colour Anodising without box	2.00	Sqm	5525.71	994.63	6520.34	13040.68
220	50013453	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.	3.00	Sqm	3138.07	564.85	3702.92	11108.76
230	50004079	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.	2.00	Sqm	2852.24	513.40	3365.64	6731.28
240	50013512	Providing and fixing mild steel grill work for windows, ventilators, etc. 15 kg/sqm as per drawing including fixtures necessary welding and painting with one coat of anticorrosive paint and two coats of oil painting complete.	7.00	Sqm	1522.07	273.97	1796.04	12572.28
250	50013601	Providing and fixing white glazed earthenware Wash Hand Basin of 45cm x 30cm size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete..	1.00	No.	5395.42	971.18	6366.60	6366.60


Sr.NO.	Activity NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	Add 18% GST	Rate with GST	AMOUNT
260	50016603	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black granite / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone with rounding / moulding the edges etc. complete . Both side polish	1.00	Sqm	4043.03	727.75	4770.78	4770.78
270	50013308	Providing 25 mm to 30 mm thick partition of polished black kadappa stone slab of approved quality including giving required size and shape etc. Fixing in cement mortar 1:3 curing and cement etc. complete. b) Both side polish	1.00	Sqm	1129.18	203.25	1332.43	1332.43
280	50013486	Providing and fixing in position extruded aluminium partitions having frame made out of extruded tubular section of size 65 mm x 40 mm with 12 mm thick three layered flat pressed teak wood particle board bonded with BWP type exterior grade phenol formaldehyde synthetic resin conforming to IS 129231990, laminated on both sides, Novateak or equivalent with aluminium glazing clips of size 12 mm x 12 mm (conical) as per drawing etc. complete.	4.00	Sqm	3430.97	617.57	4048.54	16194.16
290	50013485	Providing and fixing in position anodised extruded aluminum partitions, partly glazed and partly laminated having frame made out of extruded tubular section of size 40 mm x 60 mm with 12 mm thick three layered flat pressed teak wood particle board bonded with BWP type exterior grade phenol formaldehyde synthetic resin conforming to IS 128231990, laminated on both sides, Novateak or equivalent and 5 mm thick selected quality plain/ float glass panels fixed with aluminum glass clips 12 mm x 12 mm and rubber cushioning beading to glass partitions as per approved drawing etc. complete	1.00	Sqm	3117.87	561.22	3679.09	3679.09
300	50004125	Providing and fixing PVC flush tank of 10 litre including all necessary fittings, pipe connections, socket union nut, etc. complete.	6.00	EA	1841.03	331.39	2172.42	13034.52
310	50004125	Providing and fixing WC cover including all necessary fittings, pipe connections, socket union nut, etc. complete.	6.00	EA	289.87	52.18	342.05	2052.30
320	50006176	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	Rmt	248.46	44.72	293.18	1465.90
330	50006178	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	Rmt	339.36	61.08	400.44	2002.20
340	50006180	Providing and fixing on walls/ ceiling/ floor 40 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	Rmt	496.92	89.45	586.37	2931.85
350	50006190	Providing and fixing on walls/ ceiling/ floor 50 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	Rmt	689.83	124.17	814.00	4070.00
360	50013565	Providing and fixing screw down for 25 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	EA	792.85	142.71	935.56	935.56


Sr.NO.	Activity NO.	PARTICULARS OF ITEM	QTY	Unit	SSR rate	Add 18% GST	Rate with GST	AMOUNT
370	50013567	Providing and fixing screw down for 40 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	EA	1069.59	192.53	1262.12	1262.12
380	50013568	Providing and fixing screw down for 50 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	EA	1815.98	326.88	2142.86	2142.86
Total in Rs.								412977.95
Add 3.00% contingencies								12389.34
Total in Rs.								425367.29
Add 2.00% centages								8507.35
Total in Rs.								433874.63
Say								433875.00


Assistant Engineer (C)
EHV CCCM S/Dn.-II, Aurangabad


Addl. Executive Engineer (C)
EHV CCCM S/Dn.-II, Aurangabad


Assistant Auditor
EHV C.C.C.M. Dn
M.S.E.T.Co.Ltd., A'Bad


Dy. Mgr. (F&A)
EHV C.C.C.M. Dn., A'bao


Executive Engineer (C)
EHV C.C.C.M. Division
MSETCO. Ltd. Aurangabad - 4

MAHARASHTRA STATE ELECTRICITY COMPANY LIMITED
EHV CCCM SUB-DIVISION-II, AURANGABAD

ABSTRACT

Name of the work:- Epoxy tile grout filling of Bath, WC & Water cooler area at RTC Waluj, Aurangabad.

Sr.NO.	Activity NO.	PARTICULARS OF ITEM	QTY	Unit	Rate	Add 18% GST	Rate with GST	AMOUNT
10		Providing & fixing epoxy tile grout filling in tile gaps of Bath, WC, water cooler area of RTC main building along with all labours, materials, nahani trap filling as directed with all leads, lifts etc. complete. <i>14 No. Bath, WC & cooler area corner</i>	14.00	EA	2592.33	466.62	3058.95	42825.30
20		Providing & fixing epoxy tile grout filling in tile gaps of Bath, WC, water cooler area of trainee residential building along with all labours, materials nahani trap filling as directed with all leads, lifts etc. complete. <i>12 No Bath WC floor joints</i>	12.00	EA	3662.78	659.30	4322.08	51864.96
Total in Rs.								94690.26
Add 3.00% contingencies								2840.71
Total in Rs.								97530.97
Add 2.00% centages								1950.62
Total in Rs.								99481.59
Say								99482.00

[Signature]

Assistant Engineer (C)
EHV CCCM S/Dn.-II, Aurangabad

[Signature]
Assistant Auditor
EHV C.C.C.M. Dn.
M.S.E.T.Co.Ltd., A'Bad

[Signature]
Dy. Mgr. (F&A)
EHV C.C.C.M. Dn., A'bad

[Signature]

Addl. Executive Engineer (C)
EHV CCCM S/Dn.-II, Aurangabad

[Signature]
Executive Engineer (C)
EHV C.C.C.M. Division
MSETCo. Ltd. Aurangabad